# **SITE PLAN PROJECT FINISHES / SPECIFICATION**

### SITE WORKS

### CONCRETE

GREY CONCRETE - BROOM SWEPT (LIGHT). CONFIRM EXTENT OF SURROUNDING PATHS WITH CIVIL DRAWINGS & SITE PLANS

# **PLUMBING FIXTURES & DRAINAGE**

### FIXTURES

HOSE COCKS - BRASS HOSECOCK WITH DUEL CHECK VALVE

300 x 300 GALV STEEL GRATE TO ALL DOWNPIPES. SCREW FIXED

PROVIDE 90dia SLEAVED SLOTTED AGG DRAIN BEHIND RETAINING

### **BLOCKWORK / LINING/ CLADDING**

190mm GREY BLOCKWORK - PAINT FINISH. (ALLOW TWO COLOURS).

BLOCKWORK TO FIELD SIDE TO BE LEFT FLUSH JOINTED

# STEEL WORK

ALL EXPOSED STEELWORK TO BE AS PER STRUCTURAL ENGINEERING DETAILS. ALL EXPOSED STEEL (COLUMNS, BEAMS ETC) TO BE HOT DIP GALV FINISH (UNLESS NOTED OTHERWISE)

### **ELECTRICAL**

### GENERAL

REFER TO ELECTRICAL DRAWINGS / SPECIFICATION

### **DOORS & WINDOW**

REFER TO CHAIN MESH DETAILS

### **PAINTING**

### GENERAL

PAINT SYSTEM PROVIDE STAINS PRIMERS SEALERS & LINDERCOATS WHICH ARE SUITABLE FOR THE SUBSTRATE AND RE COMPATIBLE WITH THE FINISH COAT AND EACH OTHER. ALL PAINTED SURFACES TO HAVE TWO COATS, PROVIDE DULUX OR APPROVED EOUAL.

### BLOCKWORK

GRIND WALL BLOCKWORK TO SMOOTH EDGES.

1 COAT PRIMER
2 COATS DULUX WEATHERSHIELD (TWO COLOURS)

# STRUCTURAL STEEL

HOT DIP GALV FINISH

PROVIDE SIKA SIKALASTIC 1K (OR APPROVED EQUAL) TO EXPOSED BLOCKS WALLS AND BACKED FILLED AREAS REQUIRING TANKING / WATERPROOFING.

# FIELD KERBING

a) PAINT TOP, FACE & BASE OF CHANNEL OF KERBS TO TURF EDGE AND SIMILAR TO KERB STORMWATER GULLY PITS WITH IOTUN IOTACOTE 605 TWO PACK EPOXY COATING

b) APPLY A TOP COAT OF FLEXIBITHANE TO ABOVE AREAS NOTED

### BLOCK WALLS TO FIELD

BLOCKWORK TO BE LEFT FLUSH IOINTED

CLEAN BLOCKWORK FACE AND RUBBED WITH A CONCRETE RUBBING

ANY IMPERFECTIONS TO BE FILLED WITH ACRAPATCH (WITH ADDED

PRIME WITH 1 COAT DULUX ACRATEX GREEN RENDER PRIMER (OR APPROVED EQUAL)

ONCE PRIMED - OVERCOATE WITH 2 COATS DULUX ACRASHIELD. SPRAVED THAN BACK ROLLED WITH TICK NAP ROLLER. (OR APPROVED

ALL TURF SURROUND FENCING POSTS, RAILS, FITTINGS & GATES TO BE PAINTED AS PER SPEC PRIOR TO ERRECTION ON SITE, ONLY MINOR TOUCH UP OF PAINT WORK AFTER ERECTION

# **GENERAL**

PROVIDE TREDSAFE (OR APPROVED EQUAL) AA125 STAIR NOSING WITH SELECTED COLOUR INSERT. TO COMPLY WITH AS1428.1

### TACTILE INDICATORS

PROVIDE TACTILE SYSTEMS AUSTRALIA (OR APPROVED EQUAL) STAINLESS STEEL WITH POLYHRETHANE INFILL TACTILE INDICATORS WDSP-13S-TSA (COLOUR TO BE CONFIRMED)

### ARTIFICAL GRASS

PROVIDE ARTIFICIAL TURF FIELD TURF AUSTRALIA SUMMER PRESTIGE 40mm. FIX IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS

# SIGNAGE

PROVIDE 2No. PROJECT SIGNAGE (ONE ON WATER STREET, ONE ON MASON STREET) APPROX 3.0m WIDE x 2m HIGH. CONTRACTOR TO SUBMIT SIGN WRITTING PROOF FOR APPROVAL PRIOR TO MANUFACTURING SIGN TO BE

# **FENCING - NEW FIELD**

### GENERAL.

PROVIDE CHAINWIRE (PVC COATED) FENCE. REFER

### GALVANIZED COATINGS

ALL FERROIS MATERIALS SHALL HAVE COATINGS OF ZINC COMPLY WITH AS1650. THE COATING FOR WIRE SHALL BE TYPE A (HEAVY GALVANIZED)

ALL WIRE SHALL BE MANUFACTURES FROM STEEL HAVING A TENSILE STRENGTH NOT LESS THAN 370MPa NOR MORE THAN 550MPA. PVC

ALL CLAMPS, PIPE FITTINGS, HINGES, BOLTS, NUTS AND ANY OTHER METAL PARTS SHALL BE MANUE FROM PLAIN CARBON STEEL OR

# ALL FOOTINGS TO BE READY MIX CONCRETE 20MPa TO BE USED. REFER TO STRUCTURAL ENGINEERING DETAILS

STEEL TUBES ALL TUBES TO COMPLY WITH AS1074

RAILS SHALL BE STRAIGHT AND FREE FROM JOINTS, SIZE TO BE 40mm NB UNLESS NOTED OTHERWISE. MEDIUM GALV BOTTOM RAIL LOCATION TO BE MAXIMUM 50mm ABOVE TOP OF KERB OR TOP OF EXTERNAL WALL.

GATES SHALL BE FABRICATED OUT OF 30NB PIPE FOR POSTS & RAILS AND

POST SHALL BE MEDIUM GALV & STRAIGHT AND FREE FROM IOINTS, SIZE

### BRACING STAYS

BRACING STAYS SHALL BE PROVIDED WITHOUT JOINTS AND SHALL BE 40mm NOMINAL BORE MEDIUM

CHAIN WIRE TO BE MANUF. FROM 3.15 DIA WIRE FOR HEAVY GALV CHAIN WIRE TO FORM A UNIFORM 50mm MESH. CHAIN WIRE WHERE NOTED TO HAVE BARBED SELVEDGE TOP AND KNIICKLED SELVEDGE BOTTOM, PVC COATED THROUGHOUT. GREEN FINISH THROUGHOUT FOR EXTERNAL FENCE AND FIELD SURROUND FENCE TO BE KNUCKLED SELVEDGE TOP &

2 SUPPORT CABLE SHALL BE 4mm SPIRAL TENSION CABLE FOR EXTERNAL

### LACING AND TIE WIRE

LACING AND TIE WIRE SHALL BE 2 00mm DIA WIRE THE FOLLOWING IS

MINIMUM STANDARD REQUIRED

a. GATES - ALL DIAMONDS LACED RAILS AND RESTS

b. POSTS - TIES AT 300mm CENTRES

c. TOP & BOTTOM RAILS - TOTALLY LACED EACH DIAMOND

### d. ALL OTHER SUPPORT CABLES - CLIPS OR TIE WIRE AT 500mm INTERVALS.

### NYLON NETS

NYLON NETTING SPEC

1. 60ply 45mm UV TREATED BLACK NYLON NETTING COMPLETE WITH 10mm OVERLOCKED ROPED EDGES ALL ROUND FOR EACH REQUIRED

2. FIXING ON NETTING TO FIELD SIDE. PROVIDE 3off SUPPORT CABLES INTERNALLY ARE 6mm STAINLESS STEEL COMPLETE WITH HYDRAULIC SWAG AND THIMBLES. EYES & TURN BUCKLES

3. MAIN SUPPORT POST AND RAILS STRUCTURE ARE GALV PIPE PAINTED BLACK AS PER ENGINEERING DESIGN 4. FIXING OF NETTING TO 6mm SUPPORT CABLES ARE 6mm STAINLESS

5. FIXING OF NETTING TO POST AND RAILS ARE BY 'P' CLIPS OR 6mm WIDE STAINLESS CABLE TIES AT 500mm CENTERS

### FENCING EXISTING FIELD

STEEL SNAP HOOKS AT 1m CENTRES

SUPPLY ADDITIONAL POSTS, RAILS, GATES & GALV CHAINWIRE AS PER DETAILED DRAWINGS.

# LOCK SCHEDULES

MASTER KEY SYSTEM TO ALL DOORS / GATES. HARDWARE SPEC BY

### PROJECT

KALKA SHADES REDEVELOPMENT

### FUNDING

AUSTRALIAN GOVERNMENT (+LOGO) QUEENSLAND GOVERNMENT (+LOGO)
ROCKHAMPTON REGIONAL COUNCIL (+LOGO) ROCKHAMPTON HOCKEY ASSOCIATION (+LOGO)

### HEAD CONTRACTOR

TBC (+ CONTACT NUMBER)

# LEAD CONSULTANTS

CIVIL - CALIBRE GROUP BUILDING DESIGNER - DEZIGN ELEMENTS STRUCTURAL - IS2

ELECTRICAL - ANDERSON CONSULTANTS BUILDING HYDRAULICS - CALIBRE GROUP

FIELD IRRIGATION - HYDROPLAN





# **ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS**

These plans are approved subject to the current conditions of approval associated with **Development Permit No.: D/51-2018** 

**Dated: 26 June 2018** 

FENCES / FENCE POSTS / SUPPORTS	FENCES / FENCE POSTS / SUPPORTS				
INTERNAL FENCES TO FIELD	BLACK				
NYLON FENCE TO FIELD	BLACK				
EXTERNAL COMPOUND CHAIN WIRE FENCE NEW FIELD	GREEN				
FENCE TO EXISTING FIELD	REUSE EXISTING GALV CHAIN WIRE				
BLOCK WORK					
BLOCKWORK TO INTERNAL PATHS	NATURAL FINISH. SMOOTH SURFACE				
EXTERNAL BLOCKWORK TO COMPOUND	WATERPROOFED. PAINTED TO MATCH COLORBOND 'MANGROVE'				
BLOCKWORK TO FIELD (EG BEHIND GOALS)	PAINT TO MATCH COLORBOND 'GULLY' (REFER PAINTING SPEC'S)				
GENERAL					
STAIR NOSING	YELLOW				
TACTILES	STAINLESS STEEL WITH YELLOW INSERTS				
HANDRAILS	HOT DIPPED GALV FINISH. NO PAINT.				
FIELD KERBING	GREY				

**COLOUR SCHEDULE - SITE PLAN** 

DO NOT SCALE DRAWING					
ALL DIMENSION IN MILLIMETERS					
No: Description: Date:					
Α	PRELIM TENDER	10.05.18	<b>~</b>		
В	TENDER ISSUE	14.05.18	ž		
			2		
			REVISIONS		
			뿞		
1		l			

THESE DRAWINGS, CONCEPTS & DESIGNS ARE COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT PERMISSION FROM DEZIGN ELEMENTS. DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE ACCURACY, COMPLEXNESS OF ELECTRONICALLY

### **LEGEND**

COLUMN

DP	DOWN PIPE
SK	SINK
ST	STEP
DF	DRINK FOUNTAIN
НС	HOSE COCK
FI	FIELD INLET
DB	DISTRIBUTION BOARD
COMM	COMMUNICATION CABINI
AC	AIR CONDITIONER
FR	FRIDGE
LB	LOUVRE BLOCK
NB	NOMINAL BORE
GALV	GALVANIZED
MH	MAN HOLE
AH	ACCESS HATCH



ISSUED FOR

# FOR TENDER

Project Details:
SITE PLANS
RRC & RHA
KALKA SHADES REDEVELOPMENT

Drawing Title:


ORCC No. 1247120



SITE PLAN - PROJECT

**SPECIFICATIONS** 

QBCC NO. 1247 120		DDAG	140. 0001	011
Scale:	As indicated		Rev:	
Date:	MAR 2018		В	AM 1
Drawn:	NJB			:06:24
Proje	ect No:	Drawii	ng No:	25/2018 7:06:2
18	004	S-(	01	14/05/





THE DIMENSION IN MILEUMETERS				
No:	No: Description:			
A PRELIM TENDER		10.05.18	١,	
В	B TENDER ISSUE		1 2	
			1 2	
			1	
			] ¦	
			ן '	
			1	

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLENSES OF ELECTRONICALLY
TRANSFERRED DOCUMENTS



ISSUED FOR

# **FOR TENDER**

Project Details:

SITE PLANS

RRC & RHA

KALKA SHADES REDEVELOPMENT

Drawing Title:

**EXISTING OVERALL SITE PLAN** 



QBCC No: 1247120 BDAQ No: 0001677

Scale:	1:1000		Rev:		
Date:	MAR 2018		В	AM.	
Drawn:	NJB			:06:25	
Proje	ect No:	Drawii	ng No:	4/05/2018 7:06:25 AM	
18	_004	S-(	02	14/05/	

# **ROCKHAMPTON REGIONAL COUNCIL**

These plans are approved subject to the current conditions of approval associated with

**Development Permit No.: D/51-2018** 

**Dated: 26 June 2018** 





ALL DIMENSION IN MILLIMETERS					
No:	Description:	Date:			
Α	PRELIM TENDER	10.05.18	~		
В	TENDER ISSUE	14.05.18	REVISIONS		
			2		
			≅		
			뿠		
			_		

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLENSES OF ELECTRONICALLY
TRANSFERRED DOCUMENTS



# ISSUED FOR **FOR TENDER**

Project Details: SITE PLANS

RRC & RHA KALKA SHADES REDEVELOPMENT

Drawing Title:


OVERALL SITE PLAN




QBCC No: 1247120 BDAQ No: 0001677 Scale: 1:1000

Date: MAR 2018 В Drawn: NJB Project No: Drawing No: 18\_004 S-03







ALL DIMENSION IN MILLIMETERS				
No:	Date:			
Α	PRELIM TENDER	10.05.18	,,	
В	TENDER ISSUE	14.05.18	SEVISIONS	
			2	
			5	
			Ä	
			_	

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLEXNESS OF ELECTONICALLY
TRANSFERRED DOCUMENTS



ISSUED FOR

# FOR TENDER

Project Details:

SITE PLANS

RRC & RHA

KALKA SHADES REDEVELOPMENT

Drawing Title:


**EXISTING SITE PLAN** 




0407 271 336 M

QBCC No: 1247120 BDAQ No: 0001677

GDCC N	). 124/120	DDAG	140. 000 11	<i>31 1</i>
Scale:	1:500		Rev:	
Date:	MAR 2018		В	AM:
Drawn:	NJB			7:06:26
Proje	ect No:	Drawii	ng No:	/05/2018 7
18	004	S-(	04	14/05/





THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPPRIGHTED AND THE PROPERTY OF DEZIGN BLEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN BLEMENTS.
DEZIGN BLEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLEXNESS OF BLETRONICALLY
TRANSFERRED DOCUMENTS



# ISSUED FOR

# **FOR TENDER**

Project Details:

SITE PLANS

RRC & RHA

KALKA SHADES REDEVELOPMENT

Drawing Title:


PROPOSED SITE PLAN




info@dezignelements.com.au

QBCC No: 1247120 BDAQ No: 0001677

Scale:	As indicated		Rev:		
Date:	MAR 2018		В	AM	
Drawn:	NJB			7:06:27	
Proje	ect No:	Drawii	ng No:	2018 7	
18	_004	S-(	05	14/05/	





ALL DIMENSION IN MILLIMETERS				
No:	Description:	Date:		
Α	PRELIM TENDER	10.05.18	۸,	
В	TENDER ISSUE	14.05.18	REVISIONS	
			≌	
			뿠	
			-	

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLEXNESS OF ELECTRONICALLY
TRANSFERRED DOCUMENTS



# ISSUED FOR

FOR TENDER

Project Details:

SITE PLANS RRC & RHA

KALKA SHADES REDEVELOPMENT

Drawing Title:

EXISTING LEVEL PLAN



0407 271 336

info@dezignelements.com.au

QBCC No: 1247120		BDAQ	No: 0001	677	
Scale:	1:250		Rev:		
Date:	MAR 2018		В	AM 8	
Drawn:	NJB			7:06:28	
Proje	ect No:	Drawii	ng No:	14/05/2018 7	
18	_004	S-(	06	14/05/	



DO NOT SCALE DRAWING ALL DIMENSION IN MILLIMETERS PRELIM TENDER 10.05.18 TENDER ISSUE

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLENSES OF ELECTRONICALLY
TRANSFERRED DOCUMENTS

# **ROCKHAMP TON REGIONAL COUNCIL APPROVED PLANS**

These plans are approved subject to the current conditions of approval associated with

**Development Permit No.: D/51-2018** 



ISSUED FOR

# FOR TENDER

Project Details: SITE PLANS RRC & RHA KALKA SHADES REDEVELOPMENT

Drawing Title:


PROPOSED PART SITE PLAN




0407 271 336 M

QBCC No: 1247120 BDAQ No: 0001677







THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT ON RESPONSIBLY FOR THE
ACCURACY, COMPLEXNESS OF ELECTRONICALLY
TRANSFERRED DOCUMENTS.



ISSUED FOR

FOR TENDER

Project Details:

SITE PLANS

RRC & RHA

KALKA SHADES REDEVELOPMENT



**SECTIONS & DETAILS** 


0407 271 336 M info@dezignelements.com.au E

 QBCC No: 1247120
 BDAQ No: 0001677

 Scale:
 As indicated
 Rev:

 Date:
 MAR 2018
 D
 ₹

Jeane.	715 marcacca		11.01.		
Date:	MAR 2018		В	Ā	
Drawn:	NJB			7:06:31	
Proje	ect No:	Drawii	ng No:	2018 7	
18	_004	S-(	08	14/05/	





THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLEXNESS OF ELECTRONICALLY
TRANSFERRED DOCUMENTS



ISSUED FOR

# **FOR TENDER**

Project Details:

SITE PLANS

RRC & RHA

KALKA SHADES REDEVELOPMENT

wing Title:


PROPOSED PART SITE PLAN 1



0407 271 336 M dezignelements.com.au E

QBCC No: 1247120 BDAQ No: 0001677

Scale:	As indicated		Rev:		
Date:	MAR 2018		В	AM	
Drawn:	NJB			90:33	
Project No:		Drawii	ng No:	14/05/2018 7:06:33 AM	
18	_004	S-(	09	14/05/	



EQUAL ANGLE BASE PLATE. CHAMFER ALL EDGES. HOT DIP GALV

**HANDRAIL FIXING DETAIL (TYPE 2)** 

HANDRAIL - TYPE 2

REFER TO FIXING DETAIL

DO NOT SCALE DRAWING ALL DIMENSION IN MILLIMETERS PRELIM TENDER 10.05.18 TENDER ISSUE 14.05.18

THESE DRAWINGS, CONCEPTS & DESIGNS ARE
COPYRIGHTED AND THE PROPERTY OF DEZIGN ELEMENTS
AND NOT TO BE USED FOR ANY OTHER REASON WITHOUT
PERMISSION FROM DEZIGN ELEMENTS.
DEZIGN ELEMENTS ACCEPT NO RESPONSIBLY FOR THE
ACCURACY, COMPLENSES OF ELECTRONICALLY
TRANSFERRED DOCUMENTS



ISSUED FOR

# FOR TENDER

Project Details: SITE PLANS RRC & RHA KALKA SHADES REDEVELOPMENT Drawing Title:



dezignelements
BUILDING DESIGNERS

0407 271 336 M

QBCC No: 1247120 BDAQ No: 0001677 Scale: As indicated Date: MAR 2018 В Drawn: NJB Project No: Drawing No: 18\_004 S-10



**APPROVED PLANS** 

These plans are approved subject to the

current conditions of approval associated with

**Development Permit No.: D/51-2018** 

**Dated: 26 June 2018** 





Geotechnical Investigation
Proposed Hockey Field
Kalka Shades, North Rockhampton

Prepared for Calibre Consulting Pty Ltd Project No. R18-107A

26 April 2018

# ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with

**Development Permit No.: D/51-2018** 

**Dated: 26 June 2018** 



Butler Partners (Regional) Pty Ltd ABN 43 603 849 305 246 Kent Street Rockhampton Qld 4700 PO Box 1400 Rockhampton Qld 4700

Ph: 61 7 **4927 1400** Fx: 61 7 4927 1800 enquiries@butlerpartners.com.au

Proposed Hockey Field Kalka Shades, North Rockhampton Project No.: R18-107A 26 April 2018

# **TABLE OF CONTENTS**

SECTION 1 - INTRODUCT	ON		3
1.1			
1.2		ope of Work	
1.3		1	
SECTION 2 - THE SITE			
2.1		on	
2.2			
3.1		ampling Methods	
3.2	Bore Location	ns and Supervision	5
<b>SECTION 4 - INVESTIGAT</b>	ION RESULTS		6
4.1	Reports		6
4.2	Subsurface C	Conditions	6
4.3	Groundwater		6
4.4	Laboratory Te	esting	6
		on and Sediment Control Parameters	
	4.4.2 Partic	ele Size Distribution	7
		city	
	4.4.4 Shrin	k-Swell Index	7
	4.4.5 Comp	paction Properties	8
	4.4.6 Califo	rnia Bearing Ratio	8
SECTION 5 - GEOTECHNI	CAL DESIGN DIS	CUSSION	9
5.1			
5.2	Earthworks		9
		ng Fill	
	5.2.2 Site F	Preparation	9
		/atability	
		orary Batter Stability	
		ompaction	
		cability	-
5.3			
5.4		lls	
5.5		y and Shrink-Swell Movements	
		ated Magnitude	
		n Considerations	
5.6			
		and Strip Footings.	
		l Piles	
	5.6.3.		
	5.6.3.		
	5.6.3.		
5.7		lab and Pavement Subgrade Properties	

Important Information about your Geotechnical Engineering Report (2 pages)







TABLES:	
Table 1: Groundwater Observations	ε
Table 2: Summary of Reported Emerson Class, pH and Conductivity Test Results	7
Table 3: Summary of Reported Particle Size Distribution Test Results	7
Table 4: Summary of Reported Plasticity Test Results	7
Table 5: Summary of Shrink-Swell Test Results	7
Table 6: Summary of Moisture-Density Relationship Results	ε
Table 7: Summary of California Bearing Ratio Test Results	ε
Table 8: Maximum Temporary Unprotected Dry Cut Batter Slopes to 2m to 3m Depth	10
Table 9: Minimum Compaction Requirements	
Table 10: Retaining Wall Design Parameters	11
Table 11: Maximum Working Stress Design Parameters for Pad and Strip Footings	14
Table 12: Estimated Settlement Modulus and Poisson's Ratio Values	14
Table 13: Maximum Working Bearing Pressures for Bored Cast-Insitu Piles	15
Table 14: Soil Parameters for Calculation of Lateral Load Capacity of Piles	
Table 15: Preliminary Subgrade Design Values	16
ATTACHMENTS:	
Drawing No. 1 Locality Plan and Test Locations	
Appendix A Bore Report Sheets with Explanatory Notes	
Appendix B Laboratory Test Result Reports	

Copyright 2018 © Butler Partners 2018

This publication is subject to copyright. Except as permitted under the Copyright Act 1968, no part of it may in any form or by any means (electronic, mechanical, photocopying, recording or otherwise) be reproduced, stored in a retrieval system or transmitted without prior written permission. Enquiries should be addressed to the publishers.

BUTLER PARTNERS (REGIONAL) PTY LTD

www.butlerpartners.com.au



# **SECTION 1 - INTRODUCTION**

### 1.1 Project

It is understood that the construction of a new hockey field and associated infrastructure is proposed at Kalka Shades, North Rockhampton. The proposed development is understood to comprise a new synthetic turf hockey field to the north-east of the existing hockey field, a single-storey clubhouse, two lighting towers and an access road adjacent to Frenchman's Creek.

The location and extent of the site are shown approximately on Drawing No. 1, attached.

### 1.2 Proposed Scope of Work

Based on prior knowledge of the general area, the subsurface conditions at the site were anticipated to generally comprise surface layers of fill, underlain by alluvial clay/sand mixtures, potentially underlain by weathered rock. Shallow groundwater was not envisaged.

For the scope of the proposed development it was requested by Calibre Consulting Pty Ltd (Calibre) to undertake geotechnical investigation of the site by drilling and sampling four bores to 4m to 6m depth (or prior refusal) at Calibre nominated locations. An additional two shallow bores were requested for bulk sampling of the proposed subgrade; one along the proposed access road and one within the proposed hockey field.

Using the results of the proposed fieldwork and laboratory testing outcomes, it was proposed that a report would be produced to provide geotechnical design information on each of the following topics, as appropriate:

- · subsurface conditions;
- · site preparation and earthworks;
- excavatability;
- erosion and sediment control parameters;
- · retaining wall design parameters;
- · reactive soil movement,
- · site trafficability after disturbance;

- · stability criteria for open excavation;
- groundwater observations:
- suitable alternative foundation types;
- work bearing pressures;
- · pavement and slab subgrade properties; and
- · anticipated construction aspects.

# 1.3 Commission

Based on the nominated scope of investigation work, a fee to undertake geotechnical investigation of the site was presented in a proposal on 2 February 2018. Butler Partners (Regional) Pty Ltd (Butler Partners) was subsequently commissioned by Calibre to conduct the investigation as proposed.



# **SECTION 2 - THE SITE**

# 2.1 Site Description

At the time of the investigation, the development area was part of the existing Kalka Shades sporting field complex, comprising five grass cricket fields and one existing turf hockey field and clubhouse at the western side of the site. Frenchman's Creek runs adjacent to the western side of the field, from the north to the south east. An existing grandstand structure and a storage shed were situated adjacent to the north-eastern boundary of the site. Vegetation generally comprised well-kept grass with isolated patches of bare earth and small to medium sized trees and shrubs scattered around the edges of the site.

Ground surface levels across the development area sloped very gently downward to the south, from a high of approximately RL7.5m at the northern end, to a low of approximately RL6.5m at the southern end. A relatively recent aerial photograph of the site is presented in Photograph 1, with the approximate site boundary outlined in red.



Photograph 1: Aerial view of the site taken on 26 October 2017 (Nearmap image)

# 2.2 Geology

Reference to the Geological Survey of Queensland's 1:100,000 series Rockhampton Sheet indicates that the site is mapped in an area of Quaternary Fitzroy flood plain alluvium (comprising silt, clay, sand and gravel).



# **SECTION 3 - FIELDWORK**

### 3.1 Drilling and Sampling Methods

The investigation comprised the drilling and sampling of four bores (Bores 1 to 4) to between 4.45m and 5.90m depth, with a 4wd-mounted Drill Man GT10, using solid flight auger drilling techniques. Strata identification was based on inspection of the materials recovered on the augers, supplemented by the inspection of 'disturbed' Standard Penetration Test (SPT) samples and 'undisturbed' 50mm diameter tube samples. Hand 'pocket' penetrometer readings were taken in the ends of the undisturbed tube samples in cohesive strata to assist with the assessment of soil strength.

Two additional 'shallow' bores were drilled to recover bulk samples of proposed subgrade material along the proposed access road and within the new hockey field for laboratory testing of soaked CBR.

On completion of drilling, the bores were backfilled with drill spoil and surface plugged.

### 3.2 Bore Locations and Supervision

Bore locations were set-out from co-ordinates provided by Calibre using a hand-held GPS unit and their approximate locations are shown on Drawing No. 1 attached. The ground surface level at each bore location was interpolated from survey information provided by Calibre on an unreferenced plan, received on 3 April 2018.

An experienced geotechnical engineer set out the bore locations, logged the stratigraphy encountered in the bores, directed the insitu sampling and testing program and supervised the field work.



# **SECTION 4 - INVESTIGATION RESULTS**

# 4.1 Reports

The subsurface conditions encountered at the bore locations are given on the Bore Report sheets included in Appendix A, using classification and descriptive terms defined in the accompanying notes. Laboratory test result report sheets are included in Appendix B.

### 4.2 Subsurface Conditions

For a description of the stratigraphy encountered at each bore, the Bore Report sheets should be consulted. However, in broad summary, the subsurface conditions encountered in the bores generally comprised surface layers of silty clay fill to between 0.5m and 0.9m depth, underlain by firm to very stiff gravelly/sandy/silty clay. In Bore 4, a layer of medium dense clayey/sandy gravel was encountered in the clays between 1.4m and 3.6m depth.

'Strength inversions' (i.e. 'weak' material underlying 'stronger' material) were encountered in three bores. For example, in Bore 1, very stiff sandy silty clay was underlain at 4m depth by stiff sandy silty clay; in Bore 2, very stiff silty clay was underlain at 2m depth by stiff sandy clay; and in Bore 3, very stiff gravelly clay was underlain at 3m by stiff silty clay.

### 4.3 Groundwater

Free groundwater was encountered in all bores during drilling at the depths/reduced levels indicated in Table 1.

Table 1: Groundwater Observations

<b>可以为外的主义</b> 的关系。		Groundwater Observations		
Bore	Date	Depth (m)	Reduced Level (m)	
1		3.4	RL3.6	
2	0 March 2049	1.8	RL5.1	
3	9 March 2018	2.7	RL4.5	
4		1.6	RL5.9	

Groundwater levels would be expected to be affected by seasonal and prevailing weather conditions. If construction is to be undertaken at a significant time following this investigation and/or following significant 'wet' weather, it would be prudent to confirm groundwater levels.

### 4.4 Laboratory Testing

Selected samples recovered from the bores were submitted to Butler Partners' NATA accredited Rockhampton geotechnical testing laboratory for assessment of erosion and sediment control parameters, particle size distribution, plasticity, shrink-swell index and soaked CBR. The test results are summarised and discussed in the following sections.

It should be noted that sample descriptions provided in the laboratory results summary tables (and the laboratory test result sheets) are based on the inspection of each individual laboratory test sample only. No allowance has been made in sample descriptions for sampling, sub-sampling or test methodology in determination of the mass material properties. Estimates of mass material properties are provided on each individual Bore Report sheet and as such, the laboratory test results should be read in conjunction with the relevant Bore Report sheets.



# 4.4.1 Erosion and Sediment Control Parameters

Two samples of fill and one sample of silty clay were tested to determine the Emerson Class Number, pH and electrical conductivity and a summary of the reported test results is presented in Table 2. The Emerson Class Number results indicate that the samples tested had a low potential for dispersion, <u>using distilled water</u>.

Table 2: Summary of Reported Emerson Class, pH and Conductivity Test Results

Bore	Depth (m)	Sample Description	Emerson Class No.	рН	Electrical Conductivity (mS/cm)
CBR 2	0.2 - 0.6	Fill - Silty Clay	4	6.0	0.14
3	0.5 - 0.95	Silty Clay	4	7.7	0.22
4	0.5 - 0.95	Fill - Silty Clay	4	5.0	0.29

### 4.4.2 Particle Size Distribution

Two selected samples of soil and one sample of fill were tested for measurement of particle size distribution using wash sieve grading techniques and the reported results are summarised in Table 3.

Table 3: Summary of Reported Particle Size Distribution Test Results

Bore	Depth (m)	Sample Description	Sample Moisture Content (%)	Gravel Fraction <sup>(1)</sup> (%)	Sand Fraction <sup>(2)</sup> (%)	Silt and Clay Fraction <sup>(3)</sup> (%)
CBR 2	0.2 - 0.6	Fill - Silty Clay	21.4	1	18	81
1	4.0 - 4.45	Sandy Clay	23.4	3	45	52
4	1.5 - 1.95	Clayey Sandy Gravel	9.4	43	30	27

<sup>(1)</sup> Particle size <60mm, >2mm; (2) Particle size (approximately) <2mm, >0.075mm; (3) Particle size (approximately) <0.075mm

## 4.4.3 Plasticity

One selected sample of soil and one sample of fill were tested for measurement of plasticity using Atterberg limit and linear shrinkage test methods. The reported test results are summarised in Table 4, together with the soil classification and indicate that the samples tested were of high plasticity.

Table 4: Summary of Reported Plasticity Test Results

Bore	Depth (m)	Sample Description	Sample Moisture Content (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Linear Shrinkage (%)	Classification <sup>(1)</sup>
CBR 2	0.2 - 0.6	Fill - Silty Clay	21.4	53	16	37	14.0	СН
3	0.5 - 0.95	Silty Clay	21.8	52	15	37	13.0	СН

<sup>(1)</sup> Australian Standard AS1726-1993, Geotechnical site investigations

### 4.4.4 Shrink-Swell Index

Two undisturbed samples of clay soil were tested to assess shrink-swell index (I<sub>ss</sub>) using the methods given in Australian Standard AS1289.7.1.1 – 1992. The reported test results are presented in Table 5, and indicate the sample tested showed potential for moderate to high shrink-swell movements associated with moisture content/suction variation.

Table 5: Summary of Shrink-Swell Test Results

Bore	Depth (m)	Sample Description	Sample Moisture Content (%)	Shrinkage (%)	Swell (%)	lss (% per pF)
2	1.5 – 1.9	Silty Clay	18.7	4.0	2.9	3.0
3	1.5 – 1.7	Gravelly Clay	18.7	3.0	2.3	2.3



# 4.4.5 Compaction Properties

Two selected bulk samples recovered were tested to determine (Standard) laboratory moisture-density relationship and the maximum dry density (MDD) and optimum moisture content (OMC) results for the samples tested are summarised in Table 6. The results of the moisture-density testing indicates that the (insitu) moisture contents of the samples tested were between approximately 2.2% and 2.4% 'wet' of Standard OMC, at the time of sampling.

Table 6: Summary of Moisture-Density Relationship Results

			Contral	Standard Compaction		
Bore	Depth (m)	Sample Description	Sample Moisture Content (%)	Maximum Dry Density (t/m³)	Optimum Moisture Content (%)	
CBR 1	0.1 - 0.5	Gravelly Silty Clay	23.2	1.62	21.0	
CBR 2	0.2 - 0.6	Fill - Silty Clay	21.4	1.59	19.0	

# 4.4.6 California Bearing Ratio

Two bulk samples recovered were tested for measurement of soaked CBR using the test method given in Australian Standard AS1289.6.1.1 - 1998. The samples were recompacted using Standard compactive effort at approximately OMC, then soaked under a surcharge loading of 4.5kg for four days. A summary of the reported results is presented in Table 7.

Table 7: Summary of California Bearing Ratio Test Results

		Sai		Sample P	reparation		
Bore	Depth (m)	Sample Description	Moisture Content (%)	Dry Density (t/m³)	Moisture Content (%)	Swell (%)	CBR (%)
CBR 1	0.1 - 0.5	Gravelly Silty Clay	23.2	1.54	21.2	4.0	6
CBR 2	0.2 - 0.6	Fill - Silty Clay	21.4	1.51	19.4	2.0	6



# **SECTION 5 - GEOTECHNICAL DESIGN DISCUSSION**

### 5.1 Ground Model

The results of the investigation indicated that the ground conditions (at the bore locations) generally comprised layers of silty clay fill to between 0.5m and 0.9m depth, underlain by gravelly/sandy/silty clay. A layer of clayey/sandy gravel was encountered between 1.4m and 3.6m depth in one bore. Strength inversions with depth were encountered in three bores. In these ground conditions, geotechnical design will need to consider (at least) the following key issues:

- subsurface conditions;
- variations in ground conditions across the site and with depth;
- presence of strength inversions;
- presence, uniformity and placement of existing fill;
- earthworks and site preparation;
- excavatability;
- erosion and sediment control parameters;
- site trafficability after disturbance of the site;
- reactive soil movement;
- stability criteria for open excavation;
- retaining wall design parameters;
- suitable alternative foundation types;
- working bearing pressures;
- pavement and slab subgrade properties; and
- anticipated construction aspects.

Discussion of geotechnical design parameters, as well as design and construction recommendations and suggestions are detailed in the following sections.

# 5.2 Earthworks

# 5.2.1 Existing Fill

Where existing fill is present along the site, supporting documentation should be obtained and checked to confirm that the fill has been placed in a controlled manner to a specification that is appropriate for the proposed development. If documentation does not exist (or the specification used for filling is not appropriate for the proposed development) then it is suggested that the existing fill be assumed to be 'uncontrolled'.

To minimise the risk of potentially adverse settlement due to poorly compacted zones or inclusions of deleterious material occurring, it is recommended that all uncontrolled fill present in settlement sensitive areas be removed and replaced/recompacted with controlled fill of low 'reactivity', unless settlement sensitive elements of the development can be supported on suitable material located below the fill.

# 5.2.2 Site Preparation

Site preparation in areas of future settlement sensitivity should involve removal of any existing uncontrolled fill, unsuitable materials, vegetation, topsoils and any trees or large shrubs (if present), as far in advance of construction as possible (refer Section 5.5)



Following site stripping (and excavation, as required), the exposed subgrade in areas to be developed should be uniformly compacted to the relevant (Standard) dry density ratio indicated in Table 8. 'Soft spots' could be expected in the subgrade, which should be either tyned, dried then recompacted, or excavated and replaced with compacted select fill. It is anticipated that use of a coarse granular fill ('bridging') layer may be required in the base of soft-spot excavations to provide a relatively solid base to compact over. Placement of the bridging layer and all soft spot excavations should be conducted under the supervision of an experienced engineer.

Care will be required to ensure that the effect of site earthworks does not impact adversely upon adjacent services and structures etc. (e.g. as potential settlements induced by vibratory compaction, etc.). It is also recommended that dilapidation surveys of adjacent structures and services (if applicable), etc. be undertaken prior to construction commencing on site.

# 5.2.3 Excavatability

Bulk and confined excavation of the fill and soils encountered in the bores should be readily removed using a large hydraulic excavator.

All confined excavations into which personnel entry is envisaged should be fully supported or battered/benched to a stable angle to ensure personnel safety.

# 5.2.4 Temporary Batter Stability

Stable (cut) batter angles will need to be properly assessed once earthworks design and procedures have been finalised. As a <u>preliminary</u> guide, the slope batter angles given in Table 8 are suggested for dry, <u>unsurcharged</u> batters, up to 2m to 3m in height, <u>where some movement behind batter crests is acceptable and the slopes are dewatered</u>.

Table 8: Maximum Temporary Unprotected Dry Cut Batter Slopes to 2m to 3m Depth

Material	Strength	Temporary Batter <sup>(1)</sup>
Existing Fill		1V:3H (highly variable) <sup>(2)</sup>
Gravelly/Sandy/Silty Clays	firm stiff very stiff	1V:2.5H <sup>(2)</sup> 1V:1.5H <sup>(2)</sup> 1V:1H <sup>(2)</sup>
Sandy/Clayey Gravels	medium dense	1V:2H <sup>(2)</sup>

<sup>(1)</sup> Not underlain by 'softer' materials and subject to confirmation by engineering analysis and inspection during construction

The batter angles given in Table 8 are based on the assumption that batter faces are protected from erosion and that drainage is designed to keep surface and groundwater away from the slopes. If free water is allowed to emanate from batter faces, slopes are likely to be unstable at the nominated batter slopes.

If insufficient space exists for the construction of cut batters at the slopes given in Table 8, or potential uncontrolled crest movement cannot be accepted, the excavation sides will need to be supported in order to prevent instability/control movement.

### 5.2.5 Fill Compaction

Any fill required to support structure loads and/or movement sensitive on-ground slabs etc., should be 'controlled', i.e. placed in layers having a loose thickness of not more than 250mm and uniformly compacted to the relevant (Standard) dry density ratio nominated in Table 9. Use of reactive fill should be avoided.

<sup>(2)</sup> Flatter if 'wet'



Table 9: Minimum Compaction Requirements

Description	Minimum Dry Density Ratio
General Fill (non-structural support)	95% (Standard compaction)
Pavements - >500mm below subgrade level - top 500mm of subgrade	98% (Standard compaction) 100% (Standard compaction)

To assist with the achievement of adequate control over fill placement, geotechnical testing as set out in Section 8 of Australian Standard AS3798 – 2007 *Guidelines on earthworks for commercial and residential developments* would be required. It is recommended that any earthworks in areas where future settlement control is required (and for all fill required to support floor slabs, foundations, etc.) should be undertaken under 'Level 1' geotechnical supervision and testing.

# 5.2.6 Trafficability

It is anticipated that site trafficability for rubber tyred plant will be difficult to impossible in 'wet' conditions and consideration should be given to placement of a coarse (free draining) granular working surface to enable trafficing of any sections of the site requiring all weather access. The required layer thickness will depend on the type of plant proposed to traffic the site and should be determined on a case-by-case basis. However, a layer thickness of approximately 0.15m is anticipated for 'light' equipment.

# 5.3 Site Drainage

During construction, the site should be graded such that water is readily shed and does not collect and pond over the site, otherwise softening of the subgrade will occur, especially under trafficing of construction plant and heavy vehicles.

### 5.4 Retaining Walls

An estimate of 'unsurcharged' retaining wall pressures can be obtained for 'flexible' and 'rigid' walls (up to 2m to 3m high) under drained conditions, retaining horizontal material, by using a triangular pressure distribution in conjunction with the parameters given in Table 9.

Table 10: Retaining Wall Design Parameters

Material Type	Strength/Density	Total Weight (t/m³)	Flexible Wall 'Active' Pressure Coefficient (ka)	Rigid Wall 'At Rest' Pressure Coefficient (k <sub>o</sub> )
Sandy/Silty Clay	firm to very stiff	1.9	0.40	0.60
Clayey/Sandy Gravel	medium dense	2.0	0.30	0.50

Due allowance must be included in wall design for groundwater pressure, back fill compaction, surcharge effects from adjacent structures and/or construction loading, the effects of sloping retained materials, reactive soil/fill pressures etc. Even if a drainage system is installed behind retaining walls, consideration should be given to the potential for water pressures to act on the wall as elevated groundwater levels may occur during or following prolonged 'wet' weather, or from blocked drainage etc. Drain design should incorporate free draining backfill and slotted pipe discharging into a sealed disposal system.



# 5.5 Soil Reactivity and Shrink-Swell Movements

# 5.5.1 Estimated Magnitude

The magnitude of potential reactive soil movements can be estimated using the following equation (from Australian Standard AS2870-2011 *Residential slabs and footings*), and parameters for the subject site selected based on recommendations in AS2870, results of the laboratory testing and published information:

$$y_s = \frac{1}{100} \sum_{n=1}^{N} \left( \alpha . I_{ss} . \overline{\Delta u} . h \right)_n$$

where y<sub>s</sub> is the characteristic surface movement, in millimetres;

 $\alpha$  is the lateral restraint factor;

I<sub>ss</sub> is the shrink-swell index (taken as approximately 2.5% per pF to 3.0% per pF for the site clays, based on shrink-swell laboratory test results and past experience);

 $\overline{\Delta u}$  is the soil suction change averaged over the thickness of the layer under consideration (estimated as 1.2pF in Rockhampton);

h is the thickness of layer under consideration, in millimetres; and

N is the number of soil/fill layers within the depth of suction change (2.3m in Rockhampton).

Based on a shrink-swell index range of 2.5% per pF to 3.0% per pF for the site clays, the potential characteristic surface movement values for the natural site soils (with all uncontrolled fill removed) have been calculated to be approximately 41mm to 49mm using the methods and parameters discussed above, assuming <u>normal seasonal moisture/suction variations</u>. Notwithstanding the magnitude of the calculated characteristic surface movement value, the site would be classified as Class 'P' because of the presence of the existing site fill; however, if all uncontrolled fill is removed, the site could be re-classified as Class 'H1' (Highly Reactive).

### 5.5.2 Design Considerations

The characteristic surface movement values presented above are based on normal seasonal moisture/suction variations. If trees and large shrubs are subsequently planted close to the development, significantly greater movements than those nominated above may occur due to an increased soil suction magnitude and depth. Consideration should be given to constructing root barriers around trees in order to minimise future potential soil drying or footing damage by roots from trees (if any), which may be present close to buildings.

Use of reactive materials for fill should be avoided. However, if their use cannot be avoided then the calculated characteristic surface movement value would increase significantly. It should be carefully noted that the calculated surface movement values given above <u>do not</u> include any allowance for 'abnormal' influences such as vegetation effects. It is strongly recommended that the estimated characteristic surface movement values given above for the site be recalculated once site earthworks design is completed.

It is considered that the following issues must be carefully considered in design:

Where controlled fill is placed over a natural soil subgrade, higher characteristic movements than those
nominated above could potentially occur (as the ratio of lateral restrained to unrestrained movement
will increase), particularly if the fill reactivity is greater than that of the existing site soils. If filling of the
site is proposed, a revised site classification should be considered, which takes into account the actual
reactivity, compaction and depth of fill used.



- Vegetation (particularly large trees) has the potential to significantly increase soil suction change magnitude and depth (Δu and Hs respectively in the equation above), which leads to a significant increase in potential reactive soil movements adjacent to any existing (or proposed) tree locations. If trees are to be planted 'close' to proposed buildings/structures in the future, consideration should be given to constructing root barriers around the trees, and footing design must allow for potentially (significantly) higher reactive soil movements than are nominated above.
- Abnormal subgrade moisture variations could potentially result in adverse, non-uniform reactive
  movements that are significantly greater than those nominated above for 'normal' seasonal moisture
  changes. The risk of 'abnormal' movement occurring could be reduced by ensuring over-watering of
  gardens, ponding water, broken/leaking pipes, 'close' planting of trees/shrubs, etc. does not occur.
- Significantly increased differential reactive movements could occur across proposed buildings/structures, if the subgrade partly comprises natural soils and controlled fill.

'Good practice' should be adopted in project design and detailing if control of reactive ground movement is desired. In particular, the following are recommended:

- trees/shrubs should not be planted closer than 1.5 times their mature height to movement sensitive features (unless significantly greater reactive movements than those estimated above are designed for);
- subgrade moisture content should not be allowed to change during or following construction;
- site grades should be designed to readily shed water and prevent ponding around footings and other movement sensitive areas;
- services should be designed to be flexible and to prevent any leakage and to rapidly promote removal
  of fluid if leakage does occur; and
- proposed buildings/structures should be made as flexible as possible, with regular full height movement control joints, flexible in-fill above windows and doors etc.

# 5.6 Foundations

Suitable foundations for proposed buildings (e.g. clubhouse), lighting towers, retaining walls, etc. will be dependent upon structural loadings, tolerance of buildings/structures to movement (including settlements under structural loads and shrink-swell movements), type and magnitude of loads, etc.

To minimise the risk of unacceptable differential movements, it is recommended that all foundations for individual structures be supported in similar quality materials (e.g. footings should not found partly in 'firm' clays and partly in 'stiff' clays, unless potential differential settlements can be tolerated or designed for).

It is considered that local variations in soil strength (and depth) will occur over the site and it is suggested that a 'flexible' approach be adopted to the foundation design, construction methodology and costing, so that footing sizes/founding depths can be readily adjusted as required during construction, without cost/time penalties being incurred.

An experienced geotechnical engineer should inspect all foundation excavations prior to casting to ensure bearing capacity at foundation level is adequate and to confirm final foundation dimensions. All foundation excavations should be clean, dry and free of loose/softened materials immediately prior to casting.



# 5.6.1 Pad and Strip Footings

Maximum allowable working bearing pressures for pad or strip footings are given in Table 11; ultimate values can be determined by multiplying the working stress values by 2.5.

Table 11: Maximum Working Stress Design Parameters for Pad and Strip Footings

Material	Strength	Maximum Working Bearing Capacity <sup>(1)</sup> (kPa)
Existing Fill	-	not recommended
	firm	50 (not recommended)
Gravelly/Sandy/Silty Clay	stiff	100
	very stiff	150
Clayey/Sandy Gravel	medium dense	100(2)

<sup>(1)</sup> No underlying 'softer' material

### 5.6.2 Raft

It is considered that the stiff to very stiff clays and medium dense clayey/sandy gravels encountered in the bores may be suitable to support a raft foundation, subject to the required working bearing pressure, and the distribution of structural load over the site. If any 'soft spots' or firm/loose layers are encountered at raft subgrade level, they will probably require excavation and replacement with Level 1 controlled select fill; geotechnical assessment would be required to confirm the uniformity of the soils at raft founding level and the extent/depth of any 'soft' areas.

For the preliminary assessment of raft performance, the parameters presented in Table 12 could be used, which have been based on the results of this investigation, past experience and published correlations; the Table 12 parameters do not include allowance for reactive ground movement. Detailed analysis will be required to confirm that a raft option is feasible for proposed structures, which must also include allowance for reactive ground movement.

Table 12: Estimated Settlement Modulus and Poisson's Ratio Values

Material	Strength	Settlement Modulus (E) (MPa)	Poissons Ratio (v)	
Existing Fill	-	1 – 8		
	firm	4 – 10		
Gravelly/Sandy/Silty Clay	stiff	8 – 20	0.25	
, , , , , , , , , , , , , , , , , , ,	very stiff	15 – 40		
Clayey/Sandy Gravel	medium dense	20 – 50		

# 5.6.3 Bored Piles

### 5.6.3.1 Vertical Loading

If bored pile foundations are required to provide support for structures, the effect of group action should be considered where piles are to act in groups, and an overall foundation capacity of less than the sum of individual pile capacities could result where piles are closely spaced.

Based on the ground conditions encountered in the bores (i.e. clay/gravel soils and shallow groundwater), it is considered that bored pile construction could be difficult and provision should be allowed in timing/pricing for the use of temporary steel liners, temporary dewatering and tremmie placement of concrete for bored piles. If use of bored piles is envisaged it would be considered prudent to undertake full size trial bored pile excavations prior to final adoption to confirm constructability and likely final design bearing stresses.

Preliminary only - subject to footing dimensions, depth and groundwater level



Maximum allowable working pressure values for bored pile design are given in Table 13 for 'dry' construction. Ultimate failure values can be determined by multiplying the working stress values by 2.5.

Table 13: Maximum Working Bearing Pressures for Bored Cast-Insitu Piles

Founding Material	Strength	Maximum Allowable Working Bearing Pressure (kPa			
rounding Material	Strength	Shaft	Base <sup>(1)</sup>		
Existing Fill	-	not recommended	not recommended		
	firm	5	not recommended		
Gravelly/Sandy/Silty Clay	stiff	10	150		
	very stiff	15	200		
Clayey/Sandy Gravel	medium dense	10	150		

Minimum embedment of four times pile diameter into founding materials and no underlying 'softer' material

The design of piles and ground beams must allow for potential uplift due to reactive soils, if moisture content/suction change is possible in reactive founding materials. Even if moisture change is effectively prevented, some movement will occur in controlled reactive clays during moisture content equilibration.

# 5.6.3.2 Lateral Loading

Broms¹ method of calculating lateral capacity of piles could be used to assess the lateral resistance capacity for single piles. The lateral resistance capacity from the fill encountered in the bores should be neglected unless the fill is controlled. The soil parameters presented in Table 14 could be used with this method.

Table 14: Soil Parameters for Calculation of Lateral Load Capacity of Piles

Material	Strength	Undrained Cohesion (C <sub>u</sub> )	Angle of Shearing Resistance (φ)	Total Bulk Density	Passive Earth Pressure Coefficient (Kp)
Existing Fill	•	Unreliable	Unreliable	19kN/m³	unreliable
Silty/Sandy/Gravelly Clay	firm stiff very stiff	35kPa 50kPa 100kPa		19kN/m³ 20kN/m³ 20kN/m³	2.0 2.1 2.2
Clayey/Sandy Gravel	medium dense	-	32°	21kN/m³	3.0

A material factor of 0.4 applied to the shear strength (calculated using the undrained cohesion and angle of internal friction values nominated in Table 14 for the 'natural' soils) is suggested for assessment of design lateral capacity of piles. Extreme care should be exercised with the use of any uncontrolled fill in the calculation of vertical and/or lateral capacity of foundations (it is strongly suggested that the fill not be considered unless it was placed under Level 1 control to an acceptable specification).

# 5.6.3.3 Uplift Capacity

Assessment of the uplift capacity of single pile foundations could be based on the lesser of the following:

- 75% of the shaft adhesion values presented in Table 13 (ignoring the fill material), or
- A 'cone of uplift' with a cone apex angle of 45° and adopting a buoyant unit weight of 8kN/m³.

It will be necessary to carefully consider the spacing and size of pile groups as the uplift capacity of a group of 'closely' spaced piles would be expected to be less than the sum of the individual pile capacities.

<sup>&</sup>lt;sup>1</sup> Broms, B Lateral Resistance of Piles in Cohesive Soils, *Journal of the Soil Mechanics Division*, American Society of Civil Engineers, Vol. 90, No. SM2, Vol 90, 1964, pp.27-63



# 5.7 On-Ground Slab and Pavement Subgrade Properties

Subgrade properties are expected to vary across the site following earthworks, and detailed assessment/testing will be required at the time of construction in order to confirm design values. For the purposes of the initial costing and preliminary design of on-ground slabs and pavements, cast over a natural soil or controlled fill subgrade, could be carried out using the preliminary subgrade parameters presented in Table 15, provided that the subgrade is prepared in accordance with Section 5.2.2.

Table 15: Preliminary Subgrade Design Values

Subgrade Type	CBR (%)	Modulus of Subgrade Reaction <sup>(1)</sup> (kPa/mm)
Silty Clay (natural or controlled fill)	2-6	20 – 40
Sandy/Gravelly Clay (natural or controlled fill)	3 – 8	25 – 45
Clayey/Sandy Gravel	10 – 20	55 – 70

<sup>(1)</sup> For transient loading only – sustained loads may cause consolidation settlement and appropriate design values must be determined by analysis

If reactive ground movement can occur, it is suggested that on-ground slabs be fully dowelled (and joints between slabs sealed to control differential movements and minimise under-slab moisture changes) and should be detailed to enable movement, independent of foundations, fixtures, etc.

# **BUTLER PARTNERS (REGIONAL) PTY LTD**

JENNY SALAS
Geotechnical Engineer

Reviewed by: BRUCE BUTLER Senior Principal

NICK BLOXSOM
Senior Geotechnical Engineer

# **Important Information about Your**

# Geotechnical Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

# Geotechnical Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical engineering study conducted for a civil engineer may not fulfill the needs of a construction contractor or even another civil engineer. Because each geotechnical engineering study is unique, each geotechnical engineering report is unique, prepared *solely* for the client. No one except you should rely on your geotechnical engineering report without first conferring with the geotechnical engineer who prepared it. *And no one* — *not even you* — should apply the report for any purpose or project except the one originally contemplated.

# **Read the Full Report**

Serious problems have occurred because those relying on a geotechnical engineering report did not read it all. Do not rely on an executive summary. Do not read selected elements only.

# A Geotechnical Engineering Report Is Based on A Unique Set of Project-Specific Factors

Geotechnical engineers consider a number of unique, project-specific factors when establishing the scope of a study. Typical factors include: the client's goals, objectives, and risk management preferences; the general nature of the structure involved, its size, and configuration; the location of the structure on the site; and other planned or existing site improvements, such as access roads, parking lots, and underground utilities. Unless the geotechnical engineer who conducted the study specifically indicates otherwise, do not rely on a geotechnical engineering report that was:

- · not prepared for you,
- not prepared for your project,
- not prepared for the specific site explored, or
- completed before important project changes were made.

Typical changes that can erode the reliability of an existing geotechnical engineering report include those that affect:

 the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light industrial plant to a refrigerated warehouse,

- elevation, configuration, location, orientation, or weight of the proposed structure,
- · composition of the design team, or
- project ownership.

As a general rule, always inform your geotechnical engineer of project changes—even minor ones—and request an assessment of their impact. Geotechnical engineers cannot accept responsibility or liability for problems that occur because their reports do not consider developments of which they were not informed.

# **Subsurface Conditions Can Change**

A geotechnical engineering report is based on conditions that existed at the time the study was performed. *Do not rely on a geotechnical engineering report* whose adequacy may have been affected by: the passage of time; by man-made events, such as construction on or adjacent to the site; or by natural events, such as floods, earthquakes, or groundwater fluctuations. *Always* contact the geotechnical engineer before applying the report to determine if it is still reliable. A minor amount of additional testing or analysis could prevent major problems.

# Most Geotechnical Findings Are Professional Opinions

Site exploration identifies subsurface conditions only at those points where subsurface tests are conducted or samples are taken. Geotechnical engineers review field and laboratory data and then apply their professional judgment to render an opinion about subsurface conditions throughout the site. Actual subsurface conditions may differ—sometimes significantly—from those indicated in your report. Retaining the geotechnical engineer who developed your report to provide construction observation is the most effective method of managing the risks associated with unanticipated conditions.

# A Report's Recommendations Are *Not* Final

Do not overrely on the construction recommendations included in your report. *Those recommendations are not final*, because geotechnical engineers develop them principally from judgment and opinion. Geotechnical engineers can finalize their recommendations only by observing actual

subsurface conditions revealed during construction. The geotechnical engineer who developed your report cannot assume responsibility or liability for the report's recommendations if that engineer does not perform construction observation.

# A Geotechnical Engineering Report Is Subject to Misinterpretation

Other design team members' misinterpretation of geotechnical engineering reports has resulted in costly problems. Lower that risk by having your geotechnical engineer confer with appropriate members of the design team after submitting the report. Also retain your geotechnical engineer to review pertinent elements of the design team's plans and specifications. Contractors can also misinterpret a geotechnical engineering report. Reduce that risk by having your geotechnical engineer participate in prebid and preconstruction conferences, and by providing construction observation.

# Do Not Redraw the Engineer's Logs

Geotechnical engineers prepare final boring and testing logs based upon their interpretation of field logs and laboratory data. To prevent errors or omissions, the logs included in a geotechnical engineering report should never be redrawn for inclusion in architectural or other design drawings. Only photographic or electronic reproduction is acceptable, but recognize that separating logs from the report can elevate risk.

# Give Contractors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can make contractors liable for unanticipated subsurface conditions by limiting what they provide for bid preparation. To help prevent costly problems, give contractors the complete geotechnical engineering report, but preface it with a clearly written letter of transmittal. In that letter, advise contractors that the report was not prepared for purposes of bid development and that the report's accuracy is limited; encourage them to confer with the geotechnical engineer who prepared the report (a modest fee may be required) and/or to conduct additional study to obtain the specific types of information they need or prefer. A prebid conference can also be valuable. Be sure contractors have sufficient time to perform additional study. Only then might you be in a position to give contractors the best information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions.

# **Read Responsibility Provisions Closely**

Some clients, design professionals, and contractors do not recognize that geotechnical engineering is far less exact than other engineering disciplines. This lack of understanding has created unrealistic expectations that

have led to disappointments, claims, and disputes. To help reduce the risk of such outcomes, geotechnical engineers commonly include a variety of explanatory provisions in their reports. Sometimes labeled "limitations" many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely.* Ask questions. Your geotechnical engineer should respond fully and frankly.

# **Geoenvironmental Concerns Are Not Covered**

The equipment, techniques, and personnel used to perform a *geoenviron-mental* study differ significantly from those used to perform a *geotechnical* study. For that reason, a geotechnical engineering report does not usually relate any geoenvironmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated environmental problems have led to numerous project failures*. If you have not yet obtained your own geoenvironmental information, ask your geotechnical consultant for risk management guidance. *Do not rely on an environmental report prepared for someone else*.

# **Obtain Professional Assistance To Deal with Mold**

Diverse strategies can be applied during building design, construction, operation, and maintenance to prevent significant amounts of mold from growing on indoor surfaces. To be effective, all such strategies should be devised for the express purpose of mold prevention, integrated into a comprehensive plan, and executed with diligent oversight by a professional mold prevention consultant. Because just a small amount of water or moisture can lead to the development of severe mold infestations, a number of mold prevention strategies focus on keeping building surfaces dry. While groundwater, water infiltration, and similar issues may have been addressed as part of the geotechnical engineering study whose findings are conveyed in this report, the geotechnical engineer in charge of this project is not a mold prevention consultant; none of the services performed in connection with the geotechnical engineer's study were designed or conducted for the purpose of mold prevention. Proper implementation of the recommendations conveyed in this report will not of itself be sufficient to prevent mold from growing in or on the structure involved.

# Rely, on Your ASFE-Member Geotechncial Engineer for Additional Assistance

Membership in ASFE/The Best People on Earth exposes geotechnical engineers to a wide array of risk management techniques that can be of genuine benefit for everyone involved with a construction project. Confer with your ASFE-member geotechnical engineer for more information.



8811 Colesville Road/Suite G106, Silver Spring, MD 20910 Telephone: 301/565-2733 Facsimile: 301/589-2017 e-mail: info@asfe.org www.asfe.org

Copyright 2004 by ASFE, Inc. Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with ASFE's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of ASFE, and only for purposes of scholarly research or book review. Only members of ASFE may use this document as a complement to or as an element of a geotechnical engineering report. Any other firm, individual, or other entity that so uses this document without being an ASFE member could be committing negligent or intentional (fraudulent) misrepresentation.







Butler Partners (Regional) Pty Ltd
ABN 43 603 849 305
246 Kent Street
Rockhampton Qld 4700
PO Box 1400
Rockhampton Qld 4700

Ph: 61 7 **4927 1400** Fx: 61 7 4927 1800 enquiries@butlerpartners.com.au

# Site


# **Proposed Hockey Field** Kalka Shades, North Rockhampton

Locality Plan and Test Locations

Calibre Consulting Pty Ltd

SCALE AT A4:

DATE:	FEBRUARY 2018
DRAWN:	AD
APPROVED:	
PROJECT No:	R18-107A
DRAWING No:	1 REV: A



# **LEGEND**

Proposed Hockey Field Site

**CBR** California Bearing Ratio Test



# APPENDIX A BORE REPORT SHEETS WITH EXPLANATORY NOTES



Client: Calibre Consulting Pty Ltd Project: Proposed Hockey Field

Location: Kalka Shades, North Rockhampton

Project No: R18-107A

**BORE 1** 

Page No: 1 of 1

Date: 9 March 2018

Ground Surface Level: RL7.0m\*

Depth (m)	Description	RL (m)	Lithology	Sample Type	Sample Depth (m)	Test Results
0-	FILL	7.0				3,000,000
_	- silty clay, dark brown					
-				S	0.5	4,6,9
1_	SILTY CLAY (CH)	6.0-	##	5	0.95	N=15
-	- stiff, dark brown mottled pale brown, trace fine grained sand		##			
			##		1.5	460
-			##	S	1.95	4,6,8 N=14
2-		5.0-	H.H.		1.95	
+			##			
-			##			
3	SANDY CLAY (CI)	4.0-	HH	U	3.0	pp=380
7	- very stiff, brown, fine to coarse grained sand		111		3.3	pp=000
-			121			
4-	-stiff, grey mottled orange	3.0-			4.0	
	oul, grey meased startige		]].]]	S		2,5,6 N=11
+	End of Bore at 4.45 m				4.45	
5-		2.0-				
-		2.0	-			
			1			
-			-			
6-		1.0-	-			



D Disturbed Sample

B Bulk Sample

pp Pocket Penetrometer Test (kPa)

Standard Penetration Test (SPT)

**HB** SPT Hammer Bouncing

( ) No Sample Recovery

V Vane Shear Strength, Uncorrected (kPa)

E Environmental Sample

Up Pushtube Sample

C NMLC Coring

ample Is(50) Point Load Test Result (MPa)

(d) Diametral Test

(a) Axial Test

(i) Lump Test

Rig: 4WD Drill Man GT10

**Drilling Method:** Auger

Groundwater: Free groundwater encountered at 3.4m

Remarks: \*Approximate ground surface level interpolated from an unreferenced plan provided by Calibre Consulting Pty Ltd, recieved on 3 April 2018.



Client: Calibre Consulting Pty Ltd Project: Proposed Hockey Field

Location: Kalka Shades, North Rockhampton


Project No: R18-107A

**BORE 2** 

Page No: 1 of 1

Date: 8 March 2018

Ground Surface Level: RL6.9m\*



U Undisturbed Tube Sample (50mm dia)

D Disturbed Sample

B Bulk Sample pp Pocket Penetrometer Test (kPa) S Standard Penetration Test (SPT)

**HB** SPT Hammer Bouncing

( ) No Sample Recovery

V Vane Shear Strength, Uncorrected (kPa)

E Environmental Sample

Up Pushtube Sample C NMLC Coring

Is(50) Point Load Test Result (MPa)

(d) Diametral Test

(a) Axial Test

(i) Lump Test

Rig: 4WD Drill Man GT10

Drilling Method: Auger

Groundwater: Free groundwater encountered at 1.8m

Remarks: \*Approximate ground surface level interpolated from an unreferenced plan provided by Calibre Consulting Pty Ltd, recieved on 3 April 2018.



Client: Calibre Consulting Pty Ltd Project: Proposed Hockey Field

Location: Kalka Shades, North Rockhampton

Project No: R18-107A

**BORE 3** 

Page No: 1 of 1

Date: 9 March 2018

Ground Surface Level: RL7.2m\*

	Description	RL (m)	Lithology	Sample Type	Sample Depth (m)	Test Results
0—		7.2				
	FILL - silty clay, dark brown	-				
-	SILTY CLAY (CH) - firm, dark brown, trace fine grained sand		开 开 开	S	0.5	1,3,3 N=6
1-		6.0-	##		0.95	
+	GRAVELLY CLAY (CI) - very stiff, brown-orange, fine to medium grained gravel			U	1.5	pp=500
2-	- very suit, stown-orange, line to mediant grained graves					
		5.0-				
3	- coarse grained gravel				3.0	
-	SILTY CLAY (CI) - stiff, dark brown, with fine to medium grained gravel	4.0-	##	S	3.45	3,4,5 N=9
-			井井			
1-		3.0-	开开			
1			##	U	4.5	pp=220
5-	End of Bore at 4.8 m	2.0-			1.5	
		2.0-				
1			]			



D Disturbed Sample

B Bulk Sample

pp Pocket Penetrometer Test (kPa)

S Standard Penetration Test (SPT)

**HB** SPT Hammer Bouncing

( ) No Sample Recovery

V Vane Shear Strength, Uncorrected (kPa)

E Environmental Sample

Up Pushtube Sample

C NMLC Coring

Is(50) Point Load Test Result (MPa)

(d) Diametral Test

(a) Axial Test

(i) Lump Test

Rig: 4WD Drill Man GT10

Drilling Method: Auger

Groundwater: Free groundwater encountered at 2.7m

Remarks: \*Approximate ground surface level interpolated from an unreferenced plan provided by Calibre Consulting Pty Ltd, recieved on 3 April 2018.



Client: Calibre Consulting Pty Ltd Project: Proposed Hockey Field

Location: Kalka Shades, North Rockhampton

Project No: R18-107A

**BORE 4** 

Page No: 1 of 1
Date: 8 March 2018

Ground Surface Level: RL7.5m\*

nebm (m)	Description	RL (m)	Lithology	Sample Type	Sample Depth (m)	Test Results
0		7.5	********			
	FILL - silty clay, dark brown	7.0-		s	0.5	6,8,9 N=17
1-	SILTY CLAY (CI) - stiff, brown, with fine to medium grained sand				0.95	
2-	CLAYEY SANDY GRAVEL (GC) - medium dense, brown, fine to medium grained gravel, angular	6.0-		D S	1.4 1.5	6,10,10 N=20
-		5.0-				
3	SANDY GRAVEL (GC) - medium dense, brown, fine to medium grained gravel	4.0-		S	3.0	7,10,4 N=14
4-	SILTY CLAY (CI) - stiff, dark grey, with medium to coarse grained sand		##; ##; ##;	D	4.0	
-		3.0-	## ##	s	4.5	3,4,4 N=8
5	- pale brown, trace fine grained sand	2.0-	开开 开开 开开			
-		-	H.H.	U	5.6	pp=180
6	End of Bore at 5.9 m		TALES A		5.9	

U Undisturbed Tube Sample (50mm dia)

D Disturbed Sample

B Bulk Sample pp Pocket Penetrometer Test (kPa) S Standard Penetration Test (SPT)

**HB** SPT Hammer Bouncing

( ) No Sample Recovery

V Vane Shear Strength, Uncorrected (kPa)

E Environmental Sample

Up Pushtube Sample C NMLC Coring

Is(50) Point Load Test Result (MPa)

(d) Diametral Test

(a) Axial Test

(i) Lump Test

Rig: 4WD Drill Man GT10

**Drilling Method: Auger** 

Groundwater: Free groundwater encountered at 1.6m

Remarks: \*Approximate ground surface level interpolated from an unreferenced plan provided by Calibre Consulting Pty Ltd, recieved on 3 April 2018.



# Notes on Description and Classification of Soil

The methods of description and classification of soils used in this report are generally based on Australian Standard AS1726-1993 Geotechnical Site Investigations.

Soil description is based on an assessment of disturbed samples, as recovered from bores and excavations, or from undisturbed materials as seen in excavations and exposures or in undisturbed samples. Descriptions given on report sheets are an interpretation of the conditions encountered at the time of investigation.

In the case of cone or piezocone penetrometer tests, actual soil samples are not recovered and soil description is inferred based on published correlations, past experience and comparison with bore and/or test pit data (if available).

Soil classification is based on the particle size distribution of the soil and the plasticity of the portion of the material finer than 0.425mm. The description of particle size distribution and plasticity is based on the results of visual field estimation, laboratory testing or both. When assessed in the field, the properties of the soil are estimated; precise description will always require laboratory testing to define soil properties.

Where soil can be clearly identified as FILL this will be noted as the main soil type followed by a description of the composition of the fill (e.g. FILL – yellow-brown, fine to coarse grained gravelly clay fill with concrete rubble). If the soil is assessed as possibly being fill this will be noted as an additional observation.

Soils are generally described using the following sequence of terms. In certain instances, not all of the terms will be included in the soil description.

### MAIN SOIL TYPE (CLASSIFICATION GROUP SYMBOL)

- strength/density, colour, structure/grain size, secondary and minor components, additional observations


Information on the definition of descriptive and classification terms follows.

### SOIL TYPE and CLASSIFICATION GROUP SYMBOLS

	Major Divisions	Particle Size	Classification Group Symbol	Typical Names
COARSE GRAINED SOILS (more than half of material is larger than 0.075 mm)	BOULDERS	> 200mm		
	COBBLES	63 – 200mm		
	GRAVELS (more than half of coarse fraction is larger than 2.36mm)	Coarse: 20 – 63mm Medium: 6 – 20mm Fine: 2.36 – 6mm	GW	Well graded gravels, gravel-sand mixtures little or no fines.
			GP	Poorly graded gravels and gravel-sand mixtures, little or no fines, uniform gravels.
			GM	Silty gravels, gravel-sand-silt mixtures.
			GC	Clayey gravels, gravel-sand-clay mixtures.
	SANDS (more than half of coarse fraction is smaller than 2.36mm)	Coarse: 0.6 – 2.36mm Medium: 0.2 – 0.6mm Fine: 0.075 – 0.2mm	sw	Well graded sands, gravelly sands, little or no fines.
			SP	Poorly graded sands and gravelly sands; little or no fines, uniform sands.
			SM	Silty sands, sand-silt mixtures.
			SC	Clayey sands, sand-clay mixtures.
FINE GRAINED SOILS (more than half of material is smaller than 0.075 mm)	SILTS & CLAYS (liquid limit <50%)		ML	Inorganic silts and very fine sands, silty/clayey fine sands or clayey silts with low plasticity.
			CL and CI	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays.
			OL	Organic silts and organic silty clays of low plasticity.
	SILTS & CLAYS (liquid limit >50%)		мн	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils.
			СН	Inorganic clays of high plasticity.
			ОН	Organic clays of medium to high plasticity, organic silts.
	HIGHLY ORGANIC SOILS		Pt	Peat and other highly organic soils.



#### PLASTICITY CHART FOR CLASSIFICATION OF FINE GRAINED SOILS



(Reference: Australian Standard AS1726-1993 Geotechnical site investigations)

#### **DESCRIPTIVE TERMS FOR MATERIAL PROPORTIONS**

	Coarse Grained Soils	Fine Grained Soils			
% Fines	Modifier	% Coarse	Modifier		
< 5	Omit, or use 'trace'	< 15	Omit, or use trace.		
5 – 12	Describe as 'with clay/silt' as applicable.	15 – 30	Describe as 'with sand/gravel' as applicable.		
> 12	Prefix soil as 'silty/clayey' as applicable	> 30	Prefix soil as 'sandy/gravelly' as applicable.		

#### STRENGTH TERMS - COHESIVE SOILS

Strength Term	Undrained Shear Strength	Field Guide to Strength
Very soft	< 12kPa	Exudes between the fingers when squeezed in hand.
Soft	12 – 25kPa	Can be moulded by light finger pressure.
Firm	25 – 50kPa	Can be moulded by strong finger pressure.
Stiff	50 – 100kPa	Cannot be moulded by fingers, can be indented by thumb.
Very stiff	100 – 200kPa	Can be indented by thumb nail.
Hard	> 200kPa	Can be indented with difficulty by thumb nail.

#### **DENSITY TERMS - NON COHESIVE SOILS**

Density Term	Density Index	SPT "N"	CPT Cone Resistance
Very loose	< 15%	0 – 5	0 – 2MPa
Loose	15 – 35%	5 – 10	2 – 5MPa
Medium dense	35 – 65%	10 – 30	5 – 15MPa
Dense	65 – 85%	30 – 50	15 – 25MPa
Very dense	> 85%	> 50	> 25MPa

#### COLOUR

The colour of a soil will generally be described in a 'moist' condition using simple colour terms (eg. black, grey, red, brown etc.) modified as necessary by "pale", "dark", "light" or "mottled". Borderline colours will be described as a combination of colours (eg. grey-brown).

#### **EXAMPLE**

e.g.  $\,$  CLAYEY SAND (SC) – medium dense, grey-brown, fine to medium grained with silt.

Indicates a medium dense, grey-brown, fine to medium grained clayey sand with silt.



# APPENDIX B LABORATORY TEST RESULT REPORTS



# **Moisture Content Report**

Client : Address : Calibre Consulting Pty Ltd

PO Box 1580, Rockhampton, QLD, 4700

Report Number: Report Date : R18-107A - 1/1 26/03/2018

Project Name :

**Proposed Hockey Field** 

Order Number : Test Method :

AS1289.2.1.1

Project Number :

R18-107A

Location: Kalka Shades , North Rockhampton

Page 1 of 2

Soil Description :	Gravelly Silty Clay	Fill - Silty Clay	Sandy Silty Clay	Silty Clay
Oven Temperature (°C) :	105-110	105-110	105-110	105-110
	Depth: 0.1 - 0.5m	Depth: 0.2 -0.6m	Depth: 4.0 - 4.45m	Depth: 1.5 - 1.9m
Sample Location :	Bore No.: CBR #1	Bore No.: CBR #2	Bore No.: 1	Bore No.: 2
Lot Number :	-	-	-	•
Material Source :	Insitu	Insitu Insitu		Insitu
Material Type :		-	-	-
Date Tested :	16/03/2018	16/03/2018	16/03/2018	16/03/2018
Date Sampled :	9/03/2018	9/03/2018	9/03/2018	8/03/2018
Sampling Method :	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)
Test Number :	-	-	-	





Accredited for compliance with ISO/IEC 17025. - Testing

APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665



# **Moisture Content Report**

Client : Address : **Calibre Consulting Pty Ltd** 

PO Box 1580, Rockhampton, QLD, 4700

Project Name : Project Number : **Proposed Hockey Field** 

Location:

R18-107A

Kalka Shades , North Rockhampton

Report Number: Report Date :

R18-107A - 1/1

26/03/2018

Order Number:

Test Method:

AS1289.2.1.1

Page 2 of 2

Sample Number :	R18-1424	R18-1425	R18-1426	R18-1427
Test Number :	•		-	- 1
Sampling Method :	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)
Date Sampled :	9/03/2018	9/03/2018	8/03/2018	8/03/2018
Date Tested :	16/03/2018	16/03/2018	16/03/2018	16/03/2018
Material Type :	-			
Material Source :	Insitu	Insitu Insitu		Insitu
Lot Number :	-	-	•	
Sample Location :	Bore No.: 3 Depth: 0.5 - 0.95m	Bore No.: 3  Depth: 1.5 - 1.7m	Bore No.: 4  Depth: 0.5 - 0.95m	Bore No.: 4  Depth: 1.5 - 1.95m
Oven Temperature (°C) :	105-110	105-110	105-110	105-110
Soil Description :	Silty Clay	Gravelly Clay	Fill - Silty Clay	Clayey Sandy Gravel
Moisture Content (%):	21.8	18.7	15.8	9.4
Remarks :				



Accredited for compliance with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665





Rockhampton Laboratory 246 Kent Street Rockhampton QLD 4700 Telephone: 61 (07) 4927 1400 Accreditation No:. 19665

Accredited for compliance with ISO/IEC 17025 - Testing

#### **EMERSON CLASS NUMBER TEST REPORT**

Test Procedure: AS1289.3.8.1 pH TEST REPORT

Test Procedure: AS1289.4.3.1

CONDUCTIVITY REPORT Soil Chemical Methods, Rayment & Lyons

Client:	Calibre Consulting Pty Ltd	Report No.:	R18-107A_ECN_R1421-1426
Project:	Proposed Hockey Field	Tested by:	NW
l = ==4:==.	Kalka Shadaa Nadh Baakhawataa	Date:	23/03/2018
Location:	Kalka Shades, North Rockhampton	Checked by:	AE
Project No:	R18-107A	Date:	26/03/2018

THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL Determination of Emerson Class Number Immerse air dried 2-4mm diameter crumbs of soil in water No Slaking Slaking Complete Some Dispersion Dispersion No Swelling Dispersion Class 8 Class 1 Class 2 Class 7 Immerse moistened remoulded 3mm diameter soil balls in water No Dispersion Dispersion Class 3 No Calcite or Gypsum Calcite or Gypsum\* Present Present Class 4 Make up 1:5 soil/w ater suspension. Shake 10 minutes, allow to stand 5 minutes Dispersion Flocculation Class 5 Class 6

Sample Number:	R1421	R1424	R1426	
Sampling Method:				
AS1289.1.2.1	Clause 6.5.3	Clause 6.5.3	Clause 6.5.3	
Bore:	CBR#2	3	4	
Depth (m):	0.2-0.6	0.5-0.95	0.5-0.95	
Date Sampled:	9/03/2018	9/03/2018	8/03/2018	
Sample Description:	Fill - Silty Clay	Silty Clay	Fill - Silty Clay	
Water Type:	Distilled	Distilled	Distilled	
Water Temperature (°C):	21.0	21.0	20.4	
Emerson Class Number	4	4	4	T T
pH	6.0	7.7	5.0	
Conductivity (mS/cm)	0.14	0.22	0.29	

Comments:

Disclaimer:- Conductivity method is not NATA accredited

Authorised Signatory

Dwain Carolan

Date 26/03/2018



# **Particle Size Distribution Report**

Client: Address: Calibre Consulting Pty Ltd

PO Box 1580, Rockhampton, QLD, 4700

Project Name : Project Number: **Proposed Hockey Field** 

Location:

R18-107A

Kalka Shades , North Rockhampton

Report Date:

R18-107A - 2/1

26/03/2018

Order Number:

Report Number:

Test Method:

AS1289.3.6.1

Page 1 of 3

Sample Number :

Sampling Method:

Sampled By:

Nick Bloxsom

Date Sampled:

Date Tested:

23/03/2018

Material Type:

Material Source :

4.75

2,36

1.18

0.600

0.425

0.300

0.150

0.075

R18-1421

AS1289.1.2.1 (6.5.3)

9/03/2018

Insitu

SAMPLE LOCATION

Bore No.: CBR #2

Depth: 0.2 -0.6m

Fill - Silty Clay

Test Number : Lot Number :

Specification Number:

Remarks: AS Sieve Percent Specification Limits Size(mm) Passing 100 75 63 53 37.5 26.5 19.0 100 16.0 100 13.2 100 9.5 99 6.7 99

99

99

99


98

97

96

90

81





Accredited for compliance with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665

Document Code RF ISO 141-11



# **Particle Size Distribution Report**

Client: Address: **Calibre Consulting Pty Ltd** 

PO Box 1580, Rockhampton, QLD, 4700

Project Name: Project Number : **Proposed Hockey Field** R18-107A

R18-1422

Location:

Kalka Shades , North Rockhampton

Report Number: Report Date :

R18-107A - 2/1

26/03/2018

Order Number: Test Method:

AS1289.3.6.1

Page 2 of 3

Sample Number :

Sampling Method: AS1289.1.2.1 (6.5.3)

Sampled By:

Nick Bloxsom

Date Sampled:

9/03/2018

Date Tested :

20/03/2018

Material Type:

4.75

2.36

1.18

0.600

0.425

0.300

0.150

0.075

SAMPLE LOCATION

Bore No.: 1

Depth: 4.0 - 4.45m

Sandy Clay

Test Number:

Lot Number:

Specification Number:

Material Source	Insitu		
Remarks :			
AS Sieve Size(mm)	Percent Passing	Specification Limits	
100			
75			
63			
53			
37.5			
26.5			
19.0			
16.0			
13.2			
9.5			
6.7	100		

99

97

93

86


80

73

61

52







Accredited for compliance with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665

Document Code RF ISO 141-11



# **Particle Size Distribution Report**

Client: Address: Calibre Consulting Pty Ltd

PO Box 1580, Rockhampton, QLD, 4700 **Proposed Hockey Field** 

Project Name: Project Number:

Location:

Kalka Shades , North Rockhampton

Report Number: Report Date :

R18-107A - 2/1

26/03/2018

Order Number:

Test Method:

AS1289.3.6.1

Page 3 of 3

Sample Number: Sampling Method:

R18-1427 AS1289.1.2.1 (6.5.3)

Sampled By:

Nick Bloxsom

Date Sampled:

8/03/2018 20/03/2018

Date Tested: Material Type :

SAMPLE LOCATION

Bore No.: 4

Depth: 1.5 - 1.95m

Clayey Sandy Gravel

Test Number :

Material Type : Material Source :		-						lest	Number :		- 1		-	
		Insitu			Lot N	Lot Number :			1001	-				
Remarks :								Spec	ification Nu	mber :			•	
AS Sieve Size(mm)	Percent Passing	Specification Limits												
100														
75			100							1			111	7:
63														/
53			90			-	-						1	-
37.5													p/	
26.5	100		80			-	-							
19.0	90													
16.0	84		70									/		
13.2	79									_	,¢			
9.5	73		Ç 60		- 1									
6.7	66		ing(°											
4.75	66		s 50											
2.36	57		Percent Passing(%)											
1.18	47		e 40											
0.600	41					0								
0.425	38		30											
0.300	35		30	o-										
0.150	30													
0.075	27		20											
			10											$\dashv$



Accredited for compliance with ISO/IEC 17025. - Testing



0.425

AS Sieve Size(mm)

APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665

Document Code RF ISO 141-11



# **Atterberg Limits Report**

Client : Address : Calibre Consulting Pty Ltd

PO Box 1580, Rockhampton, QLD, 4700

**Proposed Hockey Field** 

Project Name : Project Number : Location:

R18-107A

on: Kalka Shades , North Rockhampton

Report Number: Report Date : R18-107A - 3/1

ate: 26/03/2018

Order Number : Test Method :

Page 1 of 1

AS1289.3.1.2, 3.2.1, 3.3.1 &

3.4.1

Sample Number :	R18-1421	R18-1424	
Test Number :	-	-	
Date Sampled :	9/03/2018	9/03/2019	
Date Tested :	22/03/2018	22/03/2018	
Sampled By :	Nick Bloxsom	Nick Bloxsom	
Sampling Method :	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	
Material Source :	Insitu	Insitu	
Material Type :		-	
Sample Location :	Bore No.: CBR #2	Bore No.: 3	
	Depth: 0.2 -0.6m	Depth: 0.5 - 0.95m	
	Fill - Silty Clay	Silty Clay	
Lot Number :	- E		
Moisture Method :	AS1289.2.1.1	AS1289.2.1.1	
Sample History :	Oven Dried	Oven Dried	
Sample Preparation :	Dry	Dry	
Notes:	Some Curling Occured	Some Curling Occured	
Mould Length (mm) :	250.3	250.0	
Liquid Limit (%) :	53	52	
Plastic Limit (%) :	16	15	
Plasticity Index (%) :	37	37	
Linear Shrinkage (%):	14.0	13.0	
SPECIFICATION DETAILS			
Specification Number :			
Liquid Limit - Max :			
Plasticity Index - Max :			
Linear Shrinkage - Max :			
Remarks :	5		 



Accredited for compliance with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number : 19665



# **Shrink Swell Index Report**

Client:

**Calibre Consulting Pty Ltd** 

Address :

PO Box 1580, Rockhampton, QLD, 4700

Kalka Shades , North Rockhampton

Project Name :

**Proposed Hockey Field** 

Project Number : Location:

R18-107A

Report Number: Report Date:

R18-107A - 5/1

28/03/2018

Order Number: Test Method:

AS1289.7.1.1

Page 1 of 1

Sample Number :	R18-1423	R18-1425	
Test Number :		-	
Sampling Method :	AS1289.1.2.1 (6.5.3)	AS1289.1.2.1 (6.5.3)	
Sampled By :	Nick Bloxsom	Nick Bloxsom	
Date Sampled :	8/03/2018	9/03/2018	
Date Tested :	14/03/2018	14/03/2018	
Material Type :	-		
Material Source :	Insitu	Insitu	
Sample Location :	Bore No.: 2  Depth: 1.5 - 1.9m	Bore No.: 3  Depth: 1.5 - 1.7m	
Inert Material Estimate (%) : PP before (kPa) :	0	0	
PP after (kPa) :			
Shrinkage Moisture Content (%):	18.4	18.8	
Shrinkage (%) :	4.0	3.0	
Swell Moisture Content Before (%) :	18.6	18.7	
Swell Moisture Content After (%) :	20.0	19.7	
Swell (%) :	2.9	2.3	
Unit Weight (t/m³) :	1.9	1.97	
Shrink Swell Index Iss (%) :	3.0	2.3	
Visual Classification :	Silty Clay	Gravelly Clay	
Cracking :	Minor	Minor	
Crumbling :	NII	Nil	
Remarks :			



Accredited for compliance with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number 19665



Rockhampton Laboratory 246 Kent Street Rockhampton Queensland 4700

Telephone: 61 (07) 4927 1400

# California Bearing Ratio Report ( 1 Point)

Client: Address : Calibre Consulting Ptv Ltd

PO Box 1580, Rockhampton, QLD, 4700

Project Number:

R18-107A

Project Name: **Proposed Hockey Field** 

Location: Kalka Shades, North Rockhampton Report Number:

Report Date :

R18-107A - 4/1 27/03/2018

Order Number:

Test Method:

AS1289.6.1.1

Page 1 of 2

SAMPLE LOCATION

Bore No.: CBR #1

Depth: 0.1 - 0.5m

Sample Number:

R18-1420

Date Sampled : Date Tested :

9/03/2018 23/03/2018

Sampled By :

Nick Bloxsom

Sampling Method:

AS1289.1.2.1 (6.5.3)

Material Source :

Insitu

Material Type:

Lot Number:

Test Number :

Remarks : Moisture Method: AS1289.2.1.1 Maximum Dry Density (t/m³): 1.62 Optimum Moisture Content (%): 21.0 Compactive Effort: Standard Nominated Percentage of MDD: 95 Nominated Percentage of OMC: 100

Achieved Percentage of MDD: 95 Achieved Percentage of OMC : 101.0 Dry Density Before Soak (t/m3): 1.54 Dry Density After Soak (t/m3): 1.48 Moisture Content Before Soak (%) : 21.2

Moisture Content After Soak (%) : 25.1 Density Ratio After Soak (%): 91 Field Moisture Content (%): 16.5 Top Moisture Content - After 24.0 Penetration (%) : Total Moisture Content - After 23.0

Soak Condition : Soaked Soak Period (days): 4 4.0

Swell (%): 4.5 CBR Surcharge (kg): Oversize (%):

Bearing Ratio 2.5mm (%): 6 Bearing Ratio 5.0mm (%):

CBR Value (%): 6

Site Selection

Oversize Material Replaced (%):

Penetration (%):

Soil Description :

Gravelly Silty Clay



Accredited for compliance with ISO/IEC 17025. - Testing

-



Joshua Hamilton - Senior Technician NATA Accreditation Number: 19665

Document Code RF ISO 39-2



Page 2 of 2

SAMPLE LOCATION

Bore No.: CBR #2

Depth: 0.2 -0.6m

# California Bearing Ratio Report (1 Point)

Client: Address : **Calibre Consulting Pty Ltd** 

**Proposed Hockey Field** 

PO Box 1580, Rockhampton, QLD, 4700

Report Number: Report Date :

R18-107A - 4/1

27/03/2018

Order Number: Test Method:

AS1289.6.1.1

Location: Kalka Shades , North Rockhampton

Sample Number :

Project Number:

Project Name :

R18-1421

R18-107A

Date Sampled:

9/03/2019

Date Tested:

23/03/2018 Nick Bloxsom

Sampled By: Sampling Method:

AS1289.1.2.1 (6.5.3)

Material Source :


Material Type:

Insitu

Lot Number:

Test Number:

Remarks :	
Moisture Method :	AS1289.2.1.1
Maximum Dry Density (t/m³) :	1.59
Optimum Moisture Content (%):	19.0
Compactive Effort :	Standard
Nominated Percentage of MDD :	95
Nominated Percentage of OMC :	100
Achieved Percentage of MDD :	95
Achieved Percentage of OMC :	102.0
Dry Density Before Soak (t/m³) :	1.51
Dry Density After Soak (t/m³) :	1.48
Moisture Content Before Soak (%) :	19.4
Moisture Content After Soak (%):	26.3
Density Ratio After Soak (%):	93
Field Moisture Content (%) :	23.2
Top Moisture Content - After Penetration (%):	23.3
Total Moisture Content - After Penetration (%) :	22.2
Soak Condition :	Soaked
Soak Period (days) :	4
Swell (%) :	2.0
CBR Surcharge (kg) :	4.5
Oversize (%) :	-



Site Selection :

Oversize Material Replaced (%) :

Soil Description : Fill - Silty Clay

**Accredited for compliance** with ISO/IEC 17025. - Testing



APPROVED SIGNATORY

Joshua Hamilton - Senior Technician NATA Accreditation Number:

19665 Document Code RF ISO 39-2



# Kalka Shades Hockey Complex

Second Field Flood Impact Assessment

# ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with

**Development Permit No.: D/51-2018** 

**Dated: 26 June 2018** 

## Kalka Shades Hockey Complex

Second Field Flood Impact Assessment

Client: Rockhampton Regional Council

ABN: 59 923 523 766

#### Prepared by

AECOM Australia Pty Ltd
Level 1, 130 Victoria Parade, PO Box 1049, Rockhampton QLD 4700, Australia T +61 7 4927 5541 F +61 7 4927 1333 www.aecom.com
ABN 20 093 846 925

01-Feb-2018

Job No.: 60534898

AECOM in Australia and New Zealand is certified to ISO9001, ISO14001 AS/NZS4801 and OHSAS18001.

 $\ensuremath{\texttt{@}}$  AECOM Australia Pty Ltd (AECOM). All rights reserved.

AECOM has prepared this document for the sole use of the Client and for a specific purpose, each as expressly stated in the document. No other party should rely on this document without the prior written consent of AECOM. AECOM undertakes no duty, nor accepts any responsibility, to any third party who may rely upon or use this document. This document has been prepared based on the Client's description of its requirements and AECOM's experience, having regard to assumptions that AECOM can reasonably be expected to make in accordance with sound professional principles. AECOM may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified. Subject to the above conditions, this document may be transmitted, reproduced or disseminated only in its entirety.

# **Quality Information**

Document Kalka Shades Hockey Complex

Ref 60534898

Date 01-Feb-2018

Prepared by Richard Corbett

Reviewed by Ben McMaster

#### **Revision History**

Rev	Revision Date	Details	Authorised	
			Name/Position	Signature
0	22-Jan-2018	Draft for Client Review	Ben McMaster Rockhampton Office Manager	Original Signed
А	1-Feb-2018	Final Issue	Ben McMaster Rockhampton Office Manager	the same

# **Table of Contents**

1.0	Introd	uction	1	
	1.1	Background	1	
	1.2	Project Objectives	1	
	1.3	Report Structures	1	
	1.4	Notes on Flood Frequency	1	
	1.5	Limitations and Exclusions	2	
2.0	Frencl	hmans Creek and Thozets Creek Flood Study	4	
	2.1	Overview	4	
	2.2	Model Description	4	
		2.2.1 Hydrologic Modelling Approach	4	
		2.2.2 Hydraulic Model Development	4	
		2.2.3 Hydraulic Model Overview		
3.0	Hydra	Hydraulic Model Development		
	3.1	Baseline Model	6	
	3.2	Initial Developed Case Modelling	5 6 6 6	
		3.2.1 Model Development	6	
		3.2.2 Difference in PWSE (D010 to D013)	10	
	3.3	Mitigation Option Iteration 1	14	
		3.3.1 Model Development	14	
		3.3.2 Difference in PWSE (D014)	16	
	3.4	Mitigation Option Iteration 2	17	
		3.4.1 Model Development	17	
		3.4.2 Difference in PWSE (D014a)	19	
	3.5	Mitigation Option Iteration 3	20	
		3.5.1 Difference in PWSE (D016)	21	
		3.5.2 Peak Depth Averaged Velocity (D016)	22	
	3.6	Hydraulic Model Development Summary	23	
		3.6.1 Key Findings	23	
4.0	Concl	Conclusion		
	4.1	Preferred Mitigation Option (D016)	25 25	
	4.2	Residual Project Risks	26	
	4.3	Recommendations	27	
5.0	Refere		28	
Appe	ndix A			
	Calibr	re Consulting Drawings	Α	
Appe	ndix B		_	
	GIS M	1apping	В	

#### **List of Tables**

Table 1	AEP to ARI Comparison	2 5
Table 2	Hydraulic Model Setup Overview	
Table 3	Predicted PWSE upstream of the existing hockey field (range of events)	25
List of Figures		
Figure 1	E2 Baseline Topography – Kalka Shades Complex	7
Figure 2	D010 Developed Case Topography – Kalka Shades Complex	7
Figure 3	D011 Developed Case Topography – Kalka Shades Complex	8
Figure 4	D012 Developed Case Topography – Kalka Shades Complex	8
Figure 5	D013 Developed Case Topography – Kalka Shades Complex	9
Figure 6	1% AEP 90 minute storm - D010 minus E2 (Baseline) Difference in PWSE	10
Figure 7	1% AEP 90 minute storm - D011 minus E2 (Baseline) Difference in PWSE	11
Figure 8	1% AEP 90 minute storm - D012 minus E2 (Baseline) Difference in PWSE	12
Figure 9	1% AEP 90 minute storm - D013 minus E2 (Baseline) Difference in PWSE	13
Figure 10	D014 Developed Case Topography – Kalka Shades Complex	14
Figure 11	D015 Developed Case Topography – Kalka Shades Complex	15
Figure 12	1% AEP 90 minute storm - D014 minus E2 (Baseline) Difference in PWSE	16
Figure 13	D014a Developed Case Topography – Kalka Shades Complex	17
Figure 14	D015a Developed Case Topography – Kalka Shades Complex	18
Figure 15	1% AEP 90 minute storm - D014a minus E2 (Baseline) Difference in PWSE	19
Figure 16	D016 Developed Case Topography – Kalka Shades Complex	20
Figure 17	1% AEP 90 minute storm - D016 minus E2 (Baseline) Difference in PWSE	21
Figure 18	1% AEP 90 minute storm - D016 minus E2 (Baseline) Difference in Peak Depth Averaged Velocity	22

1

#### 1.0 Introduction

#### 1.1 Background

In February 2016 Rockhampton Regional Council (RRC) engaged AECOM Australia Pty Ltd (AECOM) to undertake a preliminary flood impact assessment for a second field at the Kalka Shades Hockey Complex, located off Water Street, Koongal. The preliminary assessment was delivered in April 2016, the findings of which can be reviewed in AECOM letter RL44/16 (dated 15 April 2016).

Following delivery of the preliminary flood impact assessment, the Rockhampton Hockey Association (RHA) decided to investigate alternative sites for the complex, mainly due to predicted local catchment flood impacts. This investigation did yield an alternative site, in Parkhurst, which was progressed by RHA to the point where final design and costings were estimated. This site however was also found to be unsuitable, due to the large cost of developing two new fields to achieve RHAs desired level of service. RHA undertook further discussions with RRC and ultimately made the decision to further investigate development of the Kalka Shades complex.

AECOM are currently undertaking the Floodplain Management Services (FMS) project for RRC. Within the FMS project, AECOM have recently developed updated direct rainfall TUFLOW hydraulic models for local catchments within the Rockhampton area. This includes the Frenchmans Creek and Thozets Creek catchments, which encompasses the Kalka Shades complex.

Following discussions between RRC and AECOM it was agreed that the latest hydraulic model would provide a better representation of the existing and proposed conditions at the Kalka Shades complex, when compared to the previous hydraulic model used for the preliminary assessment in April 2016.

#### 1.2 Project Objectives

The key objectives of this project are to:

- Update predicted impacts of the proposed Kalka Shades development, using the latest hydraulic modelling available for the catchment.
- Further refine flood mitigation options, to reduce potential hydraulic impacts to an acceptable level.
- Assess whether improved local catchment flood immunity can be achieved for the existing field, with the implementation of reasonable mitigation works to offset impacts to an acceptable level.

#### 1.3 Report Structures

The structure of this report is as follows:

- Section 2.0 describes the Frenchmans Creek and Thozets Creek Local Catchment Flood Study (AECOM, 2017) which has been adopted for this project.
- · Section 3.0 describes the hydraulic model development and results.
- · Section 3.6 presents project conclusions and recommendations.
- Section 5.0 presents the references used during the project.

#### 1.4 Notes on Flood Frequency

The frequency of flood events is generally referred to in terms of their Annual Exceedance Probability (AEP) or Average Recurrence Interval (ARI). For example, for a flood magnitude having 5% AEP, there is a 5% probability that there will be floods of equal or greater magnitude each year. The correspondence between the two systems is presented in the ensuing table.

Table 1 AEP to ARI Comparison

Annual Exceedance Probability (AEP) %	Average Recurrence Interval (ARI) Years
63 (1 EY)	1
39	2
18	5
10	10
5	20
2	50
1	100
0.5	200

In this report, the AEP terminology has been adopted to describe the frequency of flooding.

#### 1.5 Limitations and Exclusions

The following limitations apply to this study:

- All design flood events were assessed for a single critical duration, based on an analysis of multiple storm durations for the 1% AEP event, which was completed in the Frenchmans Creek and Thozets Creek Baseline Flood Assessment (AECOM, 2017).
- Aerial survey data (in the form of LiDAR) used to develop the topography for the hydraulic model has a vertical accuracy of  $\pm$  0.15 m on clear, hard surfaces and a horizontal accuracy of  $\pm$  0.45 m.
- Assessment of the probability of coincident local rainfall and Fitzroy River flood events has not been undertaken.
- The hydraulic model has been calibrated to a single historical event, being the local flood event which occurred as a result of TC Marcia in February 2015. The model has been validated to two other local flood events, namely Ex-TC Debbie in March 2017 and Ex-TC Oswald in January 2013.
- Fitzroy River hydraulic impact assessment has not been carried out due to the project site being located in a storage area of the floodplain. Hydraulic impacts due to Fitzroy River flooding are not anticipated.
- Hydrologic and hydraulic modelling is based on methods and data outlined in Australian Rainfall and Runoff (AR&R) 1987. The 1987 revision has been adopted as per Council's request. Refer to the ARR, Data Management and Policy Review (AECOM, 2017) for details surrounding changes recommended in the 2016 revision.
- Assessment of hydraulic impacts associated with Council's preferred design scenario (D16) has been undertaken for the 63%, 39%, 18%, 10%, 5%, 2% and 1% AEP's.
- Any use which a third party makes of this document, or any reliance on or decision to be made based on it, is the responsibility of such third parties. AECOM accepts no responsibility for damages, if any, suffered by any third party as a result of decisions or actions made based on this document.
- Where information has been supplied by the Client or other external sources, the information has been assumed correct and accurate unless stated otherwise. No responsibility is accepted by AECOM for incorrect or inaccurate information supplied by others.

AR&R Revision Project 15 outlines several fundamental themes which are also particularly relevant:

- All models are coarse simplifications of very complex processes. No model can therefore be perfect, and no model can represent all of the important processes accurately.
- Model accuracy and reliability will always be limited by the accuracy of the terrain and other input data.
- Model accuracy and reliability will always be limited by the reliability / uncertainty of the inflow data.
- A poorly constructed model can usually be calibrated to the observed data but will perform poorly in events both larger and smaller than the calibration data set.
- No model is 'correct' therefore the results require interpretation.
- A model developed for a specific purpose is probably unsuitable for another purpose without modification, adjustment, and recalibration. The responsibility must always remain with the modeller to determine whether the model is suitable for a given problem.

## 2.0 Frenchmans Creek and Thozets Creek Flood Study

#### 2.1 Overview

In December 2016, RRC engaged AECOM to undertake the Floodplain Management Services (FMS) program for the 2017 calendar year. The FMS program entails the completion of a number of individual floodplain management projects including the Frenchmans Creek and Thozets Creek Local Catchment Study.

The key objectives of this project were:

- The development of a detailed hydraulic model based on current best practice procedures, capable of adequately simulating the flood characteristics and behaviour of the local catchment using the latest available data.
- The development of clear and easy to understand flood mapping products for use in future community education and awareness campaigns.
- Determination of key hydraulic controls within the study area which will later be used to inform mitigation options analysis.

The Frenchmans Creek and Thozets Creek Phase 1 Baseline Flood Study included the development of a TUFLOW model for the lower portion of the Frenchmans Creek and Thozets Creek local catchment. This model utilises a combination of runoff-routing and direct rainfall approaches in order to determine the overland flow paths and establish baseline flood extents and depths within the study area.

#### 2.2 Model Description

The Baseline model which was developed for Frenchmans Creek and Thozets Creek Local Catchment Study has been adopted in its entirety for the Kalka Shades Hockey Complex Flood Assessment.

The following sub-sections describe the model set up and parameters.

#### 2.2.1 Hydrologic Modelling Approach

The hydrology inputs for this model have been developed using both runoff routing for the broader catchment and direct rainfall.

An XP-Rafts model (version 2013) was developed for the upper portion of the Frenchmans Creek and Thozets Catchment by Aurecon in 2014. This model was provided by RRC and utilised to provide upper catchment inflows. An overview of the hydrologic model development can be reviewed in the Frenchmans Creek and Thozets Creek Hydrologic and Hydraulic Modelling Report (Aurecon, 2014).

Direct rainfall inputs were applied directly to the TUFLOW hydraulic model. This TUFLOW model generally covers the middle and lower catchment areas of Frenchmans Creek and Thozets Creek.

A full summary of the hydrology inputs for the Frenchmans Creek and Thozets Creek Local Catchment Study model can be found in the Frenchmans Creek and Thozets Creek Baseline Flood Study – Volume 1 Report (AECOM, 2017).

#### 2.2.2 Hydraulic Model Development

The modelling platform which was used for the development of the Frenchmans Creek and Thozets Creek Local Catchment model was TUFLOW build version 2016-03-AE. Details regarding the model setup can be seen in Table 2.

Table 2 Hydraulic Model Setup Overview

Parameter	Frenchmans Creek and Thozets Creek Local Catchment Model
Completion Date	June 2017
AEP's Assessed	1EY, 39%, 18%, 10%, 5%, 2%, 1%, 0.2%, 0.05% AEP and PMF
Hydrologic Modelling	XP-RAFTS Inflow and Direct Rainfall Approach
IFD Input Parameters	Refer to Section Frenchmans Creek and Thozets Creek Baseline Flood Study – Volume 1 Report (AECOM, 2017)
Hydraulic Model Software	TUFLOW version 2016-03-AE-w64-iDP
Grid Size	3m
DEM (year flown)	2016
Roughness	Spatially varying and depth varying standard values – consistent with South Rockhampton Model and Frenchmans and Thozets Creek Hydrologic and Hydraulic Modelling Report (Aurecon, 2014).
Eddy Viscosity	Smagorinsky
Model Calibration	Calibrated to 2015 event, verified to 2013 and 2017 events.
Downstream Model Boundary	7 inflow boundary along the steep bushland boundaries, 2 rating curve boundary conditions along the western boundary, 1 tidal boundary on the south boundary.
Timesteps	1 second (3m 2D) and 0.5 second (1D)
Wetting and Drying Depths	Cell centre 0.0002 m
Sensitivity Testing	Stormwater Infrastructure Blockage, ±15% Hydraulic Roughness, Riverine and Local Catchment Coincident Event, Inlet Structure Dimensions and Climate Change

#### 2.2.3 Hydraulic Model Overview

For full details of the hydraulic model setup and development refer to the Frenchmans Creek and Thozets Creek Baseline Flood Study – Volume 1 Report (AECOM, 2017).

## 3.0 Hydraulic Model Development

#### 3.1 Baseline Model

The baseline model has been adopted entirely from the Frenchmans Creek and Thozets Creek Baseline Flood Study (AECOM, 2017) without any changes for the baseline scenario.

#### 3.2 Initial Developed Case Modelling

#### 3.2.1 Model Development

The following general methodology was undertaken to assess the proposed development:

- An initial set of Developed Case simulations were simulated for the 1% AEP critical duration event, including:
  - **D010** à Proposed development of second field, as per Calibre Consulting project R15041 drawings (Rev 2) dated April 2016, with no mitigation works included.
    - § A copy of Calibre Consulting drawings has been provided in **Appendix A**.
  - **D011** à As per D010 configuration, with the inclusion of a 30m grassed swale on the eastern side of the second field.
  - **D012** à As per D011 configuration, with the addition of clearing / excavation works within Frenchmans Creek to the north and west of the existing field.
  - **D013** à As per D012 configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
- Results of the initial Developed Case scenarios were compared to the corresponding Baseline results, to establish the predicted changes in peak flood extents, peak flood height and peak depth averaged velocity.
- High level GIS mapping was produced for discussion with RRC.
  - The latest difference mapping was also compared to the April 2016 difference mapping, to confirm similar predicted flood impacts.
- The initial modelling results were used to further develop mitigation options.

Figure 1 shows the E2 Baseline topography, for easy comparison to Figure 2 to Figure 5 which provides the Developed Case topography for the D010 to D013 scenarios.




Figure 1 E2 Baseline Topography – Kalka Shades Complex




Figure 2 D010 Developed Case Topography – Kalka Shades Complex




Figure 3 D011 Developed Case Topography - Kalka Shades Complex




Figure 4 D012 Developed Case Topography – Kalka Shades Complex




Figure 5 D013 Developed Case Topography – Kalka Shades Complex

#### 3.2.2 Difference in PWSE (D010 to D013)

Figure 6 to Figure 9 show results of the D010 to D013 scenarios, along with a brief discussion on the performance of each configuration as compared to the E2 Baseline results.




Figure 6 1% AEP 90 minute storm - D010 minus E2 (Baseline) Difference in PWSE

Comparison of the D010 Developed Case 1% AEP results to the E2 Baseline results show:

- Increases in Peak Water Surface Elevations (PWSE) upstream of the new and existing fields, extending north as far as Tomkys Street.
- A decrease in PWSE downstream of the new field.
- A negligible increase in flood extents.




Figure 7 1% AEP 90 minute storm - D011 minus E2 (Baseline) Difference in PWSE

The difference in PWSE for the D011 Developed Case 1% AEP event, compared to the E2 Baseline results, shows:

- Increases in flood height upstream of the new and existing fields, extending north as far as Tomkys Street. The predicted increase in PWSE is, however, smaller compared to the predicted D010 scenario impact.
- · A decrease in PWSE downstream of the new field.
- A negligible increase in flood extents.




Figure 8 1% AEP 90 minute storm - D012 minus E2 (Baseline) Difference in PWSE

Comparison of the 1% AEP D012 Developed Case and E2 Baseline results shows:

- Predicted increases in PWSE have been further reduced upstream of the new and existing fields, when compared to the D011 scenario impact.
- · A decrease in PWSE downstream of the new field.
- A negligible increase in flood extents.




Figure 9 1% AEP 90 minute storm - D013 minus E2 (Baseline) Difference in PWSE

Figure 9 shows the following for the 1% AEP D013 Developed Case difference in PWSE, compared to the E2 Baseline results:

- Increases in PWSE upstream of the new and existing fields extending further north to Mostyn Street and further south to Lakes Creek Road.
- · A decrease in PWSE downstream of the new and existing fields.
- Some increase in flood extents in the Tomkys Street and Mostyn Street areas.

The predicted increase in PWSE and flood extent appears to be due to increased tailwater levels downstream of the existing Tomkys Street breakout, resulting in flood waters being 'held up' to the north, south and west of the proposed development.

#### 3.3 Mitigation Option Iteration 1

#### 3.3.1 Model Development

Following completion of the initial Developed Case modelling, the results were used to further refine the proposed mitigation works. The analysis showed that the eastern swale was more effective in reducing flood impacts when compared to excavation / clearing works within Frenchmans Creek, leading to Mitigation Option Iteration 1:

- D014 à As per D010 configuration, with the inclusion of a 80m wide grassed swale on the
  eastern side of the second field. This required removal of two existing sheds and the practice
  cricket nets.
- D015 à As per D014 configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
  - The D015 scenario was not simulated, as the results of the D014 simulation were sufficient to inform future option development.

Figure 10 and Figure 11 show the topography for the D014 and D015 configurations respectively.




Figure 10 D014 Developed Case Topography - Kalka Shades Complex




Figure 11 D015 Developed Case Topography – Kalka Shades Complex

#### 3.3.2 Difference in PWSE (D014)

Figure 12 shows the difference in PWSE between D014 Developed Case and E2 Baseline, for the 1% AEP critical duration event. It can be seen that the D014 scenario has achieved the desired result in the area between Tomkys Street and Mason Street, where predicted impacts in private property are less than 20mm.

There remains however a predicted increase in PWSE of up to 52mm within private properties in Tooker Street. An associated decrease in PWSE is predicted downstream of the new field.




Figure 12 1% AEP 90 minute storm - D014 minus E2 (Baseline) Difference in PWSE

Due to the predicted impact within Tooker Street properties, further mitigation option development was requested by Council.

#### 3.4 Mitigation Option Iteration 2

#### 3.4.1 Model Development

While the D014 configuration did show a reduction in predicted flood impacts, discussions with Council identified a preference to reduce predicted impacts to less than 20mm within private property. Analysis of the D014 results showed an opportunity to further reduce predicted impacts through further refinement of the eastern channel, as follows:

- **D014a** à As per D014 configuration, with the removal of the existing earth mound within the proposed grassed swale behind Tooker Street properties.
- D015a à As per D014a configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
  - The D015a scenario was not simulated, as the results of the D014a simulation were sufficient to inform future option development.

The topography for scenarios D014a and D015a are provided in Figure 13 and Figure 14 respectively.




Figure 13 D014a Developed Case Topography – Kalka Shades Complex




Figure 14 D015a Developed Case Topography - Kalka Shades Complex

#### 3.4.2 Difference in PWSE (D014a)

The difference in PWSE between D014a Developed Case and E2 Baseline, for the 1% AEP critical duration event is provided in Figure 15. Removal of the mound within the 100m grassed swale for Developed Case D014a has achieved the desired result, where predicted impacts in private property are less than 20mm.

There remains a predicted increase in PWSE adjacent to the new field and south of Mason Street; however these are located within Council owned land. An associated decrease in PWSE is predicted north of Tooker Street and downstream of the new field.




Figure 15 1% AEP 90 minute storm - D014a minus E2 (Baseline) Difference in PWSE

For the proposed second field development, the D014a configuration achieves Council's desired level of flood impact within private property. However it is unlikely the same configuration would continue to show predicted impacts of less than 20mm, if the existing field embankment were raised to improve current flood immunity.

Further mitigation option development was therefore undertaken, seeking to allow for the development of the new field plus augmentation of the existing field, whilst maintaining less than a 20mm increase in PWSE within private property.

#### 3.5 Mitigation Option Iteration 3

With the D014a scenario achieving Council's desired outcome relating to predicted impacts within private property, the focus turned to improving the flood immunity of the existing hockey field. At present the existing field is predicted to have flood immunity between the 39% AEP and 18% AEP local catchment event.

The D013 scenario demonstrated that improving the existing field flood immunity to 1% AEP results in unacceptable impacts. The **D016** scenario therefore sought to improve the existing field flood immunity to 2% AEP. In addition, the D014a results identified an opportunity to further balance predicted impacts by relocating the proposed second field further to the east, thereby allowing flow between the fields.

- D016 à Proposed second field moved 10m to the east, with the addition of a concrete barrier around the existing field to provide 2% AEP local catchment flood immunity (with no allowance for freeboard). Grassed swales provided on either side of new field (70m wide on eastern side and 30m on western side of new field).
  - This scenario also includes the removal of the Mason Street road embankment (10m length) and will necessitate removal of the existing power pole and overhead service line connected to the cricket shed (which is also being removed in this scenario).

Figure 16 shows the D016 topography and demonstrates the relocation of the second field and inclusion of grassed swales on either side of the new field.




Figure 16 D016 Developed Case Topography – Kalka Shades Complex

The D016 scenario was selected as the final configuration for this assessment and was consequently simulated for the 63% AEP, 39% AEP, 18% AEP, 10% AEP, 5% AEP, 2% AEP and 1% AEP critical duration local catchment event.

#### 3.5.1 Difference in PWSE (D016)

The following difference in PWSE mapping is included in **Appendix B**, for the critical storm duration:

- Map B1 à 63% AEP Difference in PWSE D016 minus E2 (Baseline)
- Map B2 à 39% AEP Difference in PWSE D016 minus E2 (Baseline)
- Map B3 à 18% AEP Difference in PWSE D016 minus E2 (Baseline)
- · Map B4 à 10% AEP Difference in PWSE D016 minus E2 (Baseline)
- Map B5 à 5% AEP Difference in PWSE D016 minus E2 (Baseline)
- Map B6 à 2% AEP Difference in PWSE D016 minus E2 (Baseline)
- Map B7 à 1% AEP Difference in PWSE D016 minus E2 (Baseline)

Figure 17 shows the difference in PWSE, for the 1% AEP critical storm event.




Figure 17 1% AEP 90 minute storm - D016 minus E2 (Baseline) Difference in PWSE

Review of the difference in PWSE mapping attached in Appendix B shows:

- Flood extents and flood depths are predicted to increase during frequent events (63% AEP and 39% AEP) on the eastern side of the new field, due to the proposed grass swale and reduction of the high bank of the upstream Frenchmans Creek anabranch.
- In general, flood levels are predicted to reduce to the north and west of the existing and new fields, as a result of the additional flow through the proposed grassed swales.
- An associated general increase in PWSE is predicted to the east and south of the existing and new fields.
- Increases in PWSE are reasonably well balanced on either side of the new field, during the 1% AEP event.

- In the 1% AEP event, predicted increases in PWSE are less than 20mm in private property and are reduced in some cases, with the exception of two private properties south of Mason Street (western spur), where predicted increases in PWSE are up to 32mm.
- The raised embankment / flood wall within the existing field results in increased PWSE within the field area during the 1% AEP event. This is due to the embankment being raised only to 2% AEP.
- The predicted reduction in Tooker Street properties during the 1% AEP event, is due to opening up the Mason Street road embankment.

#### 3.5.2 Peak Depth Averaged Velocity (D016)

The following difference in Peak Depth Averaged Velocity (PDAV) mapping is included in **Appendix B**, for the critical storm duration:

- Map B8 à 63% AEP Difference in PDAV D016 minus E2 (Baseline)
- Map B9 à 39% AEP Difference in PDAV D016 minus E2 (Baseline)
- Map B10 à 18% AEP Difference in PDAV D016 minus E2 (Baseline)
- · Map B11 à 10% AEP Difference in PDAV D016 minus E2 (Baseline)
- Map B12 à 5% AEP Difference in PDAV D016 minus E2 (Baseline)
- Map B13 à 2% AEP Difference in PDAV D016 minus E2 (Baseline)
- Map B14 à 1% AEP Difference in PDAV D016 minus E2 (Baseline)

The PDAV maps for the 1% AEP baseline and D016 scenarios are also provided in **Appendix B**, for the critical storm duration:

- Map B15 à 1% AEP Baseline PDAV
- Map B16 à 1% AEP D016 PDAV

Figure 18 shows the difference in difference in PDAV, for the 1% AEP critical storm duration.




Figure 18 1% AEP 90 minute storm - D016 minus E2 (Baseline) Difference in Peak Depth Averaged Velocity

Review of the PDAV mapping attached in Appendix B shows:

- Generally PDAV is predicted to increase to the east and south of the new field, with an associated reduction predicted to the north and west of the complex.
- 1% AEP Baseline PDAV ranges from 1.2m/s to 1.6m/s at the proposed location of the new field.
- 1% AEP D016 PDAV reaches up to 2.2m/s in this same location.
- Assessment of erosion protection for new grassed swales and other disturbed areas has not been assessed. This should be investigated in more detail during a subsequent phase of the project using the velocity outputs provided in this report.

#### 3.6 Hydraulic Model Development Summary

The following Developed Case scenarios have been simulated for the 1% AEP local catchment event, unless otherwise noted:

- **D010** à Proposed development of second field, as per Calibre Consulting project R15041 drawings (Rev 2) dated April 2016, with no mitigation works included.
- **D011** à As per D010 configuration, with the inclusion of a 30m grassed swale on the eastern side of the second field.
- D012 a As per D011 configuration, with the addition of remediation works within Frenchmans Creek to the north and west of the existing field.
- **D013** à As per D012 configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
- **D014** à As per D010 configuration, with the inclusion of a 80m grassed swale on the eastern side of the second field.
- **D015** à As per D014 configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
- D014a à As per D014 configuration, with the removal of existing mound within the 80m grassed swale behind Tooker Street properties.
- D015a à As per D014a configuration, with the addition of a concrete barrier around the existing field to provide 1% AEP local catchment flood immunity.
- D016 à Proposed second field moved 10m to the east, with the addition of a concrete barrier around the existing field to provide 2% AEP local catchment flood immunity (with no freeboard). Grassed swales provided on either side of new field, with removal of the existing mound behind Tooker Street properties and removal of the Mason Street road embankment (10m length).
  - Simulated for the 63% AEP, 39% AEP, 18% AEP, 10% AEP, 5% AEP, 2% AEP and 1% AEP critical duration local catchment event.

#### 3.6.1 Key Findings

Analysis of the Developed Case modelling results reveals:

- Construction of the new field, with no mitigation works (D010), increases flood heights by 75-150mm in the 1% AEP event within private properties along Tooker Street and Mason Street.
   Increased flood heights aren't expected to affect any existing dwellings, and there is not expected to be a significant change in flood extent in the 1% AEP event.
- Inclusion of the open channel **(D011)** reduces impacts to the west of the new field but will not significantly benefit properties to the east (i.e. Tooker Street).
- Inclusion of significant excavation / clearing works within the creek **(D012)** doesn't result in a significant further reduction when compared to D011 (open channel only). The works within the creek are expected to be very costly and will likely require significant environmental / cultural heritage approvals.

- Protection of the existing field for the 1% AEP event **(D013)** is expected to have significant hydraulic impacts, even with inclusion of the open channel and creek excavation / clearing works.
- For the **D014** 1% AEP event, the predicted private property flood impacts in the area between Tomkys Street and Mason Street has been reduced to less than 20mm. However, a predicted increase in PWSE of up to 52mm remains within Tooker Street private properties. An associated decrease in PWSE is predicted downstream of the new field.
- The (D014a) 1% AEP results show that further opening the 80m grassed swale has achieved RRC's desired result, where predicted impacts in private property are less than 20mm. There remains a predicted increase in PWSE adjacent to the new field and south of Mason Street; however these are located within Council owned land. An associated decrease in PWSE is predicted north of Tooker Street and downstream of the new field.
- As noted above, the **D015** and **D015a** scenarios were not modelled as the D014 and D014a configurations were sufficient to inform further mitigation option development.
- Results of the 1% AEP (**D016**) scenario (refer **Appendix B**) show predicted increases in PWSE are less than 20mm in private properties and are reduced in some cases, with the exception of two private properties south of Mason Street (western spur), where predicted increases in PWSE are up to 32mm. Increases in PWSE are reasonably well balanced on either side of the new field. The raised embankment around the existing field results in increased PWSE within the field area during the 1% AEP event. This is due to the embankment being raised only to 2% AEP. The predicted reduction in Tooker Street properties is likely due to opening up the road embankment.

#### 4.0 Conclusion

#### 4.1 Preferred Mitigation Option (D016)

As shown in Section 3.6 a number of Developed Case scenarios have been assessed, to assist Council understand the predicted flood impacts of the proposed Kalka Shades development, as well as the benefits of potential mitigation options.

Ultimately Council made the decision to progress with scenario D016 as the preferred Development configuration and flood mitigation strategy. The D016 Scenario includes:

- Proposed second field moved 10m to the east, with a minimum top of embankment elevation of 8.15mAHD to provide 1% AEP local catchment flood immunity. Provision for freeboard should be confirmed by RRC in the subsequent phase of the project.
- A concrete barrier around the existing field to provide 2% AEP local catchment flood immunity. A
  minimum top of barrier elevation of 7.8mAHD will be required. Freeboard has not been included
  to minimise afflux in larger magnitude flood events.
  - Table 3 shows the predicted PWSE upstream of the existing hockey field, for a range of historic local catchment flood events and the 1% AEP Fitzroy River design flood event. It can be seen that the proposed concrete barrier around the existing field is higher than all events shown.

Table 3	Predicted PWSE u	pstream of the existing	hockey field	(range of events)

Event	PWSE upstream of Existing Hockey Fields (mAHD)
Jan 2013 Local Catchment (Ex. TC Oswald)	7.54
Feb 2015 Local Catchment (TC Marcia)	7.70
Mar 2017 Local Catchment (Ex. TC Debbie)	7.47
1% AEP Fitzroy River Flood	7.70
Existing Field Raised Embankment	7.80

- Grassed swales provided on either side of the new field, with the following general arrangement (to be confirmed by the civil design consultant):
  - Eastern Channel à V-Drain shape; Depth at northern end = 600mm; Width = 45m to 70m; Longitudinal Grade = 0.5%; Excavation Volume = approximately 2,000m<sup>3</sup>.
  - Western Channel à V-Drain shape; Depth at northern end = 500mm; Width = 30m to 40m; Longitudinal Grade = 0.3%; Excavation Volume = approximately 870m<sup>3</sup>.
- Removal of the Mason Street road embankment (approximately 10m length).
- Removal of the existing cricket sheds on Mason Street.
- Removal of the existing power pole and overhead service line connected to the Mason Street cricket sheds.

The mapping attached in Appendix B shows the D016 scenario difference in PWSE and difference in PDAV across the range of events assessed. The mapping generally shows:

- Increased flood extents and flood depths during frequent events (63% AEP and 39% AEP) on the
  eastern side of the new field. This is due to the proposed grass swale and reduction of the high
  bank of the upstream Frenchmans Creek anabranch.
- Flood levels are predicted to reduce to the north and west of the existing and new fields, as a result of the additional flow through the proposed grassed swales. An associated general increase in PWSE is predicted to the east and south of the existing and new fields.

- Increases in PWSE are reasonably well balanced on either side of the new field, during the 1% AEP event. In the 1% AEP event, predicted increases in PWSE are less than 20mm in private property and are reduced in some cases, with the exception of two private properties south of Mason Street (western spur), where predicted increases in PWSE are up to 32mm.
- The raised embankment / flood wall within the existing field results in increased PWSE within the field area during the 1% AEP event. This is due to the embankment being raised only to 2% AEP.
- Generally PDAV is predicted to increase to the east and south of the new field, with an associated reduction predicted to the north and west of the complex.
- 1% AEP Baseline PDAV ranges from 1.2m/s to 1.6m/s at the proposed location of the new field. 1% AEP D016 PDAV reach up to 2.2m/s in this same location. Assessment of erosion protection for new grassed swales and other disturbed areas has not been assessed. This should be investigated in more detail during a subsequent phase of the project using the velocity outputs provided in this report.

#### 4.2 Residual Project Risks

Although the proposed D016 configuration is predicted to offset the majority of flood impacts, there remain a number of residual risks arising from the project:

- The predicted flow velocity under the proposed clubhouse may result in pier scour, which has not been assessed at this stage. It is recommended a pier scour assessment be completed in subsequent stages of the project.
- It is assumed the proposed clubhouse floor level is above the 1% AEP Developed Case Local Catchment flood level, with allowance for freeboard. Should this not be the case, predicted flood impacts would likely increase.
- The current development drawings, at the time of this report, show the proposed clubhouse within the western grassed swale (D016 scenario only). It is likely that sediment and debris deposition will occur under building, increasing the requirement for maintenance.
- The predicted increase in velocity between the two fields may require scour protection for the raised embankments around the existing and proposed fields. It is recommended a scour assessment be completed in subsequent stages of the project.
- The proposed swales will cut into the high bank of the upstream Frenchmans Creek anabranch. This may trigger statutory approvals. This should be investigated by RRC.
- No assessment of creek bank stability has been undertaken, nor has the design of bank protection works where the proposed swales will cut through the high bank. It is recommended this be completed in subsequent stages of the project.
- Proposed grassed swales have flat longitudinal grades, which divert flows from the creek to the floodplain. Longitudinal grades can't be increased due to the constraints posed by the existing cricket facilities downstream of the hockey fields. Accumulation of sediment and debris may occur within the swales and downstream of their discharge point, requiring additional maintenance after flood events.
- The existing cricket fields are predicted to be inundated more frequently due to the inclusion of the grassed swales. Council should undertake consultation with the Rockhampton Cricket Association regarding the potential need for more frequent maintenance.
- The peak flood depths adjacent to the existing field are up to 1.0m in the 2% AEP local catchment event. Existing openings in the field embankment, to allow access for emergency vehicles and ingress/egress to the field area, will need to be closed off via flood gates or the like.
- While it is likely there would be negligible impact to flood storage during Fitzroy River flood events, this has not been formally assessed at this stage of the project.
- Internal drainage within the existing and new hockey fields has not been assessed. Final sizing and configuration of internal drainage systems are to be assessed by others.

#### 4.3 Recommendations

It is recommended that:

- The findings of this report be discussed with Rockhampton Hockey Association (RHA) and other key stakeholders (i.e. Rockhampton Cricket Association).
- RRC's / RHA's engineering consultant undertake the following works:
  - a pier scour assessment for the proposed clubhouse,
  - review the need for protection works for the raised field embankments,
  - review the need for erosion protection for new grassed swales and other disturbed areas,
  - assess creek bank stability and bank protection requirements where the grassed swales are proposed,
  - investigate statutory approval requirements associated with all proposed works,
  - undertake final design of internal drainage system.

#### 5.0 References

Calibre Consulting project R15041 drawings (Rev 2) dated April 2016 (refer Appendix A).

Australian Rainfall and Runoff (2012). *Project 15 – Two Dimensional Modelling in Urban and Rural floodplains - Stage 1& 2 Report.* Available at: <a href="http://arr.ga.gov.au/">http://arr.ga.gov.au/</a>, accessed 13 March 2017.

Institution of Engineers Australia (1998), Australian Rainfall and Runoff – A Guide to Flood Estimation, Volumes 1 and 2.

BMT WBM (2016), TUFLOW User manual - Build 2016-03-AE.

Rockhampton Regional Council (2017), Frenchmans Creek and Thozets Creek–Baseline Flood Study – Volume 1 Report, prepared by AECOM, 2017.

# Appendix A

Calibre Consulting
Drawings



## PROPOSED SYNTHETIC TURF HOCKEY FIELD

### KALKA SHADES, NORTH ROCKHAMPTON, QLD



LOCALITY PLAN LOT 1 ON LN2893 N.T.S

ROCKHAMPTON REGIONAL COUNCIL

#### DRAWING LIST

No.	TITLE DESCRIPTION
GENERAL	
000	COVER SHEET
001	GENERAL NOTES SHEET 1 OF 2
002	GENERAL NOTES SHEET 2 OF 2
003	EXISTING SITE PLAN
004	PROPOSED SITE PLAN
EARTHWORKS	
100	BULK EARTHWORKS PLAN
SITE WORKS	
200	PROPOSED FIELD LAYOUT PLAN
201	SITE SECTIONS PLAN
202	TYPICAL DETAILS PLAN
STORMWATER	
300	STORMWATER LAYOUT PLAN SHEET 1 OF 2
301	STORMWATER LAYOUT PLAN SHEET 2 OF 2
302	STORMWATER LONGSECTIONS PLAN
303	STORMWATER CALCULATIONS TABLE
304	STORMWATER DETAILS PLAN
WATER	
400	WATER RETICULATION LAYOUT PLAN
SERVICES	
500	ELECTRICAL LAYOUT PLAN
EROSION AND SED	IMENT CONTROL
600	CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN
601	POST CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN





PROPOSED SYNTHETIC TURF HOCKEY FIELD KALKA SHADES, NORTH ROCKHAMPTON, QLD

Project No.: Milestone: Drawing No.: Re R15041 DESIGN 000

#### **GENERAL**

#### 1.1. EXISTING SERVICES

THE BUILDER SHALL ESTABLISH THE EXTENT AND LOCATION OF ALL EXISTING SERVICES WITHIN THE WORKS AREA. ALL SERVICES SHALL BE PROTECTED AGAINST ACCIDENTAL DAMAGE DURING THE CONSTRUCTION OF THE WORKS. THE BUILDER SHALL BE RESPONSIBLE FOR ALL COSTS INCURRED DUE TO DAMAGE TO EXISTING SERVICES.

#### 2.0. AS-CONSTRUCTED INFORMATION

IF REQUIRED, THE BUILDER SHALL PROVIDE LEVELS AND DIMENSION INFORMATION SUITABLE TO CONFIRM TO THE SATISFACTION OF THE SUPERINTENDENT THAT THE WORKS HAVE BEEN CONSTRUCTED TO THE LEVELS AND DIMENSIONS SHOWN ON THE DRAWINGS. THE BUILDER SHALL PROVIDE ALL AS-CONSTRUCTED INFORMATION NECESSARY FOR THE PREPARATION OF THE AS-CONSTRUCTED PLANS SUITABLE FOR COUNCILS SATISFACTION.

THE MINIMUM INFORMATION REQUIREMENTS ARE AS FOLLOWS:

- 2.1. ROAD AND DRAINAGE:
- 2.2. LOCATIONS OF MANHOLES, GULLY PITS AND
- 2.3. INVERT LEVELS OF INLET AND OUTLET PIPES
  AT MANHOLES AND GULLY PITS ON LAYOUT
  DIAN.
- 2.4. INVERT LEVELS OF CULVERTS AND INLETS AND OUTLETS;
- 2.5. TOP OF MANHOLE AND GULLY PIT LEVELS AT THE CENTRE POINT ON LAYOUT PLAN:
- 2.6. INDICATE ACTUAL PIPE SIZES, CLASSES AND GRADES ON THE LAYOUT PLAN:
- 2.7. LOCATIONS OF ALL SERVICES INCLUDING WHERE THEY CROSS THE ROADS (E.G. ELECTRICITY, WATER, SEWER, TELSTRA, DRAINAGE PIPES).
- 2.8. LOCATION OF ALL STREET LIGHTING POLES, ELECTRICITY SERVICE TURRETS AND ELECTRICAL CONDUITS (INCLUDING SIZE AND NUMBER).
- 2.9. ALL DIMENSIONS SHALL BE PROVIDED IN METRES CORRECT TO 2 DECIMAL PLACES. ALL LEVELS SHALL BE ON AUSTRALIAN HEIGHT DATUM (AHD) IN METRES CORRECT TO 3 DECIMAL PLACES;
- 2.10. THE TEST RESULTS FOR THE DEPTH OF EACH PAVEMENT LAYER. TEST RESULTS AND THE LEVEL CORRELATION SHEET FOR THE SUBGRADE AND BASE ARE TO BE SUBMITTED TO THE ENGINEER PRIOR TO THE COUNCIL INSPECTION;
- 2.11. QUALITY ASSURANCE TESTING RESULTS FOR THE PAVEMENT AND ASPHALT;
- 2.12. THE "AS CONSTRUCTED" INFORMATION FOR ROADWORKS AND DRAINAGE SHALL BE PROVIDED WITHIN FOURTEEN (14) DAYS ON COMPLETION OF ROADWORKS AND DRAINAGE.

#### 3.0. INSPECTIONS

A MINIMUM OF 24 HOURS NOTICE OF ALL REQUIRED INSPECTIONS SHALL BE GIVEN BY THE BUILDER TO THE SUPERINTENDENT. THE PRINCIPAL REQUIRES INSPECTIONS AT THE FOLLOWING STAGES OF CONSTRUCTION.

- 3.1. ROADWORKS AND STORMWATER DRAINAGE
- 3.2. AT SUBGRADE LEVEL
- 3.3. SUB-BASE LEVEL PRIOR TO KERBING
- 3.4. BASE COURSE PRIOR TO PRIMING & ASPHALT
- 3.5. ALL STORMWATER PIPES PRIOR TO BACKFILLING
- 3.6. ANY WORKS REQUIRING PLACEMENT OF REINFORCING STEEL.

CHECK LEVELS AND TESTING RESULTS WILL BE REQUIRED PRIOR TO INSPECTIONS WHERE APPLICABLE.

#### **EARTHWORKS AND ROADWORKS**

#### 1.0. EARTHWORKS

#### 1.1. TOPSOIL

THE BUILDER SHALL STRIP TOPSOIL FROM THE WHOLE OF THE EARTHWORKS AREA INCLUDING ANY AREAS OF ALLOTMENT FILL TO A DEPTH OF MINIMUM 100mm OR AS DIRECTED BY THE SUPERINTENDENT AND STOCKPILE IT IN THE NOMINATED STOCKPILE AREA PRIOR TO COMMENCING BULK EARTHWORKS. THE BUILDER SHALL BE REQUIRED TO CARRY OUT TEMPORARY STABILISING MEASURES TO MINIMISE THE TRANSPORTATION OF AIRBORNE MATERIAL THAT MAY CAUSE NUISANCE TO NEIGHBOURING PROPERTIES.

#### 1.2. PAVEMENT BOX

THE BUILDER SHALL INITIALLY CONSTRUCT THE EARTHWORKS TO THE LEVEL OF THE UNDERSIDE OF THE PAVEMENT BOX AS SHOWN ON THE DRAWINGS. THE FOOTPATHS SHALL BE EXCAVATED AND OR FILLED TO THE LEVELS SHOWN ON THE DRAWINGS.

#### 1.3. BULK FILLING

#### 1.3.1. ROADS

PRIOR TO ANY FILLING THE AREA TO BE FILLED SHALL BE PROOF ROLLED BY FOUR PASSES OF A 10 TONNE MINIMUM STATIC MASS ROLLER. THE FINAL PASS SHALL BE TREATED AS TEST ROLLING IN ACCORDANCE WITH TESTING CLAUSE 5.4 OF AS 3798 WITH INSPECTION CARRIED OUT BY THE APPROVED GEOTECHNICAL TESTING AUTHORITY OR THE SUPERINTENDENT. THE COST OF PROOF AND TEST ROLLING SHALL BE DEEMED TO BE INCLUDED IN THE CONTRACT LUMP SUM. FILLING SHALL BE PLACED IN LAYERS OF NOT MORE THAN 200mm LOOSE THICKNESS AND COMPACTED TO A MINIMUM STANDARD MAXIMUM DRY DENSITY AS DETERMINED BY AS 1289, E1.1 AND SPECIFIED IN THIS SPECIFICATION. TEST FREQUENCY SHALL BE AS STATED IN THE QUALITY ASSURANCE TESTING TABLE A. AT ALL TIMES DURING BULK EARTHWORKS THE BUILDER SHALL ENSURE THAT THE WORKS ARE KEPT IN A STATE SO AS NOT TO ALLOW PONDING ON THE WORKS OR EROSION FROM THE WORKS IN THE EVENT OF RAIN. THE MOISTURE CONTENT OF THE FILL SHALL BE MAINTAINED AS CLOSE AS IS PRACTICAL TO OPTIMUM MOISTURE CONTENT DURING THE COMPACTION OF THE FILL.

#### 1.3.2. BUILDING PADS

THE BUILDER SHALL BE REQUIRED TO PROVIDE CERTIFICATION THAT FILL DEEPER THAN 300mm PLACED ON THE BUILDING PAD HAS BEEN SUPERVISED IN ACCORDANCE WITH LEVEL 1 AS DEFINED BY AS3798. CERTIFICATION SHALL STATE THAT FILL IS SIMILAR TO THAT DEFINED IN SECTION 6.1.2 OF AS2870.1 AND CAN THUS BE CLASSIFIED AS "CONTROLLED FILL".

THE TESTING STRATEGY SHALL BE DEVELOPED IN ACCORDANCE WITH SECTION 8 OF AS3798 AND REQUIRES APPROVAL FROM THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF FILLING. EVERY FIELD DENSITY TEST SHALL BE IDENTIFIED BY LOCATION AND LEVEL.

PAYMENT FOR GEOTECHNICAL TESTING ASSOCIATED WITH ALLOTMENT FILLING CERTIFICATION SHALL BE DEEMED TO BE INCLUDED IN THE TENDERED PRICE FOR EARTHWORKS.

#### 1.4. DUST CONTROL

THE BUILDER SHALL ENSURE THAT DUST RESULTING FROM THE EARTHWORKS OPERATIONS IS KEPT TO A MINIMUM BY THE APPLICATION OF WATER TO THE WORKS AREA OR BY OTHER APPROVED METHODS AS DIRECTED BY THE SUPERINTENDENT DURING ALL PERIODS OF CONSTRUCTION.

# 1.5. WATER FOR CONSTRUCTION PURPOSES THE PRINCIPAL SHALL NOT SUPPLY WATER FOR USE IN CONSTRUCTION OF THE WORKS. THE BUILDER SHALL MAKE HIS OWN ARRANGEMENTS FOR OBTAINING WATER FOR THESE PURPOSES. WATER CAN BE PURCHASED FROM ROCKHAMPTON REGIONAL COUNCIL WITH PRIOR CONSENT.

# 1.6. REPLACEMENT OF UNSOUND MATERIAL IF DURING PROOF ROLLING OF THE FILL AREAS OR IN THE CONSTRUCTION OF CUTS, UNSOUND OR UNSUITABLE MATERIAL IS ENCOUNTERED WHICH IN THE OPINION OF THE SUPERINTENDENT IS NOT SUITABLE FOR INCLUSION IN THE FILL, THE BUILDER SHALL EXCAVATE AND REMOVE TO SPOIL AS DIRECTED ON SITE SUCH UNSUITABLE MATERIAL. THE BUILDER SHALL THEN REPLACE THE UNSOUND MATERIAL WITH SUITABLE MATERIAL DRAWN FROM THE CUTTING OPERATION ON SITE (IF AVAILABLE), OR

#### 1.7. REPLACEMENT OF TOPSOIL

FROM A SUITABLE SUPPLIER (MIN. CBR 15).

AT THE COMPLETION OF THE BULK EARTHWORKS, ROADWORKS AND SERVICES INSTALLATION AND FOLLOWING APPROVAL OF THE FINISHED SURFACE OF FOOTPATHS AND OTHER FILLED AREAS, THE BUILDER SHALL LIGHTLY TYNE UP THE FILL SURFACE AND REPLACES THE STOCKPILED TOPSOIL IN THE AREAS NOMINATED BY THE SUPERINTENDENT.

THE FINISHED SURFACE OF THE TOPSOIL SHALL BE LIGHTLY STATIC ROLLED AND WATERED TO PRODUCE AN EVEN SURFACE SUITABLE FOR SEEDING AND FERTILISING.

#### 2.0. PAVEMENT

GRAVEL QUANTITIES ARE BASED ON AN ASSUMED THICKNESS OF PAVEMENT. THE ACTUAL THICKNESS WILL BE DIRECTED BY THE SUPERINTENDENT FOLLOWING RECEIPT OF SUBGRADE TESTING. THE QUANTITIES SHOWN MAY BE VARIED BY THE SUPERINTENDENT, BY REDUCING, INCREASING OR OMITTING ANY GRAVEL QUANTITY. PAYMENT WILL BE MADE AT THE RELEVANT RATES IN THE PRICED BILL OF QUANTITIES ON THE CALCULATED QUANTITIES BASED ON DESIGN THICKNESS DETERMINED AFTER SUBGRADE TESTING.

#### 2.1. PAVEMENT MATERIAL

THE PAVEMENT MATERIAL SHALL BE WELL GRADED AND CONTAIN NO ORGANIC MATTER. ALL PAVEMENT MATERIAL MUST BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT. TEST RESULTS SHALL BE MADE AVAILABLE TO PROVE COMPLIANCE WITH THIS SPECIFICATION. THE BASE COURSE MATERIAL SHALL BE MR TYPE 2.1 AND THE SUB-BASE COURSE MATERIAL SHALL BE MR TYPE 2.3, OR 2.5 AS DEEMED IN THE PAVEMENT DESIGN

#### 2.2. SERVICES

NO PAVING MATERIAL SHALL BE PLACED IN AN AREA UNTIL ALL SERVICE CONDUITS, DRAINAGE PIPES, WATER AND SEWERAGE ROAD CROSSING HAVE BEEN COMPLETED, TESTED AND BACKFILLED UNLESS APPROVED BY THE SUPERINTENDENT.

#### 2.3. PAVEMENT COMPACTION

THE MINIMUM COMPACTION TEST REQUIREMENTS SHALL BE AS FOLLOWS:

AREA	MINIMUM COMPACTION REQUIREMENTS
BUILDING PADS	95%
SUBGRADE STANDARD	100%
SUB-BASE STANDARD	100%
BASE STANDARD	100%

#### 2.4. PROOF ROLLING

AFTER COMPACTION OF THE SUBGRADE IS COMPLETED, THE SUBGRADE SHALL BE PROOF ROLLED IN THE PRESENCE OF THE ENGINEER/SUPERINTENDENT IF REQUIRED AND ANY AREAS OF UNSUITABLE MATERIAL SHALL BE REMOVED AS DIRECTED.

#### 2.5. TOLERANCES

SURFACE LEVEL OF ROADS AND KERB AND CHANNEL SHALL BE AS FOLLOWS:

SUBGRADE SURFACE: +0mm TO -25mm
PAVEMENT THICKNESS: +20mm TO -10mm
WEARING COURSE THICKNESS: +10mm TO -0mm

THE TOLERANCE REQUIREMENTS ON THE FINISHED

#### FINISHED SURFACE

A) HORIZONTAL ALIGNMENT: <u>+</u>50mm

#### B) VERTICAL/GEOMETRIC TOLERANCE

) PRIMARY TOLERANCE:

<u>+</u>5mm

ii) DEVIATION FROM 3m STRAIGHT EDGE: ±5mm iii) CROSSFALL: +0.2%

IV) RATE OF CHANGE OF CROSSFALL: +0.02% PER METRE.

KERB & CHANNEL DESIRABLE MINIMUM GRADE: 0.5%
KERB & CHANNEL ABSOLUTE MINIMUM GRADE: 0.25%
KERB & CHANNEL MAXIMUM PONDING DEPTH: 5mm

#### 3.0. CONCRETE WORK

#### 3.1. GENERAL

CONCRETE WORK NOT SPECIFICALLY COVERED IN THIS JOB SPECIFICATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RELEVANT DRAWINGS AND/OR LOCAL AUTHORITY STANDARDS.

#### 3.2. CAST INSITU

ALL CAST INSITU CONCRETE WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS.

#### 3.3. CONCRETE STRENGTH

ALL CONCRETE WORK SHALL BE CLASS N32 UNLESS OTHERWISE SPECIFIED.

#### 4.0 JUNCTION WITH EXISTING ROADS

WHERE WORK UNDER THIS CONTRACT ABUTS THE EXISTING SURFACES, THE CONNECTION SHALL BE NEAT, SMOOTH AND WORKMANLIKE AND TO THE ENGINEER'S SATISFACTION. THE GRADING AND LEVELS AT SUCH JUNCTIONS AS SHOWN ON THE DRAWINGS ARE INDICATIVE ONLY AND SHALL BE CHANGED TO SUIT THE ACTUAL CONDITIONS IF AND AS MAY BE DIRECTED BY THE ENGINEER DURING CONSTRUCTION AND TO COUNCIL'S SATISFACTION.

#### 5.0. TESTING

IN GENERAL TESTING WILL BE REQUIRED TO BE CARRIED OUT IN ACCORDANCE WITH THE ATTACHED TABLE A.



ROCKHAMPTON HOCKEY ASSOCIATION





PROPOSED SYNTHETIC TURF HOCKEY FIELD

KALKA SHADES, NORTH ROCKHAMPTON, QLD

PRELIMINARY

GENERAL NOTES SHEET 1 OF 2

NOT FOR CONSTRUCTION PURPOSES PROJECT NO.

CT No. DRAWING No. REVIS RE15041 001

2

#### STORMWATER DRAINAGE

#### 1.1. PIPES

ALL PIPES SHALL BE PRECAST CONCRETE PIPE MANUFACTURED TO COMPLY WITH AS4058:1992 OR FIBRE REINFORCED CONCRETE PIPES TO COMPLY WITH AS4139. ALL PRECAST CONCRETE PIPES SHALL BE CLASS 2 UNLESS NOTED OTHERWISE ON THE DRAWINGS. ALL PIPES SHALL HAVE FLUSH JOINTS AND BE INSTALLED WITH EXTERNAL RUBBER BANDS UNLESS NOTED OTHERWISE ON THE DRAWINGS.

ALL POLYVINYL CHLORIDE (UPVC) PIPES AND FITTINGS TO COMPLY WITH AS 1254, AS/NZS 1260, AS 1273, AS/NZS 1477, AS/NZS 2179.2 AND AS 2032.

ALL PIPES INSTALLED SHALL BE NEW AND FREE FROM ANY DAMAGE.

#### 2.0. EXCAVATION AND BACKFILLING

THE PIPE TRENCHES SHALL BE EXCAVATED TO ALLOW A MINIMUM 100MM OF APPROVED BEDDING TO THE BOTTOM AND ALL SIDE AND TOP OF THE PIPE. ALL BEDDING, SURROUNDS, AND BACKFILL MATERIAL SHALL BE COMPACTED IN MAXIMUM 150MM LAYERS AND A MINIMUM 95% MAXIMUM DRY DENSITY AS DETERMINED BY AS 1289 E.1.1 OR DENSITY INDEX OF MINIMUM 70% AS DETERMINED BY AS 1289 E.G.1. ALL BACKFILL UNDER ROAD PAVEMENTS SHALL HAVE A MINIMUM OF 97% MAXIMUM DRY DENSITY AS DETERMINED BY AS 1289 F.1.1.

#### 3.0. LAYING AND JOINTING

PIPE LAYING SHALL BEGIN AT THE DOWN STREAM END OF THE LINE WITH THE GROOVED ENDS OF THE PIPE FACING UPSTREAM. THE END OF THE PIPE SHALL BE CLEANED PRIOR TO THE INSTALLATION OF THE EXTERNAL RUBBER BAND. LIFTING HOLES IN PIPES SHALL BE SECURELY PLUGGED WITH MANUFACTURER PLUGS OR DRY PACK MORTAR PRIOR TO BACKFILLING. ALL DRAINAGE LINES SHALL BE CONSTRUCTED WITH A TOLERANCE OF + 15mm IN LINE AND LEVEL FROM THE ALIGNMENT SHOWN ON THE DRAWINGS OVER ANY 30m LENGTH. ALL PIPES MUST FALL IN THE REQUIRED DIRECTION.

#### 4.0. CONCRETE WORK

CONCRETE WORK, SIDE DRAINS, SEEPAGE DRAINS, AND OTHER ITEMS NOT SPECIFICALLY COVERED IN THIS JOBS SPECIFICATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RELEVANT DRAWINGS AND/OR ATTACHED SPECIFICATION. SIDE DRAINS AND SEEPAGE DRAINS SHALL BE CONSTRUCTED WHERE SHOWN ON THE DRAWINGS OR WHERE DIRECTED BY THE SUPERINTENDENT.

#### 4.1. CAST INSITU

ALL CAST INSITU CONCRETE WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS. NOTWITHSTANDING ANYTHING TO THE CONTRARY, NO SEPARATE PAYMENT WILL BE MADE FOR REINFORCING STEEL AND THE COST SHALL BE DEEMED TO BE INCLUDED IN THE VARIOUS CONCRETE ITEMS.

ALL CONCRETE WORK SHALL BE CLASS N32 UNLESS OTHERWISE SPECIFIED.

#### 5.0. INLETS

ALL ROAD GULLIES SHALL BE PRECAST CONCRETE PITS OR APPROVED EQUIVALENT AND SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS' SPECIFICATIONS. ANY INSITU CONCRETE WORK SHALL COMPLY WITH AS3600.

ALL FIELD GULLIES SHALL BE INSTALLED IN ACCORDANCE WITH THE DRAWINGS AND THE MANUFACTURERS' SPECIFICATIONS. ANY INSITU CONCRETE WORK SHALL COMPLY WITH AS3600.

#### 6.0. KERB AND CHANNEL

ALL KERB AND CHANNEL SHALL BE INSTALLED WITH AN APPROVED SLIP FORM EXTRUDER TO THE SATISFACTION OF THE SUPERINTENDENT. THE KERB AND CHANNEL PROFILE AND OTHER KERB ONLY PROFILES SHALL COMPLY WITH THE DRAWINGS. THE EXTRUDED PROFILE SHALL HAVE TOOLED JOINTS AT MAXIMUM 5.0M CENTRES. ALL KERB AND CHANNEL SHALL BE SUBJECTED TO A WATER TEST WITHIN 24 HOURS OF PLACEMENT AND ANY SECTION PONDING GREATER THAN 5mm 20 MINUTES AFTER TESTING SHALL BE RECTIFIED IN AN APPROVED MANNER AND THE COST SHALL BE BORNE BY THE BUILDER. ALL WATER TESTING SHALL BE IN THE PRESENCE OF THE ENGINEER.

#### QUALITY ASSURANCE TESTING TABLE A:

#### SUBGRADE

#### FIELD DENSITY

1 TEST PER 75m OF ROADWAY OR AS NOMINATED BY THE ENGINEER.

#### SOAKED CBR

1 ON EACH REPRESENTATIVE SAMPLE AS DIRECTED BY THE ENGINEER.

#### **PREPARATION**

INSPECTION AND APPROVAL BY ENGINEER PRIOR TO COMMENCEMENT OF PAVING.

#### SURVEY LEVELS

PROVIDED BY BUILDER AT DESIGN CHAINAGES PRIOR TO JOINT COUNCIL AND ENGINEER INSPECTION.

#### SUB-BASE

#### PARTICLE SIZE DISTRIBUTION

1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. DISTRIBUTION

SAMPLE IF REQUESTED.

#### ATTERBERG LIMITS

1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. SOAKED CBR1

#### 1 PER SOURCE.

FIELD DENSITY

1 TEST PER 75m OF ROADWAY OR AS NOMINATED BY THE ENGINEER.

CONFIRMATION OF INSITU COMPACTED DEPTH BY LEVEL SURVEY PROVIDED BY THE BUILDER AT DESIGN CHAINAGES PRIOR TO INSPECTION BY ENGINEER.

#### BASE

#### PARTICLE SIZE DISTRIBUTION

1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. ATTERBERG LIMITS

1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED.

SOAKED CBR

#### 1 PFR SOURCE. FIFI D DENSITY

1 TEST PER 75m OF ROADWAY OR AS NOMINATED BY THE ENGINEER.

CONFIRMATION OF INSITU COMPACTED DEPTH BY LEVEL SURVEYPROVIDED BY THE BUILDER AT DESIGN CHAINAGES PRIOR TO INSPECTION BY ENGINEER.

#### **BUILDING PAD**

COMPACTION FIELD DENSITY TEST WITH LEVEL 1 SUPERVISION AS DEFINED IN AS 3798-1990 TESTING FREQUENCY AS DETERMINED BY AS 3798-1990 SECTION 8, BUT GENERALLY 1 PER 200mm LAYER OF 200M3 BY APPROVAL OF ENGINEER.

ASPHALT TESTS BY MANUFACTURER AGGREGATE GRADING BITUMEN CONTENT COMPACTED DENSITY MAXIMUM DENSITY STABILITY FI NW STIFFNESS VOIDS IN AGGREGATE VOIDS FILLED 1 SERIES OF TESTS PER 1000m3 LAID.

#### **STORMWATER**

SAND BEDDING, ALIGNMENT AND LEVEL INSPECTION AND APPROVAL BY SUPERINTENDENT OF BEDDING AND LAYING OF STORMWATER PIPE. LEVELS SUPPLIED BY BUILDER AND APPROVED BY SUPERINTENDENT.

#### TRENCH BACKFILL

1 FIELD DENSITY TEST PER SECTION OF TRENCH. AS-CONSTRUCTED SURVEY INFORMATION TO THE APPROVED OF THE SUPERINTENDENT.

REVISION DATE ISSUE DESCRIPTION DRAWN DESIGNED CHECKED 04/2016 FOR CO-ORDINATIO COPYRIGHT his document and the copyright contained in this document is the property of alibre Consulting and must not be used, copied, reproduced, modified, adapted o

**ROCKHAMPTON HOCKEY ASSOCIATION** 



PROPOSED SYNTHETIC TURF **HOCKEY FIELD** 

KALKA SHADES, NORTH **ROCKHAMPTON, QLD** 


**PRELIMINARY** 

NOT FOR CONSTRUCTION PURPOSES


**GENERAL NOTES** 

SHEET 2 OF 2

2 R15041 002




#### **LEGEND**



#### **NOTES**

- 1. ALL BATTERS TO BE 1 ON 4 MAX UNLESS OTHERWISE SPECIFIED.
- 2 THE CONTRACTOR SHALL ESTABLISH THE EXTENT AND LOCATION OF ALL EXISTING SERVICES WITHIN OR ADJACENT TO THE WORKS AREA. ALL SERVICES SHALL BE PROTECTED AGAINST ACCIDENTAL DAMAGE DURING CONSTRUCTION OF THE WORKS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS INCURRED BY DAMAGE TO EXISTING SERVICES.



1:1000 (A3)



REVISION	DATE	ISSUE DESCRIPTION	DRAWN	DESIGNED	CHECKED	
1	01/2016	PRELIMINARY	PL	CS	CS	
2	04/2016	FOR CO-ORDINATION	PL	JA	CS	
						© COPYRIGHT
						This document and the cop

ASSOCIATION







**HOCKEY FIELD** 


KALKA SHADES, NORTH **ROCKHAMPTON, QLD** 


**EXISTING SITE PLAN** 

NOT FOR CONSTRUCTION PURPOSES R15041 003 2












TYPICAL SECTION A-A
SCALE 1:100 (A3)




## PRELIMINARY

R	EVISION DATE	ISSUE DESCRIPTION	DRAWN	DESIGNED	CHECKED		ROCKHAMPTON HOCKEY		Calibre Consulting (QLD) Pty Ltd	PROJECT		DRAWING TITLE		l
	1 01/2016	PRELIMINARY	PL	CS	CS				Consulting Engineers, Structural - Civil	PROPOSED SYNTHETIC TURF		SITE SECTIONS	PLAN	,
	2 04/2016	FOR CO-ORDINATION	PL	JA	CS		ASSOCIATION		238 Quay Street, Rockhampton	HOCKEY FIELD	PRELIMINARY			1
								- 1:1	Queensland 4700, Australia					
							ROCKHAMPTON HOCKEY	Calling	Tel: +61 7 4931 0777					
						© COPYRIGHT	HOCKET		www.calibreconsulting.co	KALKA SHADES, NORTH	NOT FOR CONSTRUCTION PURPOSES	DD C YOUR V	PRANTING N	PERMITTON
						This document and the convrisht contained in this document is the property of		CONSULTING	•	ROCKHAMPTON, QLD	NOT FOR CONSTRUCTION FOR COLS	PROJECT No.	DRAWING No.	KEVISION
						Calibre Consulting and must not be used, copied, reproduced, modified, adapted or			NEW ZEALAND MELBOURNE PERTH	NOCKHAWIFTON, QLD		R15041	201	۱ و
						developed wholly or in part without the prior written consent of Calibre Consulting.		ROCKHAMPTON SING	APORE SUNSHINE COAST SYDNEY			K13041	201	4







-HEIGHT OF WEIR LEVEL.



TYPICAL SECTION THRU BOOT WASH SCALE 1:25 (A3)


TYPICAL BUND WALL DETAIL SCALE 1:25 (A3)







EMERGENCY SERVICES/MAINTENANCE ACCESS TRACK TYPICAL SECTION SCALE 1:50 (A3)

TYPICAL PRECAST CONCRETE PANELS SCALE 1:50 (A3)







SCALE 1:100 (A3)

CONCRETE BOUNDARY BARRIER TYPICAL SECTION SCALE 1:50 (A3)

CONCRETE BOUNDARY BARRIER TYPICAL DETAIL SCALE 1:2

PR	MIN	AR	Y

REVISION	DATE	ISSUE DESCRIPTION	DRAWN	DESIGNED	CHECKED		CLIENT
1	01/2016	PRELIMINARY	PL	CS	CS		
2	04/2016	FOR CO-ORDINATION	PL	JA	CS		
						© COPYRIGHT	
						This document and the copyright contained in this document is the property of	
						Calibre Consulting and must not be used, copied, reproduced, modified, adapted or	

-SL62 CENTRALLY PLACED

CONCRETE INVERT DETAIL N.T.S

> **ROCKHAMPTON HOCKEY** ASSOCIATION




	ore Consulting (QLD) Pty Ltd ulting Engineers, Structural - Ci	vil
	Quay Street, Rockhampton	
	ensland 4700, Australia	
	61 7 4931 0777	
	+61 7 4921 4866	
	.calibreconsulting.co	
CONSULTING		
BRISBANE CANBERRA NEW ZE		
ROCKHAMPTON SINGAPORE	SUNSHINE COAST SYDN	EY


PROPOSED SYNTHETIC TURF **HOCKEY FIELD** 


KALKA SHADES, NORTH **ROCKHAMPTON, QLD** 

**PRELIMINARY** NOT FOR CONSTRUCTION PURPOSES

PROJECT No. R15041	DRAWING No.	REVISION 2







		LOCATION			TIME		SUB-CAT	CHMENT R	UNOFF				INLET D	DESIGN							D	RAIN DESIG	N							HEAD	DLOSSES	S					PAR	T FULL			DES	SIGN LEVE	LS		
					tc	I	C10	C A	C×A	+CA	Q				Qg	Qь		tc	1 .	CA.	Qt (	Qm Qs	Qp	L	S		٧	T		V2/2g	Ku	hu	Kl	hl Kw	hw	Sf	hf		Vp				$\perp$		$\perp$
DESIGN ARI	STRUCTURE No.	DRAIN SECTION	SUB-CATCHMENTS Contributing	LAND USE SLOPE OF CATCHMENT	SUB-CATCHMENT	RAINFALL INTENSITY	10yr RUNOFF CO-EFFICIENT CO-EFFICIENT	OF RUNOFF SUB-CATCHMENT AREA		SUM OF (C × A)	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS) ROAD GRADE AT INLET	MINOR FLOW ROAD CAPACITY	INLET TYPE	FLOW INTO INLET	BYPASS FLOW	BYPASS Structure no.	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	(C × A)	MAJOR TOTAL FLOW MAJOR SLIREACE FLOW	CAPACITY MAJOR SURFACE FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE / BOX Dimensions (CLASS)	FLOW VELOCITY FULL (PIPE GRADE VELOCITY)	TIME OF FLOW IN REACH STRICTURE	CHART No. STRUCTURE RATIOS FOR YC. VALUE CALCULATIONS	VELOCITY HEAD	U/S HEADLOSS Coefficient	U/S PIPE STRUCT. HEADLOSS	LAT. HEADLOSS CO-EFFICIENT	HEADLOSS W.S.E	CU-EFFICIENT CHANGE IN W.S.E	PIPE FRICTION SI OPF	PIPE FRICTION HEADLOSS (L × Sf)	ОЕРТН	VELOCITY	OBVERT LEVELS DRAIN SECTION	H.G.L	UPSIREAM H.G.L LAT. H.G.L	W.S.E.	SURFACE OR K&C	STRUCTURE No.
yrs				%	min			ha			l/s		l/s		l/s l	/s		min m			/s l/	/s l/s	l/s	m				min		m		m		m	m			m				m m			
1 100	1/2	1/2 to 2/2	1/2		5.00 5.00	104 322	0	.72 0.025 .99 0.025	0.018 0.025	0.018 0.025	5 22	5 0.20		101	5	0	2/2	5.00 5.00	104 322	0.018 0.025	22	(Pi	5 se flow= Gra	25.250 te flow)	0.50	150(U)	0.27 (0.73)	0.42	Qg 0.005 Qo 0.005 Do 150 CHRT 32: Vo2/2gDo 0.02 H/Do 0.90 Kg side flow 6.62 end flow 4.81	0.004	6.62	0.024		6.62	2 0.024	0.07	0.017		- T	7.015 7. 6.889 7.	154 7.1 137	.178	7.178	7.182	1/2
1 100	2/2	2/2 to 3/2	1/2;2/2		5.00 5.00	104 322	0	.72 0.079 .99 0.079		0.057 0.078	16 70	16 0.20		101	16	0	3/2		101 313	0.075 0.103	90	(Pipe flo	20 v= Sum upst		0.50 ws)	225(U)	0.45 (0.99)	0.42	Qg 0.016 Qo 0.020 Do 225 CHART 33 Angle 1 S/Do 2.5 Du/Do 0.67 Qg/Qo 0.76 K 2.17 S/Do 1.75 cor 0.57 Ku 2.74 Kw 2.74	0.010	2.74	0.028		2.74	0.028	0.10	0.026		6	6.956 7. 6.830 7.	109 7.1 083	137	7.137	7.139	2/2
1 100	3/2	3/2 to 4/2	1/2;2/2;3/2		5.00 5.00	104 322	0	.72 0.099 .99 0.099	0.068 0.094	0.068 0.094	20 84	20 0.20		101	20	0	4/2		99 304	0.143 0.197	166	(Pipe flo	39 v= Sum upst		0.50 ws)	225(U)	0.85 (0.99)	0.34	Qg 0.019 Qo 0.039 Do 225 CHART 33 Angle 1 S/Do 2.5 Du//Do 1.00 Qg/Qo 0.49 K 1.49 S/Do 2.13 cor 0.14 Ku 1.63 Kw 1.63	0.037	1.63	0.060		1.63	0.060	0.37	0.076		6	6.810 7. 6.708 6.	023 7.0 947	083	7.083	7.082	3/2
1 100	4/2	4/2 to 5/2	1/2;2/2;3/2;4/2		5.00 5.00	104 322	0	.72 0.074 .99 0.074	0.056 0.077	0.056 0.077	16 69	16 0.20		101	16	0	5/2	6.18 6.18	97 298	0.199 0.274	227	(Pipe flo	53 v= Sum upst		0.50 ws)	300(U)	0.73 (1.15)	0.51	Qg 0.015 Qo 0.053 Do 300 CHART 33 Angle 1 S/Do 2.5 Du/Do 0.75 Qg/Qo 0.28 K 0.31 S/Do 1.65 cor 0.25 Ku 0.56 Kw 0.56	0.027	0.56	0.015		0.56	5 0.015	0.20	0.062		6	6.751 6. 6.597 6.	932 6.9 870	4.7	6.947	7.048	3 4/2
1 100	5/2	5/2 to 5/1	1/2;2/2;3/2;4/2;5/2		5.00 5.00	104 322	0	.72 0.166 .99 0.166	0.120 0.164	0.120 0.164	35 147 FL01	35 0.00 W WIDTH/DEPTH 0.010D		1750.15	35	0			94 289	0.319 0.438	352	(Pipe flo	v= Sum upst	61.851 atten flo		300(U)	1.14 (1.15)	0.90		0.066	0.76	0.050		1.13	0.079	0.49	0.305		6	6.577 6. 6.268 6.	820 6.8 515	870	6.895	6.978	5/2
1 100	1/1	1/1 to 2/1	1/1		5.00 5.00	104 322	0	.72 0.025 .99 0.025	0.018 0.025	0.018 0.025	5 22	5 0.20		101	5	0	2/1	5.00 5.00	104 322	0.018 0.025	22	(Pi	5 se flow= Gra	25.251 te flow)	0.50	150(U)	0.27 (0.73)	0.42	Qg 0.005 Qo 0.005 Do 150 CHRT 32: Vo2//2gDo 0.02 H/Do 0.75 Kg side flow 7.22 end flow 5.21	0.004	7.22	0.027		7.22	2 0.027	0.07	0.017		6	6.686 6. 6.560 6.	802 6.8 785	129	6.829	7.183	1/1
1 100	2/1	2/1 to 3/1	1/1;2/1		5.00 5.00	104 322	0	.72 0.074 .99 0.074	3 0.056 3 0.077	0.056 0.077	16 69	16 0.20		101	16	0		5.42 5.42	101 313	0.074 0.102	89	Pipe flo	20 v= Sum upst		0.50 ws)	225(U)	0.45 (0.99)	0.42	Qg 0.016 Qo 0.020 Do 225 CHART 33 Angle 1 S/Do 2.5 Du/Do 0.67 Qg/Qo 0.76 K 2.17 S/Do 1.66 cor 0.67 Ku 2.84 Kw 2.84	0.010	2.84	0.029		2.84	0.029	0.10	0.026		6	6.627 6. 6.501 6.	756 6.7 730	85	6.785	7.139	2/1
1 100	3/1	3/1 to 4/1	1/1;2/1;3/1		5.00 5.00	104 322	0		0.068 0.094		20 84	20 0.20		101	20	0			99 304	0.142 0.196	166	(Pipe flo	39 v= Sum upst	20.376 ratten flo		225(U)	0.85 (0.99)	0.34	Qg 0.019 Qo 0.039 Do 225 CHART 33 Angle 1 S/Do 2.5 Du/Do 1.00 Qg/Qo 0.49 K 1.49 S/Do 2.03 cor 0.18 Ku 1.67 Kw 1.67	0.037	1.67	0.061		1.67	0.06	0.37	0.076			6.481 6. 6.379 6.	669 6.7 593	30	6.730	7.082	! 3/1
1 100	4/1	4/1 to 5/1	1/1;2/1;3/1;4/1		5.00 5.00	104 322		.72 0.074 .99 0.074	0.056 0.077		16 69	16 0.20		101	16	0				0.198 0.273	226	(Pipe flo	53 v= Sum upst		0.50 ws)	300(U)	0.73 (1.15)	0.51	Qg 0.015 Qo 0.053 Do 300 CHART 33 Angle 1 S/Do 2.5 Du/Do 0.75 Qg/Qo 0.28 K 0.31 S/Do 1.56 cor 0.28 K 0.59 Kw 0.59	0.027	0.59	0.016		0.59	0.016	0.20	0.062		6	6.421 6. 6.268 6.	577 6.5 515	93	6.593	7.047	4/1
1 100	5/1	5/1 to 6/1	1/2;2/2;3/2;4/2;5/2; /1;2/1;3/1;4/1;5/1	1	5.00 5.00	104 322	0	.72 0.166 .99 0.166	0.120 0.164	0.120 0.164	147	35 0.00 W WIDTH/DEPTH 0.010D	l I	1750.15	35	0		7.59 7.59	90 276	0.637 0.875	671	(Pipe flo	159 v= Sum upst	118.106 ratten flo	0.30 ws)	450(2)	1.00 (0.98)	1.97		0.051	0.74	0.038		0.74	0.038	0.31	0.369		6	6.394 6. 6.039 6.	477 6.5 108	i15	6.515	6.977	5/1
1 100	6/1	6/1 to 7/1	1/2;2/2;3/2;4/2;5/2; /1;2/1;3/1;4/1;5/1	1										24				9.56 9.56	82 252	0.637 0.875	612	Pipe flo	159 v= Sum upst		ws)	450(2)	(0.98)	0.25	Qo 0.159 Do 450 CHART 50 Du/Do100 alpha 76 K'w 0.29 Vu 1.00 WSE 0.10 Ku 1.70 Kw 1.99	0.051	1.70	0.087		1.99	0.102	0.31	0.046			6.019 6. 5.975 5.	021 6.1 975	.108	6.123	6.308	6/1

STORMWATER CALCULATIONS TABLE

PRELIMINARY

REVISION	DATE	ISSUE DESCRIPTION	DRAWN	DESIGNED	CHECKED	
1	01/2016	PRELIMINARY	PL	CS	CS	
2	04/2016	FOR CO-ORDINATION	PL	JA	CS	
						© COPYRIGHT
						This document and the copyright contained in this document is the property of
						Calibre Consulting and must not be used, copied, reproduced, modified, adapted or developed wholly or in part without the prior written consent of Calibre Consulting.

ROCKHAMPTON HOCKEY
ASSOCIATION



PROPOSED SYNTHETIC TURF HOCKEY FIELD KALKA SHADES, NORTH

ROCKHAMPTON, QLD

PRELIMINARY


NOT FOR CONSTRUCTION PURPOSES

STORMWATER CALCULATION TABLE


303


R15041

2



SCALE 1:50 (A3)





### PRELIMINARY

ROCKHAMPTON HOCKEY
ASSOCIATION
ROCKHAMPTON
HOCKEY




PROPOSED SYNTHETIC TURF HOCKEY FIELD


KALKA SHADES, NORTH ROCKHAMPTON, QLD


PREL	IMINARY
------	---------


STORMWATER DETAILS PLAN

NOT FOR CONSTRUCTION PURPOSES PROJECT No. DRAWING No. REVESION R15041 304 2









# Appendix B

**GIS Mapping** 

