PARAGON Consulting Engineers Pty Ltd

4-Lot Subdivision, 20 Withers Street, Kawana 4701 (Lot 101 on SP329781)

Engineering Report

To Accompany the Reconfiguring of a Lot Application

For Apollo Care

September 2023

Project Reference: 2477-02

Revision B

ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS These plans are approved subject to the current conditions of approval associated with Development Permit No.: D/81-2023 Dated: 25 January 2024

Written By:

Paragon Consulting Engineers Pty Ltd P.O. Box 1175, Mackay, QLD, 4740 Telephone: (07) 4957 7330 Facsimile: (07) 4957 7334 E-Mail: mail@paragonce.com

Document Control

Rev No	Date	Revision Details	Author	Reviewer	Approver
A	18/09/23	For Council Approval	RMH	BKP	BKP RPEQ: 19819
В	27/09/23	Lot Numbers Amended	Alsk	p-lunil	6-10mil

Contents

Section	1		Page
1.0	Introduction		
2.0	Roadworks		
	2.1	Access Easements	2
	2.2	Parking	4
	2.3	Footpaths	4
	2.4	Kerb and Channel	4
3.0	Sto	rmwater Management	5
	3.1	Overland Flow Paths	5
	3.2	Underground Drainage	5
	3.3	Roof Drainage	6
	3.4	Stormwater Detention	6
4.0	0 Water Reticulation		7
	4.1	Water Service Connections	7
5.0	Sev	ver Reticulation	8
	5.1	Sewer Reticulation	8
	5.2	Sewer Easements	8
6.0	Gas	Reticulation	10
	6.1	Gas Easement	10
7.0	Ele	ctrical and Telecommunications Services	10
	7.1	General	10
Refe	References		11

Appendix A – Preliminary Layout Drawings	
2477-02-001 – Existing Site Features	12
2477-02-002 – Proposed Site Layout	12
Appendix B – Photographs	13
Appendix C – DBYD Search Results	20
Appendix D – Existing Services Drawings	21
Appendix E – Detailed Site Survey	22

1.0 Introduction

This Report has been prepared by Paragon Consulting Engineers Pty Ltd on behalf of Apollo Care to accompany the Development Application for Reconfiguration of a Lot 4pplication for the proposed 4-Lot Subdivision at 20 Withers Street, Kawana, QLD.

The subject land is described as Lot 101 on SP329781. The plan area of the subject land is approximately 4.86Ha. It is proposed that the subject land be subdivided as indicated on the preliminary Drawing No. 2477-02-002. Refer to Appendix A for further details.

The detailed design of the proposed earthworks, roadworks, access and services will be undertaken in accordance with the requirements as set out in the Rockhampton Region Planning Scheme and the Capricorn Municipal Development Guidelines.

2.0 Roadworks

2.1 Access Easements

The existing site (Lot 101 on SP329781) has four distinct areas, which are as follows:

- Villas, which are located on proposed Lot 1
- Relocated cottages, which are located on proposed Lot 2
- Units, which are located on proposed Lot 3
- Aged care facility, which is located on proposed Lot 4

Our subdivision site access assessment, that is based on the existing facilities is outlined in the following subsections.

Access easement for proposed Lot 1

The existing villas within proposed Lot 1 obtain vehicle access from Alexandra Street. Vehicles travelling to proposed Lot 1 need to drive through proposed Lot 2 in order to reach proposed Lot 1. Therefore, within proposed Lot 2 an access easement will need to be placed over the pavement and associated verge from Alexandra Street through to the southern boundary of proposed Lot 2.

Access easement for proposed Lot 2

The existing cottages within proposed Lot 2 obtain vehicle access from Alexandra Street. The existing vehicle turnaround facility for the cottages is located in the eastern portion of proposed Lot 4. Therefore, an access easement will need to be placed over the turnaround facility and associated vehicle access within Lot 4.

The existing turnaround facility is currently unsealed with no accompanying signage. It is proposed that road edge guide posts are installed to better define the turnaround area. Appropriate road signage, such as 'No Parking' signs shall also be installed to ensure that the turnaround area is not used for parking. An access easement shall be placed over the road pavement, associated verge and turnaround area facility within proposed Lot 4.



Figure 1 - Existing turnaround facility in the north-eastern portion of the site

Within the eastern portion of proposed Lot 4 there are currently ten cottages. On the current plan of development, a potential aged care build-out (of up to an additional 40 residence) has been designated on the eastern portion of proposed Lot 4. A separate application will be lodged for the aged care facility expansion. This application will need to identify any changes required to the vehicle access easement and turnaround area that services proposed Lot 2.

Access easement for proposed Lot 3

The existing units within proposed Lot 3 obtain vehicle access from Alexandra Street. Vehicles travelling to proposed Lot 3 need to drive through proposed Lot 2 in order to reach proposed Lot 3. Therefore, within proposed Lot 2 an access easement will need to be placed over the pavement from Alexandra Street through to the southern boundary of proposed Lot 2.

Access easement for proposed Lot 4

The existing aged care facility within proposed Lot 4 has a sealed parking area that adjoins Withers Street. The parking area has separate entry and exit vehicle cross-overs to Withers Street. The existing parking area does not need alterations for the proposed four-lot subdivision.

Proposed Lot 4 has a secondary 'back-of-house' type access from Alexandra Street that traverses proposed Lot 2. Therefore, within proposed Lot 2 an access easement will need to be placed over the pavement from Alexandra Street through to proposed Lot 4.

2.2 Parking

Proposed Lot 1 has 13 visitor parking facilities plus one disabled parking bay with shared zone. Each villa has its own driveway and sheltered parking spaces.

Proposed Lots 2 and 3 have no visible formal parking facilities. However, they have unsealed areas that are currently being used for vehicle parking.

The age care facility within proposed Lot 4 has a formal sealed parking facility for 22 vehicles, based on aerial photographs. These parking bays are located off Withers Street at the entrance to the facility.

2.3 Footpaths

A section of footpath is located along the southern corner of Alexandra Street running from the Farm Street intersection to the Alexandrea Street entrance leading to Proposed Lot 2.

During a site inspection in December 2022 works were being carried out to install a new footpath along Farm Street for the full length of the block.

Proposed Lot 2,3 & 4 all have internal footpaths without connections to the adjoining streets.

2.4 Kerb and Channel

All three adjoining streets (Alexandra, Farm & Wither Street) have barrier kerb and channels.

3.0 Stormwater Management

3.1 Overland Flow Paths

As of writing this report, insufficient survey levels information is available to fully assess the overland flow paths.

The Villas located inside Proposed Lot 1 falls towards the centre of the road field inlet pits.

For Proposed Lot 2 the overland flow path falls away from Alexandra Street towards Proposed Lots 3 and 4.

Based on the footpath levels along the units located in Proposed Lot 3 the overland flow path falls towards Withers Street.

Based on the existing surface levels information available, Proposed Lot 4 appears to flow internally towards grated inlets pits inside the age care facility. The carpark for the facility also flows towards the internal gully pits located centrally.

During major rainfall events, it is likely that the stormwater drainage infrastructure within the subject site would become inundated. Once the underground stormwater drainage system has reached its capacity, excess stormwater flows will travel overland, with the overland flow from the southern portion of the site discharging into the basin and the northern portion of the site overflowing and contributing to the Withers Street Road reserve.

3.2 Underground Drainage

Proposed Lot 1 has seven surveyed field inlets within the roadways, which feed into the stormwater basin that is located in Proposed Lot 3.

Proposed Lot 2 has no underground drainage surveyed on site. The overland flow shall be covered by the proposed access / stormwater easement inside the lot. This proposed easement shall cease when the east to west running stormwater easement is reached inside proposed Lot 3.

Proposed Lot 3 houses a stormwater basin which shall remain. An appropriately sized stormwater easement shall be placed over the stormwater basin.

The underground drainage for the Carpark located in proposed Lot 4 will flow to an outlet located to the south west boundary of proposed lot 3. This outlet then travels via an open channel into the headwall perpendicular to Withers Street.

Refer to drawing 2477-02-003 within Appendix A for further details regarding the proposed stormwater drainage easements.

3.3 Roof Drainage

It is presumed that roof water from all of the existing buildings currently discharge into the stormwater basin, that is located on Proposed Lot 3.

It should be noted that the standalone housing (Relocated cottages) along Alexandra Street has no detected stormwater, hence the roof drainage outlets onto ground level. Which as noted prior, falls towards the access street, which in turn falls towards the stormwater basin with Proposed Lot 3.

3.4 Stormwater Detention

The existing on-site detention basin located in Proposed Lot 3 shall remain. As part of future development applications, any further increases in impervious area on site shall be assessed to determine if further stormwater detention infrastructure is required.

4.0 Water Reticulation

4.1 Water Service Connections

Proposed Lot 1 houses a water meter on the Farm Street frontage.

Proposed Lot 2 requires a new water meter to be installed on the Alexandra Street frontage, as the existing meter servicing the detached cottages will be located on Proposed Lot 4's Alexandra Street frontage.

The units located inside Proposed Lot 3 are currently being serviced by the water meter located on the Withers Street frontage.

Proposed Lot 4 has two water meters, one is located on the Withers Street frontage and the other is located on the Alexandra Street frontage. The Withers Street water meter services the age care facility, while the Alexandra Street water meter services the detached housings in the Relocated Cottages.

Once the aforementioned changes have been made for Proposed Lot 2, each lot shall have an independent water connection.

5.0 Sewer Reticulation

5.1 Sewer Reticulation

Proposed Lot 1 is currently serviced by an existing public sewer main (council asset). Refer to Woollam Construction Drw HS-01 (Project No Q5398), in Appendix D for further details.

Proposed Lot 2 is currently serviced via an existing public sewer main (council asset). Refer to Rockhampton Regional Council Drw DS1684(9) (Plan SP267888/101), in Appendix D for further details.

Proposed Lot 3 is serviced via an existing public sewer main (council asset) that is located on the southern side of the existing building on Proposed Lot 3. A sewer easement will be required over the council owned sewer mains. Refer to Rockhampton Regional Council Drw DS1684 (Plan SP267888/101), in Appendix D for further details.

Proposed Lot 4 is serviced via an existing private 150mmØ sewer main running from north to southeast along the Alexandra St Side of the property. Refer to Gary J.Garnett & Associates Pty Ltd Drw 1817/12/H1 Issue D, in Appendix D for further details.

The existing system is functional and has independent connections to each lot, and therefore shall remain as is. Refer to drawing 2477-02-002 within Appendix A for further details.

5.2 Sewer Easements

A total of four sewer easement are proposed for the site to protect the existing sewer infrastructure.

The public sewer main (council asset) that runs from north to southeast parallel with Alexandrea Street requires a 4m easement as it is a council asset that is located on private land.

Proposed Lot 3 has a public sewer main (council asset) that will require a 4m easement as it is a council asset that is located on private land.

The private sewer main that runs along the Withers Street boundary requires a 4m easement that shall be located centrally over the existing main. The easement shall begin at the northern boundary of Lot 4 and follow the main along the northern boundary and along Withers Street before terminating at the southern end of the private sewer main, where it connects to the public sewer main (council asset).

Lastly the public sewer main (council asset) running from through Proposed Lot 3 requires an additional easement from the lot 1 boundary though the stormwater basin to the existing easement as it is a council asset that is located on private land.

6.0 Gas Reticulation

6.1 Gas Easement

An existing gas line has been located running from the south easter corner of the kitchen/ laundry units to Alexandra Street. This line will require an easement centrally located over the gas main. The width of this gas line will need to be in accordance to the asset owners' requirements.

Refer to drawing 2477-02-002 within Appendix A for further details.

7.0 Electrical and Telecommunications Services

7.1 General


An independent review shall by undertaken by a suitably qualified electrical engineer to determine the requirements for any electrical and telecommunication easements, service upgrades and/or alterations to suit the proposed subdivision.


References

- 1. Rockhampton Region Planning Scheme Policies 2015
- 2. Rockhampton Regional Council's Interactive Mapping January 2023
- 3. Queensland Urban Drainage Manual, Fourth Edition 2016

Appendix A – Preliminary Layout Drawings

2477-02-001 – Existing Site Features 2477-02-002 – Proposed Site Layout





Appendix B – Photographs



Age care facility carpark, looking north towards the main entrance



Age care facility carpark, looking west



Age care facility water meter along Withers Street



Kitchen / Laundry units within Proposed Lot 3



Proposed Lot 3 water meter on Withers Street frontage



Age care facility drainage outlet. The headwall in the centre of the photo discharges to the headwall on the lefthand side of the photo (these stormwater flows bypass the stormwater basin)



The stormwater headwall that captures stormwater discharge from the age care facilities underground stormwater drainage network



Existing stormwater basin located in Proposed Lot 3



Photo looking along the Alexandra Street property boundary, looking south



Photo looking along the Farm Street property boundary, looking east




Road profile of access road inside Proposed Lot 1, looking east



Unsealed access at the west boundary of Proposed Lot 2, looking south

Appendix C – DBYD Search Results



Plans generated 17/11/2022 by Pelicancorp TicketAccess Software | www.pelicancorp.com

AU.AARNet - Overview Plan.docx (29 June 2018)




Paper size A3 Map has been designed to be reproduced in colour

AU.Ergon Energy (QLD) - Response Plan.docx (03 Sep 2021)


Plans generated 17/11/2022 by Pelicancorp TicketAccess Software | www.pelicancorp.com

A	DBYD	Ţ.	Planned Cross Bonding Link Box - New/Updated Planned Cross Bonding Link Box - Remove
	SYMBOLOGY		Planned Disconnect Box - New/Updated
Energy VV Oueensla			Planned Disconnect Box - Remove
Queensia	nd LEGEND		Planned Distribution Pad Substation – New/Updated
Cross	Bonding Link Box - Critical		Planned Distribution Pad Substation - Remove
· ·	nnect Box - Critical		Planned Distribution Ground Substation - New/Updated
	Main Unit		Planned Distribution Ground Substation - Remove
	pution Pad Substation	Ē,	Planned Ring Main Unit – New/Updated
÷ Earth			Planned Ring Main Unit - Remove
🛉 Remo	te Earth	÷	Planned Earth – New/Updated
-	Marker	L L	Planned Earth - Remove
	nole	M	Planned Cable Marker – New/Updated
Manho	ble	M	Planned Cable Marker - Remove
Comn	nercial Industrial Pillar	(Planned Remote Earth – New/Updated
Distril	oution Cabinet	Ţ	Planned Remote Earth - Remove
Link P	llar	M	Planned Underground Warning Post – New/Updated
Servic	e Pillar	M	Planned Underground Warning Post - Remove
🔀 Feede	r Pillar		Planned Pilot Cubicle – New/Updated
O Pole			Planned Pilot Cubicle – Remove
😧 Street	tlight Column	(I)	Planned Fibre Patch Panel – New/Updated
Comm	nunication Junction Pillar		Planned Fibre Patch Panel – Remove
💿 Comn	nunication Pit		Planned Commercial Industrial Pillar – New/Updated
Fibre	Patch Panel	GI	Planned Commercial Industrial Pillar – Remove
ilot (Cubicle		Planned Distribution Cabinet – New/Updated
🕳 🔹 Under	ground Asset 33kV and above		Planned Distribution Cabinet – Remove
	ground Asset below 33kV		Planned Link Pillar – New/Updated
	ground Conduit or without cable		Planned Link Pillar – Remove
Pit			Planned Service Pillar – New/Updated
Comm	nunication Boundary		Planned Service Pillar – Remove
Reser	ve (RE)	0	Planned Pole – New/Updated
Water	Resource (WR)	Ō	Planned Pole – Remove
Cadas	stral Parcels	\otimes	Planned Manhole – New/Updated
		\odot	Planned Manhole – Remove
Planne	ed Jointing Pit – New/Updated	\odot	Planned Streetlight Column – New/Updated
Planne	ed Jointing Pit - Remove	۲	Planned Streetlight Column – Remove
Planne	ed Communication Boundary – New/Updated	\odot	Planned Handhole – New/Updated
Planne	ed Communication Boundary - Remove		Planned Handhole – Remove
= Planne	ed Tunnel/Trench/Bore - New/Updated		Planned Communication Junction Pillar – New/Updated
≡= Planne	ed Tunnel/Trench/Bore - Remove		Planned Communication Junction Pillar – Remove



Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work. A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.



WARNING

Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information.

As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D.

Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it

Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy.

Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work. A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.

OPENING ELECTRONIC MAP ATTACHMENTS -

Telstra Cable Plans are generated automatically in either PDF or DWF file types dependant on the site address and the size of area selected. You may need to download and install free viewing software from the internet e.g.

IT'S HOW WE CONNECT

PDF Map Files (max size A3)

Adobe Acrobat Reader (http://get.adobe.com/reader/),

DWF Map Files (all sizes over A3)

Autodesk A360 (https://360.autodesk.com/viewer) or

Autodesk Design Review (<u>http://usa.autodesk.com/design-review/</u>) for DWF files. (Windows)



Telstra DBYD map related enquiries

email - Telstra.Plans@team.telstra.com 1800 653 935 (AEST Business Hours only)



REPORT ANY DAMAGE TO THE TELSTRA NETWORK IMMEDIATELY

Report online - <u>https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra-equipment</u>

Ph: **13 22 03**

If you receive a message asking for a phone or account number say: "I don't have one" then say "Report Damage" then press 1 to speak to an operator.



Telstra New Connections / Disconnections 13 22 00




Telstra asset relocation enquiries: 1800 810 443 (AEST business hours only). <u>NetworkIntegrity@team.telstra.com</u> https://www.telstra.com.au/consumer-advice/digging-construction

Certified Locating Organisation (CLO) https://dbydlocator.com/certified-locating-organisation/

DBYDCertification Please refer to attached Accredited Plant Locator.pdf



Telstra Smart Communities Information for new developments (developers, builders, homeowners) https://www.telstra.com.au/smart-community



WARNING: Telstra plans and location information conform to Quality Level 'D' of the Australian Standard AS 5488 -Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy shown on the plans. FURTHER ON SITE INVESTIGATION IS REQUIRED TO VALIDATE THE EXACT LOCATION OF TELSTRA PLANT PRIOR TO COMMENCING CONSTRUCTION WORK. A plant location service is an essential part of the process to validate the exact location of Telstra assets and to ensure the assets are protected during construction works. The exact position of Telstra assets can only be validated by physically exposing them. Telstra will seek compensation for damages caused to its property and losses caused to Telstra and its customers.





APA Group PO Box 6014 Halifax Street South Australia 5000

STOP For your immediate information THERE IS A CRITICAL GAS PIPELINE AND/OR ASSOCIATED INFRASTRUCTURE in the area of your works.

17/11/2022

Company: Paragon Consulting Engineers Pty Ltd Lauren Leotta 95 Sydney Street Mackay QLD 4740 Lauren.leotta@paragonce.com

Dear Lauren Leotta

Sequence Number:	218341096	
Worksite Address:	20 Withers Street	
	Kawana	
	QLD	4701

Thank you for your Dial Before You Dig enquiry regarding the location of Gas Assets. We can confirm that the APA Group has **Critical Gas Assets** in the vicinity of the above location.

You are hereby notified that **before you commence any works** you are required to complete the attached '**Work In The Vicinity Of Critical Gas Assets**' request form and forward this to APA as soon as practicable.

As laid out in the **Duty of Care** requirements supplied, any activity in the vicinity of Critical Gas Assets operated by APA requires an Authority to Work Permit and potentially attendance on site by an APA representative during any work. Please ensure you read and comply with all the relevant requirements. Should you have any questions with regards to the attached information please contact our Qld Planning & Scheduling Officer - (07) 3215 6644.

Caution - Damage to gas assets could result in possible explosion and fire with the risk of personal injury. For Gas Emergencies please call 1800 GAS LEAK (1800 427 532)


Please find enclosed the following information:-

- APA's Duty of Care, If you are unclear of your obligations under these requirements please contact the APA Representative listed above immediately
- An overview map with your requested area highlighted to assist in locating APA's Gas Assets
- A map(s) showing APA's Gas Assets in the requested area, this information is valid for 30 days from the date of this response, please check this represents the area you requested, if it does not, please contact the APA Representative listed above immediately
- A 'Work In The Vicinity Of Critical Gas Assets' request form, please complete and forward to APA as soon as practicable, via <u>PermitsQld@apa.com.au</u>, or the address above. A minimum of **5 business** days advance notification is required to process Authority To Work Request applications

The outcome of this request may be that a qualified APA Group Representative will be required on site when you undertake your proposed works, if this is the case, this will need to be arranged dependent on their availability. Whilst we will aim to facilitate this within 5 business days from a decision, **this cannot be guaranteed**.








APA Group does not guarantee the accuracy or completeness of the map and does not make any warranty about the data. APA Group is not under any liability to the user for any loss or damage (including consequential loss or damage) which the user may suffer resulting from the use of this map.

Mapping information is provided as AS5488-2013 Quality Level D

APA Group • PO Box 6014 Halifax Street SA 5000 • Email: DBYDNetworksAPA@apa.com.au • Template: QLD Critical Jan 2022 Page 4 of 11 • 17/11/2022







TRANSMISSION PRESSURES P6,P7,P9-P12 Medium Density PE CP RECTIFIER UNIT PRIORITY MAIN (BEHIND PIPE) P2,P4,P8 High Density PE CP TEST POINT/ ANODE D / 4 S ST or S# Steel syphon LPG (COLOUR BY PRESSURE) \$6# (e.g. \$61) Steel Class 600 TRACE WIRE POINT • \$ ABANDONED \$3# (e.g. \$33) Steel Class 300 PIPELINE MARKER IDLE W2 or GAL Wrought Galv. Iron NOT TIED IN N.T.I. 🖸 W3 or PGAL Poly Coat Wrought Galv. Iron COUPLING & END CAP SLEEVE or CASING / SPLIT (BEHIND PIPE) / / DEPTH OF COVER С Pipe diameter in millimetres is shown before pipe UNKNOWN code e.g. 40P6 = 40mm nominal diameter EASEMENT/ JURISDICTION -----EXAMPLES 40P6 in 80C2 40mm High Pressure Medium Density Polyethylene in an 80mm Cast Iron Casing 6358 63mm Medium Pressure Steel This map is created in colour and shall be printed in colour Line / Polygon Request 5 0.009km AN Scale 1:700 APA Group does not guarantee the accuracy or completeness of the map and does not make any warranty about the data. APA Group is not under any liability to the user for any loss or damage (including consequential loss or damage) which the user may uffer resulting from the use of this map

Mapping information is provided as AS5488-2013 Quality Level D APA Group • PO Box 6014 Halifax Street SA 5000 • Email: DBYDNetworksAPA@apa.com.au • Template: QLD Critical Jan 2022 Page 5 of 11 • 17/11/2022








Page 6 of 11 • 17/11/2022








Page 7 of 11 • 17/11/2022








PIPE AND BOUNDARIES		PIPE CODE / MATERIALS		OBJECTS or TERMS		Мар Кеу
SERVICE (COLOUR BY PRESSURE)		C2, CI	Cast Iron	VALVES		
OW PRESSURES		CU	Copper	BURIED VALVES		
MEDIUM PRESSURES		N2, NY, NY11	Nylon	GATE / REGULATORS	R 8	
HIGH PRESSURES		P# (e.g. P6)	Polyethylene (PE)	GAS SUPPLIED = YES	*	1 3
RANSMISSION PRESSURES		P6,P7,P9-P12	Medium Density PE	CP RECTIFIER UNIT		2 4
PRIORITY MAIN (BEHIND PIPE)		P2,P4,P8	High Density PE	CP TEST POINT/ ANODE	1 4	
PROPOSED (COLOUR BY PRESSURE)		ST or S#	Steel	SYPHON	S	
LPG (COLOUR BY PRESSURE)	_	S6# (e.g. S61)	Steel Class 600	TRACE WIRE POINT		
ABANDONED		\$3# (e.g. \$33)	Steel Class 300	PIPELINE MARKER	ф-	
DLE		W2 or GAL	Wrought Galv. Iron	NOT TIED IN	n.t.i. 🕑	
SLEEVE		W3 or PGAL	Poly Coat Wrought Galv. Iron	COUPLING & END CAP	or I	
CASING / SPLIT (BEHIND PIPE)	/	Pine diameteri	n millimetres is shown before pipe	DEPTH OF COVER	С	
UNKNOWN		code e.g. 40P6 = 40mm nominal diameter				
EASEMENT/ JURISDICTION						
EXAMPLES 40P6 in 80	C2 40mr	n High Pressure Mee	dium Density Polyethylene in an 80mm (Cast Iron Casing		
6358	63mr	n Medium Pressure	Steel			
Line / Polygon Requ	est		This map is created in c	olour and shall be printed i	n colour	
Scale 1:700				0 0.009km		


 Mapping information is provided as A\$5488-2013 Quality Level D

 APA Group • PO Box 6014 Halifax Street SA 5000 • Email: DBYDNetworksAPA@apa.com.au • Template: QLD Critical Jan 2022

 Page 8 of 11 • 17/11/2022

Appendix D – Existing Services Drawings











SP267888/101



WARNING: IMAGE NOT AT ORIGINAL SCALE

Copyright protects this publication. Reproduction by whatever means is prohibited without prior written permission of the Chief Executive Officer, Rockhampton Regional Council. Rockhampton Regional Council will not be held liable under any circumstances in connection with or arising out of the use of this data nor does it warrant that the data is error free. Any queries should be directed to the Customer Service Centre, Rockhampton Regional Council or telephone 1300 22 55 77. The Digital Cadastral DataBase is current as at 2019. The State Government of Queensland (Department of Natural Resources and Mines) 2019. All other data \circ Rockhampton Regional Council 2019.



Appendix E – Detailed Site Survey

