


ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with **Development Permit No.:** D/84-2019 Dated: 04 November 2019


SITE INFORMATION



SHERRIN GROUP 155-157 MALONEY ST. KAWANA, QLD 4701 DWG N° 4221-SK01-6 by IM DATE 08/10/2019


SITE PLAN

COPYRIGHT © SPACEFRAME BUILDINGS PTY LTD



╘╬


111



EAVES 7450 <u>FIRST FLOO</u> 3700 GROUND FL	OOR	NORTH ELEVATION 1 : 100 @ A1			







MALONEY STREET

ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with **Development Permit No.: D/84-2019** Dated: 04 November 2019

GENERAL NOTES

ALL DOWNPIPES TO CONNECT TO 150 DIA. UPVC PIPE TO STORMWATER DRAIN. U.N.O.

ALL PIPES FALL @ 1:100 U.N.O.

ALL UPVC STORMWATER PIPES TO COMPLY WITH A.S. 1254 AND INSTALLATION TO A.S. 3500.

BEDDING: USE APPROVED SAND WITH MIN. 30MM TOP COVER TO ALL PIPES. GRATES TO BE HOT DIP GALVANISED.

ALL STORMWATER CONNECTIONS ARE TO BE PROVIDED BY THE DRAINER.

ALL BOX GUTTERS TO HAVE OVERFLOWS TO THE EXTERNAL OF THE BUILDING.

LEGEND

SWSW	EXISTING STORMWATER DRAINAGE
/ /	AGRICULTURAL DRAINAGE
	PROPOSED STORMWATER DRAINAGE
▲ твм	TEMPORARY BENCHMARK (A.H.D.)
PSM	PERMANENT SURVEY MARK (A.H.D.)
	STORMWATER PIT (450 x 450)
DP FFL RCP RL SL SWIC IL DS US WB OCC	DOWNPIPE FINISHED FLOOR LEVEL REINFORCED CONCRETE PIPE REDUCED LEVEL SURFACE LEVEL STORMWATER INSPECTION CHAMBER INVERT LEVEL DOWNSTREAM UPSTREAM WATER BASIN OUTLET CONTROL CHAMBER
	LANDSCAPING

BIO-RETENTION

	BIO-RETENTION	(TREATMENT)			
	BIO-RETENTION	(FILTER)			
TREATMENT	142m² x 300mm	$DEEP = 43m^3$			
FILTER	62m² x 500mm [62m ² x 500mm DEEP = 31m ³			
SITE INFOF	RMATION				
L.36-38 on S	L.36-38 on SP263881 5,855 m ²				
FLOOR AREA		805 m ²			
LANDSCAPIN	IG 6%	346 m ²			
space					
1 11.					

DESIGN + CONSTRUCT SOLUTIONS



STORMWATER PLAN SHERRIN GROUP 155-157 MALONEY ST. KAWANA, QLD 4701

DWG N° 4221-61-2 by IM DATE 08/10/2019

STORMWATER MANAGEMENT PLAN

155 & 157 MALONEY STREET, KAWANA

9 October 2019



ACN 105 078 377 5/541 Old Cleveland Rd, CAMP HILL QLD 4152 Ph (07) 3398 4992 www.stormw.com.au **ROCKHAMPTON REGIONAL COUNCIL**

APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with

Development Permit No.: D/84-2019

Dated: 04 November 2019

Job No: J7059 v1.0

Job Name: 155 & 157 Maloney Street, Kawana

Report Name	Date	Report No.
Stormwater Management Plan	9 October 2019	J7059 v1.0

Project Engineer:	Jack Hu BE Civil, MIEAust E Jack@stormw.com.au
Reviewed By:	Darren Rogers BE Civil (Hons), MIE Aust, RPEQ Director
	E <u>darren@stormw.com.au</u>



Table of Contents

1.0	Int	roduction	.1
2.0	Sit	e Conditions	.2
	2.1	Existing Site	.2
	2.2	Developed Site	.2
3.0	La	wful Point of Discharge / Stormwater Quantity Management	.3
4.0	W	ater Quality	.5
	4.1	State Planning Policy (July 2017)	.5
	4.2	Water Quality – Construction Phase	.6
	4.3	Water Quality – Operational Phase	.7
5.0	W	ater Quality Modelling	.8
	5.1	Source Nodes	.8
	5.2	Treatment Node – Bio-Retention Basin1	10
	5.3	Treatment Node – Trash Baskets1	1
	5.4	MUSIC Analysis1	12
6.0	Со	nclusions1	13
List	of Ap	pendicies1	14



1.0 INTRODUCTION

Storm Water Consulting Pty Ltd was commissioned by Peter Raspotnik (Spaceframe Buildings Pty Ltd) to prepare a Stormwater Management Plan for the development on 155 & 157 Maloney Street, Kawana .

This report has been prepared to address the issues of lawful point of discharge and stormwater quality treatment for the proposed industrial development. A bio-retention basin is proposed to meet the water quality objectives and the modelling procedures, analysis and results are presented in this report.



2.0 SITE CONDITIONS

2.1 Existing Site

The site is situated in an industrial precinct of Kawana. The site is bounded by Maloney Street to the south, Splitters Creek to the north and by industrial sites in all other directions. A locality plan is presented below. Photographs of the existing site condition are presented in Appendix B.



Figure 2.1 – Locality Plan (Bing Maps Overlay)

2.2 Developed Site

Development plans are presented in Appendix A.



3.0 LAWFUL POINT OF DISCHARGE / STORMWATER QUANTITY MANAGEMENT

The industrial subdivision was completed in 2013/2014 following the approved Op Works application (reference 136-2013) and approved development application (reference 377-2012). The industrial subdivision provided drainage pits toward the rear of each lot for the drainage of future hardstand areas. A copy of the approved plans showing the drainage pits are presented in Appendix C. An extract of the pit locations is presented in Figure 3.1 below.




Figure 3.1 – Extract of Approved Op Works Drainage Plan

A 300 mm diameter pipe extends from the field inlet pit at 2/5 shown above, toward Splitters Creek. The field inlet and 300 mm pipe are nominated as the lawful point of discharge for the development.

A catchment plan of Splitters Creek is presented in Figure 3.2 on the following page. The location of the site is also shown on this figure. The site is located within approximately the bottom third of the Splitters Creek catchment. The background notes of the Queensland Urban Drainage Manual (QUDM 2016) presents recommendations for the management of site runoff based on the various site locations along a creek. QUDM 2016 states that stormwater detention would not be considered appropriate for sites located within the bottom third of a catchment, as delaying runoff from the site could increase the flood risk to downstream properties, due to the potential for the overlapping of the hydrographs from the site and from the creek.

As there are no flood-prone properties downstream of the site (in addition to the discussion regarding the location of the site within the bottom third of the Splitters Creek catchment), stormwater detention is not recommended for the proposed development.






Figure 3.2 – Catchment Plan of Splitters Creek



4.0 WATER QUALITY

4.1 State Planning Policy (July 2017)

The State Planning Policy (SPP) sets out the requirements for water quality in the interest of the State. Developments which trigger the requirements summarised in Table 4.1 below would need to meet water quality objectives listed in Table B, Appendix 3 of the SPP.

State Planning Policy Criteria	Application to Development
 (1) A material change of use for urban purposes that involves a land area greater than 2500 square metres that: (a) will result in an impervious area greater than 25 per cent of the net developable area, or 	Criterion is applicable to development.
(b) will result in six or more dwellings, or	Criterion is NOT applicable to development.
(2) Reconfiguring a lot for urban purposes that involves a land area greater than 2500 square metres and will result in six or more lots, or	Criterion is NOT applicable to development.
(3) Operational works for urban purposes that involve disturbing more than 2500 square metres of land.	Criterion is NOT applicable to development.

The proposed development triggers the SPP, hence water quality objectives indicated in Table B, Appendix 3 of the SPP would need to be met.



4.2 Water Quality – Construction Phase

During the construction phase of a development, the pollutants listed in Table 4.2 are typically generated. Measures are required during the construction phase to manage each of these pollutants. These measures may include but are not limited to; bins and mini-skips, erosion and sediment control measures (discussed below), wash down and spill containment areas, bunds, spill clean-up kits, street sweeping and chemical agents.

Pollutant Source	
Litter	Paper, construction packaging, food packaging, cement bags, off- cuts
Sediment	Unprotected exposed soils and stockpiles during earthworks and building operations
Hydrocarbons	Fuel and oil spills leaks from construction equipment
Toxic materials	Cement slurry, asphalt primer, solvents, cleaning agents, wash waters (e.g. from tile works)
pH altering substances	Acid sulphate soils, cement slurry and wash waters

4.2.1 Erosion and Sediment Control

During the construction phase of the development, an Erosion and Sediment Control Program (E&SCP) is required to minimise water quality impacts. Such an E&SCP should provide complete and detailed instructions on the following procedures;

- Before construction activities begin, sediment fences should be constructed on the downstream site boundaries and at the base of all proposed soil stockpiles;
- Areas for plant and construction material storage should be designated. Runoff from these areas should be directed to small holding ponds in case of spillages;
- Catch drains at the downstream boundary of construction activities should also be created to ensure that any sediment-laden runoff is contained and directed into a sediment basin and not permitted to flow unmitigated to downstream areas;
- Sediment basins should be constructed at appropriate locations to collect sediment at the downstream ends of the catch drains that convey runoff from exposed areas;
- Site personnel should be educated on the sediment and control measures implemented on site; and
- Following rainfall events greater than 20mm, inspection of silt fences, sedimentation basins and other erosion control measures should be carried out. Where necessary, collected material should be removed and damaged equipment should be replaced immediately.



4.3 Water Quality – Operational Phase

During the operational (post-construction) phase of the proposed development, the following pollutants are typically generated;

- Sediment,
 Heavy Metals,
- Litter,
 Thermal Pollution,
- Faecal coliforms,
 Nutrients (N & P) and
- Hydrocarbons,
 Surfactants.

4.3.1 Water Quality Objectives

Key pollutant levels will be reduced to the levels indicated in Table B, Appendix 3 of the State Planning Policy. The Water Quality Objectives are summarised in Table 4.3 below.

Table 4.3 – Water Quality Objectives for Central Queensland (South)

Parameter	Load-based Reduction
Total Suspended Solids (TSS)	85%
Total Phosphorus (TP)	60%
Total Nitrogen (TN)	45%
Gross Pollutants > 5mm	90%

Note that the percentage reduction refers to a comparison between the un-mitigated developed site and the mitigated developed site.



5.0 WATER QUALITY MODELLING

A stormwater treatment train is proposed to meet the WQOs stated in Section 4.3.1. The Stormwater Quality Improvement Devices (SQIDs) for the treatment train were selected based on site constraints, opportunities and practicality.

A bio-retention basin is proposed toward the rear of the development. The roof runoff would be directed toward the bio-retention basin. The runoff from the balance ground areas would be captured by field inlets and filtered using trash baskets, before being directed toward the bio-retention basin.

5.1 Source Nodes

A MUSIC sub-catchment plan is presented in Figure 5.1 below. The sub-catchment types, areas and impervious proportions are summarised in Table 5.1 below.




Figure 5.1 – MUSIC Sub-Catchment Plan

Table 5.1 – Source N	ode Fractions I	mpervious
----------------------	-----------------	-----------

Source Node Area		Туре	Fraction Impervious	
Building Roof	0.105 ha	Industrial Roof	100%	
Concrete Hardstand	0.126 ha	Industrial Road	85%	
Bitumen Hardstand	0.355 ha	Industrial Road	90%	



Rainfall-runoff parameters were assigned to the source nodes in accordance with the Water by Design MUSIC Modelling Guidelines Version 1.0 - 2010 Industrial Use of the site. These parameters are summarised in Table 5.2 below.

I	Parameter	Industrial
Impervious Area Properties Rainfall threshold (mm/day)		1
	Soil storage capacity (mm)	18
	Initial storage (% of capacity)	10
Pervious Area Properties	Field Capacity (mm)	80
	Infiltration Capacity Coefficient – a	243
	Infiltration Capacity Exponent – b	0.6
	Initial depth (mm)	50
Crowndwater Dreportion	Daily recharge rate (%)	0
Groundwater Properties	Daily base flow rate (%)	31
	Daily deep seepage rate (%)	0

Table 5.2 – Rainfall – Runoff Parameters

Pollutant export parameters were assigned according to the Water by Design MUSIC Modelling Guidelines Version 1.0 - 2010. The pollutant export parameters adopted in the MUSIC model are summarised in Table 5.3 below.

Sourc		Log ₁₀ TSS (mg/L) Base Storm flow flow		Log₁ (mį	ιο TP g/L)	Log ₁₀ TN (mg/L)	
Sourc	e			Base flow	Storm flow	Base flow	Storm flow
Deef	Mean	NA	1.30	NA	-0.89	NA	0.25
Roof	Std Dev	NA	0.44	NA	0.36	NA	0.32
Dead	Mean	0.78	2.43	-1.11	-0.30	1.40	0.25
KUAU	Road Std Dev		0.44	0.48	0.36	0.20	0.32

Table 5.3 – Pollutant Export Parameters (Industrial)



5.2 Treatment Node – Bio-Retention Basin

A bio-retention basin is proposed and has been modelled in MUSIC with the parameters listed in Table 5.4 below.

Parameter	Bio-Retention Basin
Extended Detention Depth	0.3 m
Surface Area	62 m ²
Seepage Loss	0 mm/hr
Filter Area	62 m ²
Filter Depth	0.5 m
Filter median Particle Diameter	0.45 mm
Drainage	Slotted PVC Pipes
Saturated Hydraulic Conductivity	200 mm/hr
Overflow Weir Width	3.6 m

Table 5.4 – Bio-Retention MUSIC Parameters

The location of the proposed bio-retention basin is shown in Appendix A. The underdrain and overflow pit will be connected to the existing field inlet pit at the rear of the site (i.e. lawful point of discharge). Inlet drains into the bio-retention basin will require adequate scour and erosion protection, which will be configured during detailed design stage.

5.2.1 Maintenance

The recommended maintenance checklist is presented in Appendix D. The maintenance schedule can be summarised as follows:

- Monthly cleaning of litter from surface of the bio-retention basin;
- Monthly cleaning of overflow pit and immediate cleaning if a blockage is observed;
- Implementation of erosion and sedimentation controls in accordance with industry standards;
- Regular cleaning of pavements to reduce contaminants entering the bio-retention basin.



5.3 Treatment Node – Trash Baskets

Trash baskets are proposed in all field inlets within the development. Trash baskets are effective for the removal of gross pollutants and sediments and prolongs the life of the bio-retention basin. Seven (7) trash baskets were modelled in MUSIC with the parameters listed in Table 5.5 and 5.6 below.

Table 5.5 – MUSIC Input Parameters for Trash Basket

Inlet Properties	GPT
Low Flow Bypass (m ³ /s)	0
High Flow Bypass (m ³ /s)	7 x 0.02 m³/s

Table 5.6 – MUSIC Transfer Functions for Trash Basket

Transfer Functions	In	Out
Total Suspended Colids (TSS)	0	0
Total Suspended Solids (TSS)	100	40
Total Nitragan (TNI)	0	0
Total Nitrogen (TN)	50	50
Total Phaenharus (TD)	0	0
Total Phosphorus (TP)	10	10
Gross Pollutants	0	0
	14.8	0

The proposed location of the field inlet pits is presented in Appendix A. Trash baskets are proposed in all field inlet pits.

5.3.1 Maintenance

Monthly cleaning of all field inlets is required and immediate cleaning is required if blockage is observed. Cleaning is also recommended after significant rainfall events.



5.4 MUSIC Analysis

The quality of stormwater runoff and the impact of the proposed SQIDs were analysed using MUSIC version 6.2 in accordance with the water quality objectives from Table B, Appendix 3 of the State Planning Policy.

The MUSIC model was based on the 2000 to 2010 rainfall series for Rockhampton (39083) with 6-minute time steps. The MUSIC model schematic is presented in Figure 5.2 below. The MUSIC modelling results are presented in Table 5.7 below.




Figure 5.2 – MUSIC Model Schematic

Indicator	Annual Loads (kg/yr)		Reduction		
	Without SQIDs	With SQIDs	Actual	Target	
TSS	1190	109	91%	85%	
ТР	1.98	0.53	73%	60%	
TN	7.71	4.27	45%	45%	
GP	83.8	0	100%	90%	

Table 5.7 – MUSIC Model Results

The results above indicate that the required water quality objectives are met for the development.



6.0 CONCLUSIONS

This Stormwater Management Plan was prepared to address the issues of lawful point of discharge and stormwater quality treatment for the proposed industrial development at 155 & 157 Maloney Street, Kawana.

A 300 mm diameter pipe extends from the field inlet pit at 2/5 shown above, toward Splitters Creek. The field inlet and 300 mm pipe are nominated as the lawful point of discharge for the development.

The site is located within approximately the bottom third of the Splitters Creek catchment. The background notes of the Queensland Urban Drainage Manual (QUDM 2016) presents recommendations for the management of site runoff based on the various site locations along a creek. QUDM 2016 states that stormwater detention would not be considered appropriate for sites located within the bottom third of a catchment, as delaying runoff from the site could increase the flood risk to downstream properties, due to the potential for the overlapping of the hydrographs from the site and from the creek. As there are no flood-prone properties downstream of the site (in addition to the discussion regarding the location of the site within the bottom third of the Splitters Creek catchment), stormwater detention is not recommended for the proposed development.

A bio-retention basin is proposed toward the rear of the development. The roof runoff would be directed toward the bio-retention basin. The runoff from the balance ground areas would be captured by field inlets and filtered using trash baskets, before being directed toward the bio-retention basin. MUSIC model results show that the water quality objectives of the State Planning Policy are achieved through the proposed treatment train.

Darren Rogers BE Civil (Hons), MIE Aust, RPEQ 5016 Director



LIST OF APPENDICIES

APPENDIX A – Development Plans

APPENDIX B – Photographs

APPENDIX C – Approved Subdivision Plans

APPENDIX D – Stormwater Quality Maintenance Checklist

APPENDIX A

Development Plans



SITE INFORMATION

L.36-38 on SP263881 5,855 m² FLOOR AREA 805 m² GROUND FLOOR 109 m² Office 130 m² Washbay 565 m² Workshop TOTAL CARPARKS 13 LANDSCAPING 6% 346 m² space frame


DESIGN + CONSTRUCT SOLUTIONS



SITE PLAN

SHERRIN GROUP 155-157 MALONEY ST. KAWANA, QLD 4701 DWG N° 4221-SK01-6 by IM DATE 08/10/2019





MALONEY STREET

GENERAL NOTES

ALL DOWNPIPES TO CONNECT TO 150 DIA. UPVC PIPE TO STORMWATER DRAIN. U.N.O.

ALL PIPES FALL @ 1:100 U.N.O.

ALL UPVC STORMWATER PIPES TO COMPLY WITH A.S. 1254 AND INSTALLATION TO A.S. 3500.

BEDDING: USE APPROVED SAND WITH MIN. 30MM TOP COVER TO ALL PIPES. GRATES TO BE HOT DIP GALVANISED.

ALL STORMWATER CONNECTIONS ARE TO BE PROVIDED BY THE DRAINER.

ALL BOX GUTTERS TO HAVE OVERFLOWS TO THE EXTERNAL OF THE BUILDING.

LEGEND

SWSW	- EXISTING STORMWATER DRAINAGE
/ /	· AGRICULTURAL DRAINAGE
	PROPOSED STORMWATER DRAINAGE
∕∙ твм	TEMPORARY BENCHMARK (A.H.D.)
PSM	PERMANENT SURVEY MARK (A.H.D.)
	STORMWATER PIT (450 x 450)
DP FFL RCP RL SL SWIC IL DS US WB OCC	DOWNPIPE FINISHED FLOOR LEVEL REINFORCED CONCRETE PIPE REDUCED LEVEL SURFACE LEVEL STORMWATER INSPECTION CHAMBER INVERT LEVEL DOWNSTREAM UPSTREAM WATER BASIN OUTLET CONTROL CHAMBER
	LANDSCAPING

BIO-RETENTION

	BIO-RETENTIO	DN (TREATMENT)
	BIO-RETENTIO	DN (FILTER)
TREATMENT	142m² x 300r	nm DEEP = 43m ³
FILTER	62m ² x 500m	m DEEP = 31m³
SITE INFOF	RMATION	
L.36-38 on S	P263881	5,855 m²
FLOOR AREA		805 m ²
LANDSCAPIN	IG 6%	346 m ²
Sp	Da	ce
fr	an	ne

DESIGN + CONSTRUCT SOLUTIONS



STORMWATER PLAN SHERRIN GROUP 155-157 MALONEY ST. KAWANA, QLD 4701 DWG N° 4221-61-2 by IM DATE 08/10/2019 **APPENDIX B**

Photographs



Photograph 1 – Existing site condition



Photograph 2 – Splitters Creek at rear of site



Photograph 3 – Existing field inlet pits at rear of site





Photograph 4 – Outlet from existing field inlets to Splitters Creek

J7059 v1.0


APPENDIX C

Approved Subdivision Plans





13 3:04:37



5/04/13 4:43:11 PM

_		
	DO NOT SCALE OFF DRAWING	
	DIMENSIONS METERS UNO	
		F
		-
		F
		L
		Γ
		F 1
		200
	SCHLENCKER SURVEYING A.B.N. 37 147 098 815	-
		-
		L 1
	CONSULTANTS 181 East St.,	LI
	ROCKHAMPTON	
	Ph. (07) 49 271744	
	LEVEL DATUM: AHD PSM45254	-
	MERIDIAN MGA ZONE 56 PSM90349	-
	E244828.276 N7416865.593	H I
		150
	PROPERTY DESCRIPTION:	_
	LOT 1 RP601930; 232	
	ALEXANDRA STREET D/377-2012	
	COUNCIL APPROVAL	
ļ	AMENDMENTS ssue date subject lauthorised	-
Ŀ	2 21/03/13 FIRST ISSUE NG	
	2 05/04/13 POST DESIGN REVIEW NG	-
		-08
		180
	XREF FILES	180
	XREF FILES DRAWING NO. TITLE.	1.1
		1 180
		190
	DRAWING NO. TITLE.	160
		00
	DRAWING NO. TITLE.	100
	DRAWING NO. TITLE. DRAWN DATE DESIGN DATE	198
	DRAWN DATE DESIGN DATE NGGA	198
	DRAWING NO. TITLE. DRAWN DATE DESIGN DATE OCIVIL engineers	190
	DRAWN DATE DESIGN DATE NGGA	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA C N G GARDNER & ASSOCIATES N. G. GARDNER & ASSOCIATES	
	DRAWN DATE DESIGN DATE DESIGN DATE OCIVIL ENGINEERS OCIVIL ENGINEERS OCIVIL ENGINEERS	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE OCIVIL engineers (C) N 6 GARDNER & ASSOCIATES CONSUL TING ENGINEERS ACN 063 548 390 PH: 4927 3220	
	DRAWN DATE DRAWN DATE DESIGN DATE OCIVIL engineers C N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390	58
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVII engineers C N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE OCIVIL engineers (C) N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON ATHERED FOR EASE DESIGN DATE DATE OCIVIL ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON DESIGN DATE DATE OCIVIL ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON DESIGN DATE DATE OCIVIL ENGINEERS DATE OCIVIL ENGINEERS DATE DATE OCIVIL ENGINEERS DATE OCIVIL ENGINEERS DATE DATE OCIVIL ENGINEERS DATE DATE OCIVIL ENGINEERS DATE DATE OCIVIL ENGINEERS DATE DATE DATE DATE DATE OCIVIL ENGINEERS DATE DAT	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE OCIVIL engineers C N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ingga.com.au ROCKHAMPTON AUTHOREROPRIESE EFPEQ 2393 MATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers (C) N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTROREROFOR ISSA TEPEQ 2393 ANT 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE DESIGN DATE NGGAR CIVIL engineers CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTHOREBOR BERE EPEQ 2393 BATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DEVELOPMENT	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTHOREDOF ISSE IPEQ 2393 MAIT 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROADWORKS & DRAINAGE	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers C N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTHOREROFWEISE EFPEQ 2393 BATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DEVELOPMENT ROADWORKS & DRAINAGE DRAINAGE LONGITUDINAL	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTHOREDOF ISSE IPEQ 2393 MAIT 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROADWORKS & DRAINAGE	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers CIVIL engineers CIVIL engineers CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTIOREROF ISSUE TEEQ 2393 MATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROADWORKS & DRAINAGE DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2 HITTE	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers © N 6 GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ingga.com.au ROCKHAMPTON AUTHORETORE ISSE TPEQ 2393 BATT 10/102/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROADWORKS & DRAINAGE DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE OCIVIL engineers C N 6 GARDNER & ASSOCIATES ON 6 GARDNER & ASSOCIATES ON 6 GARDNER & ASSOCIATES ONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ingga.com.au ROCKHAMPTON AUTHOREROTOR IBSE TEPEO 2393 MATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROAD WORKS & DRAINAGE DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2 HERNO G1302-4-R05.DWG COM NO G1302/4 SCALE 9 11000 HORZ 20 AT A D CIZE	
	DRAWN DATE DRAWN DATE DESIGN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers C N 6 GARDNER & ASSOCIATES N. G. GARDNER & ASSOCIATES ONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ingea.com.au ROCKHAMPTON AUTIWERDOPRISE EPEQ 2393 DATE 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DEVELOPMENT ROADWORKS & DRAINAGE DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2 FILE NO G1302-4-R05.DWG ROB NO G1302/4 SCALE 0 1:000 HORZ. 20 AT A3 SIZE 0 1:200 VERT. 4	
	DRAWING NO. TITLE DRAWIN DATE DESIGN DATE DESIGN DATE NGGA CIVIL engineers C N G GARDNER & ASSOCIATES OCIVIL engineers C N G GARDNER & ASSOCIATES CONSULTING ENGINEERS ACN 063 548 390 PH: 4927 3220 EMAIL:mail@ngga.com.au ROCKHAMPTON AUTIOREROFE ISAK EPEQ 2393 MAT 10/02/2013 HUNTLY HEAVY EQUIPMENT HIRE ALEXANDRA STREET INDUSTRIAL LOT DE VELOPMENT ROADWORKS & DRAINAGE DRAINAGE LONGITUDINAL SECTIONS SHEET 2 OF 2 HEL NO G1302-4-R05.DWG IOS NO G1302/4 SCALE Q 11000 HORZ. 20 AT A3 SIZE	

APPENDIX D

Stormwater Quality Maintenance Checklist

BIORETENTION BASIN MAINTENANCE CHECKLIST						
Inspection Frequency:	1 to 6 monthly	Date of V	isit:			
Location:						
Description:						
Asset I.D.						
Site Visit by:						
INSPECTION ITEMS:			Y	Ν	Action Required (details)	
Sediment accumulation	on at inflow points?					
Litter within basin?						
Erosion at inlet or othe	er key structures?					
Traffic damage presen	nt?					
Evidence of dumping	(e.g. building waste)?					
Vegetation condition s	atisfactory (density, weeds	etc)?				
Watering of vegetation	n required?					
Replanting required?						
Mowing/slashing requ	ired?					
Clogging of drainage p	points (sediment or debris)?					
Evidence of ponding?						
Damage/vandalism to	structures present?					
Surface clogging visibl	le?					
Drainage system inspe	ected?					
Resetting of system re	equired?					
COMMENTS						